ON

THE CONNEXION

OF

THE PHYSICAL SCIENCES.

BY

MARY SOMERVILLE.

Second Edition.

LONDON:
JOHN MURRAY, ALBEMARLE STREET.
MDCCCXXXV.

IIA Lib.
00846

LONDON:
Printed by A. Spottiswoode,
New-Street-Square.

To the Queen.

MADAM,

IF I HAVE SUCCEEDED IN MY ENDEAVOUR TO MAKE THE LAWS BY WHICH THE MATERIAL WORLD IS GOVERNED MORE FAMILIAR TO MY COUNTRYWOMEN, I SHALL HAVE THE GRATIFICA-TION OF THINKING, THAT THE GRACIOUS PERMIS-SION TO DEDICATE MY BOOK TO YOUR MAJESTY HAS NOT BEEN MISPLACED.

I AM,

WITH THE GREATEST RESPECT,

YOUR MAJESTY'S

OBEDIENT AND HUMBLE SERVANT,

MARY SOMERVILLE.

Royal Hospital, Chelsea,
Jan 1 1834

PREFACE

TO

THE SECOND EDITION.

A SECOND edition of this book being called for, the Author has spared no pains to improve it: copious notes, and diagrams, illustrative of the text, have been subjoined. Many parts have been altered, and much new matter has been added, in order to keep pace with the rapid progress of the physical sciences. Even since the last pages have been printed, discoveries have been published, of sufficient importance to require an additional sheet.

PREFACE.

The progress of modern science, especially within the last five years, has been remarkable for a tendency to simplify the laws of nature, and to unite detached branches by general principles. In some cases identity has been proved where there appeared to be nothing in common, as in the electric and magnetic influences; in others, as that of light and heat, such analogies have been pointed out as to justify the expectation, that they will ultimately be referred to the same agent: and in all there exists such a bond of union, that proficiency cannot be attained in any one without a knowledge of others.

Although well aware that a far more extensive illustration of these views might have been given, the Author hopes that enough has been done to show the connexion of the physical sciences.

CONTENTS.

SECTION IV

SECTION V

SECTION VI

SECTION VII

SECTION VIII

SECTION IX

SECTION X

SECTION XI

SECTION XII

SECTION XIII

SECTION XIV

SECTION XV

SECTION XVI

SECTION XVII

SECTION XVIII

SECTION XIX

SECTION XX

SECTION XXI.

SECTION XXII.

SECTION XXIII.

SECTION XXIV.

SECTION XXV.

SECTION XXVI

SECTION XXVII

SECTION XXVIII

SECTION XXIX

SECTION XXX

SECTION XXXI

SECTION XXXII.

SECTION XXXIII.

SECTION XXXIV.

SECTION XXXV.

SECTION XXXVI.

SECTION XXXVII

ERRATA

Page 92 line 17 for "134,755" read "1,093,810"
line 10 for "21,067" read "20,937"
75 line 11 from bottom, for "eccentricity" read "twice the eccentricity"
206 line 16 for "three" read "seven"
line 7 from bottom, for "third" read "seventh."
236 The experiment mentioned in line 23 was first performed by M. Arago about twenty years ago, and published in the Third Volume of the Memoirs of the Society of Arcueil.

INTRODUCTION.

Science, regarded as the pursuit of truth, must ever afford occupation of consummate interest, and subject of elevated meditation. The contemplation of the works of creation elevates the mind to the admiration of whatever is great and noble, accomplishing the object of all study,—which, in the elegant language of Sir James Mackintosh, "is to inspire the love of truth, of wisdom, of beauty,—especially of goodness, the highest beauty,—and of that supreme and eternal Mind, which contains all truth and wisdom, all beauty and goodness. By the love or delightful contemplation and pursuit of these transcendent aims, for their own sake only, the mind of man is raised from low and perishable objects, and prepared for those high destinies which are appointed for all those who are capable of them."

In tracing the connection of the physical sciences, astronomy affords the most extensive example of their union. In it are combined the sciences of number and quantity, of rest and motion. In it we perceive the operation of a force which is mixed up with every thing that exists in the heavens or on earth; which pervades every atom, rules the motions of animate and inanimate beings, and is as sensible in the descent of a rain drop as in the

falls of Niagara, in the weight of the air as in the periods of the moon Gravitation not only binds satellites to their planet, and planets to the sun, but it connects sun with sun throughout the wide extent of creation, and is the cause of the disturbances, as well as of the order, of nature since every tremour it excites in any one planet is immediately transmitted to the farthest limits of the system, in oscillations, which correspond in their periods with the cause producing them, like sympathetic notes in music, or vibrations from the deep tones of an organ.

The heavens afford the most sublime subject of study which can be derived from science. The magnitude and splendour of the objects, the inconceivable rapidity with which they move, and the enormous distances between them, impress the mind with some notion of the energy that maintains them in their motions, with a durability to which we can see no limit. Equally conspicuous is the goodness of the great First Cause, in having endowed man with faculties, by which he can not only appreciate the magnificence of his works, but trace, with precision, the operation of his laws, use the globe he inhabits as a base wherewith to measure the magnitude and distance of the sun and planets, and make the diameter[1] of the earth's orbit the first step of a scale by which he may ascend to the starry firmament. Such pursuits, while they ennoble the mind, at the same time inculcate humility, by showing that there is a barrier which no energy, mental or physical, can ever enable us to pass: that, however profoundly we may penetrate the depths of space, there still remain innumerable systems, compared with which, those apparently so vast must dwindle into insignificance, or even become

[1] Note 1.

invisible, and that not only man, but the globe he inhabits,—nay, the whole system of which it forms so small a part,—might be annihilated, and its extinction be unperceived in the immensity of creation.

It must be acknowledged, that a complete acquaintance with physical astronomy can be attained by those only, who are well versed in the higher branches of mathematical and mechanical science[1], and that they alone can appreciate the extreme beauty of the results, and of the means by which these results are obtained. It is nevertheless true, that a sufficient skill in analysis[2] to follow the general outline,—to see the mutual dependence of the different parts of the system, and to comprehend by what means some of the most extraordinary conclusions have been arrived at,—is within the reach of many who shrink from the task, appalled by difficulties, which, perhaps, are not more formidable than those incident to the study of the elements of every branch of knowledge. There is a wide distinction between the degree of mathematical acquirement necessary for making discoveries, and that which is requisite for understanding what others have done.

All the knowledge we possess of external objects is founded upon experience, which furnishes facts; and the comparison of these facts establishes relations, from which, induction, that is to say, the belief that like causes will produce like effects, leads to general laws. Thus, experience teaches that bodies fall at the surface of the earth with an accelerated velocity, and with a force proportional to their masses. By comparison, Newton proved that the force which occasions the fall of bodies at the earth's surface, is identical with that which retains the

[1] Note 2. [2] Note 3.

moon in her orbit, and induction led him to conclude, that as the moon is kept in her orbit by the attraction of the earth, so the planets might be retained in their orbits by the attraction of the sun. By such steps he was led to the discovery of one of those powers, with which the Creator has ordained, that matter should reciprocally act upon matter.

Physical astronomy is the science which compares and identifies the laws of motion observed on earth, with the motions that take place in the heavens, and which traces, by an uninterrupted chain of deduction from the great principle that governs the universe, the revolutions and rotations of the planets, and the oscillations[1] of the fluids at their surfaces, and which estimates the changes the system has hitherto undergone, or may hereafter experience,—changes which require millions of years for their accomplishment.

The accumulated efforts of astronomers, from the earliest dawn of civilisation, have been necessary to establish the mechanical theory of astronomy. The courses of the planets have been observed for ages, with a degree of perseverance that is astonishing, if we consider the imperfection and even the want of instruments. The real motions of the earth have been separated from the apparent motions of the planets, the laws of the planetary revolutions have been discovered, and the discovery of these laws has led to the knowledge of the gravitation[2] of matter. On the other hand, descending from the principle of gravitation, every motion in the solar system has been so completely explained, that the laws of any astronomical phenomena that may hereafter occur, are already determined.

[1] Note 4. [2] Note 5.

SECTION I.

ATTRACTION OF A SPHERE.—FORM OF CELESTIAL BODIES.—TERRESTRIAL GRAVITATION RETAINS THE MOON IN HER ORBIT.—HEAVENLY BODIES MOVE IN CONIC SECTIONS.—GRAVITATION PROPORTIONAL TO MASS.—GRAVITATION OF THE PARTICLES OF MATTER.—FIGURE OF THE PLANETS.—HOW IT AFFECTS THE MOTIONS OF THEIR SATELLITES.—ROTATION AND TRANSLATION IMPRESSED BY THE SAME IMPULSE.—MOTION OF SUN AND SOLAR SYSTEM.

It has been proved by Newton, that a particle of matter[1], placed without the surface of a hollow sphere[2], is attracted by it in the same manner as if the mass of the hollow sphere, or the whole matter it contains, were collected into one dense particle in its centre. The same is therefore true of a solid sphere, which may be supposed to consist, of an infinite number of concentric hollow spheres[3]. This, however, is not the case with a spheroid[4]; but the celestial bodies are so nearly spherical, and at such remote distances from one another, that they attract and are attracted as if each were condensed into a single particle situate in its centre of gravity[5],—a circumstance which greatly facilitates the investigation of their motions.

Newton has shown that the force which retains the moon in her orbit, is the same with that, which causes heavy substances to fall at the surface of the earth. If the earth were a sphere, and at rest, a body would be equally attracted, that is, it would have the same weight

[1] Note 6. [2] Note 7. [3] Note 8.
[4] Note 9. [5] Note 10.

at every point of its surface, because the surface of a sphere is every where equally distant from its centre. But as our planet is flattened at the poles[1], and bulges at the equator, the weight of the same body gradually decreases from the poles, where it is greatest, to the equator, where it is least. There is, however, a certain latitude[2] where the attraction of the earth on bodies at its surface, is the same as if it were a sphere; and experience shows that bodies there fall through 16·0697 feet in a second. The mean distance[3] of the moon from the earth is about sixty times the radius[4] of the earth. When the number 16·0697 is diminished in the ratio[5] of 1 to 3600, which is the square of the moon's distance[6] from the earth's centre, estimated in terrestrial radii, it is found to be exactly the space the moon would fall through, in the first second of her descent to the earth, were she not prevented by the centrifugal force[7] arising from the velocity with which she moves in her orbit. The moon is thus retained in her orbit by a force having the same origin, and regulated by the same law, with that which causes a stone to fall at the earth's surface. The earth may therefore be regarded as the centre of a force which extends to the moon; and, as experience shows that the action and re-action of matter are equal and contrary[8], the moon must attract the earth with an equal and contrary force.

Newton also ascertained that a body projected[9] in space[10], will move in a conic section[11], if attracted by a force proceeding from a fixed point, with an intensity inversely as the square of the distance[12]; but that any deviation from that law will cause it to move in a curve

[1] Note 11. [2] Note 12. [3] Note 13. [4] Note 14.
[5] Note 15. [6] Note 16. [7] Note 17. [8] Note 18.
[9] Note 19. [10] Note 20. [11] Note 21. [12] Note 22.

of a different nature. Kepler found, by direct observation, that the planets describe ellipses [1], or oval paths, round the sun. Later observations show that comets also move in conic sections. It consequently follows, that the sun attracts all the planets and comets inversely as the square of their distances from his centre; the sun, therefore, is the centre of a force extending indefinitely in space, and including all the bodies of the system in its action.

Kepler also deduced from observation, that the squares of the periodic times [2] of the planets, or the times of their revolutions round the sun, are proportional to the cubes of their mean distances from his centre. [3] Hence the intensity of gravitation of all the bodies towards the sun is the same at equal distances. Consequently, gravitation is proportional to the masses [4], for, if the planets and comets were at equal distances from the sun, and left to the effects of gravity, they would arrive at his surface at the same time. [5] The satellites also gravitate to their primaries [6] according to the same law that their primaries do to the sun. Thus, by the law of action and re-action, each body is itself the centre of an attractive force extending indefinitely in space, causing all the mutual disturbances which render the celestial motions so complicated, and their investigation so difficult.

The gravitation of matter directed to a centre, and attracting directly as the mass, and inversely as the square of the distance, does not belong to it when considered in mass only; particle acts on particle according to the same law when at sensible distances from each other. If the sun acted on the centre of the earth,

[1] Note 23 [2] Note 24 [3] Note 25
[4] Note 26 [5] Note 27. [6] Note 28.

without attracting each of its particles, the tides would be very much greater than they now are, and would also, in other respects, be very different. The gravitation of the earth to the sun results from the gravitation of all its particles, which, in their turn, attract the sun in the ratio of their respective masses. There is a reciprocal action, likewise, between the earth and every particle at its surface. Were this not the case, and were any portion of the earth, however small, to attract another portion, and not be itself attracted, the centre of gravity of the earth would be moved in space by this action, which is impossible.

The forms of the planets result from the reciprocal attraction of their component particles. A detached fluid mass, if at rest, would assume the form of a sphere, from the reciprocal attraction of its particles. But if the mass revolve about an axis, it becomes flattened at the poles, and bulges at the equator [1], in consequence of the centrifugal force arising from the velocity of rotation [2], — for the centrifugal force diminishes the gravity of the particles at the equator, and equilibrium can only exist where these two forces are balanced by an increase of gravity. Therefore, as the attractive force is the same on all particles at equal distances from the centre of a sphere, the equatorial particles would recede from the centre, till their increase in number balance the centrifugal force by their attraction. Consequently, the sphere would become an oblate, or flattened spheroid; and a fluid partially or entirely covering a solid, as the ocean and atmosphere cover the earth, must assume that form in order to remain in equilibrio. The surface of the sea is therefore spheroidal, and the surface of the earth only deviates from that figure where it rises

[1] Note 11 [2] Note 29

above or sinks below the level of the sea. But the deviation is so small that it is unimportant when compared with the magnitude of the earth; for the mighty chain of the Andes, and the yet more lofty Himalaya, bear about the same proportion to the earth that a grain of sand does to a globe three feet in diameter. Such is the form of the earth and planets. The compression[1] or flattening at their poles is, however, so small, that even Jupiter, whose rotation is the most rapid, and therefore the most elliptical of the planets, may, from his great distance, be regarded as spherical. Although the planets attract each other as if they were spheres, on account of their distances, yet the satellites[2] are near enough to be sensibly affected in their motions by the forms of their primaries. The moon, for example, is so near the earth, that the reciprocal attraction between each of her particles, and each of the particles in the prominent mass at the terrestrial equator, occasions considerable disturbances in the motions of both bodies; for the action of the moon on the matter at the earth's equator, produces a nutation[3] in the axis[4] of rotation, and the re-action of that matter on the moon, is the cause of a corresponding nutation in the lunar orbit.[5]

If a sphere at rest in space, receive an impulse passing through its centre of gravity, all its parts will move with an equal velocity in a straight line; but if the impulse does not pass through the centre of gravity, its particles, having unequal velocities, will have a rotatory or revolving motion, at the same time that it is translated[6] in space. These motions are independent of one another; so that a contrary impulse, passing through its centre of gravity, will impede its progress, without interfering

[1] Note 30. [2] Note 31. [3] Note 32.
[4] Note 33. [5] Note 34. [6] Note 35.

with its rotation. As the sun rotates about an axis, it seems probable, if an impulse in a contrary direction has not been given to his centre of gravity, that he moves in space, accompanied by all those bodies which compose the solar system,—a circumstance which would in no way interfere with their relative motions; for, in consequence of the principle, that force is proportional to velocity[1], the reciprocal attractions of a system remain the same, whether its centre of gravity be at rest, or moving uniformly in space. It is computed that, had the earth received its motion from a single impulse, that impulse must have passed through a point about twenty-five miles from its centre.

Since the motions of rotation and translation of the planets are independent of each other, though probably communicated by the same impulse, they form separate subjects of investigation.

[1] Note 3.

SECTION II

ELLIPTICAL MOTION.—MEAN AND TRUE MOTION.—EQUINOCTIAL.—ECLIPTIC.—EQUINOXES.—MEAN AND TRUE LONGITUDE.—EQUATION OF CENTRE.—INCLINATION OF THE ORBITS OF PLANETS.—CELESTIAL LATITUDE.—NODES.—ELEMENTS OF AN ORBIT.—UNDISTURBED OR ELLIPTICAL ORBITS.—GREAT INCLINATION OF THE ORBITS OF THE NEW PLANETS.—UNIVERSAL GRAVITATION THE CAUSE OF PERTURBATIONS IN THE MOTIONS OF THE HEAVENLY BODIES.—PROBLEM OF THE THREE BODIES.—STABILITY OF SOLAR SYSTEM DEPENDS UPON THE PRIMITIVE MOMENTUM OF THE BODIES.

A PLANET moves in its elliptical orbit with a velocity varying every instant, in consequence of two forces, one tending to the centre of the sun, and the other in the direction of a tangent[1] to its orbit, arising from the primitive impulse, given at the time when it was launched into space. Should the force in the tangent cease, the planet would fall to the sun by its gravity. Were the sun not to attract it, the planet would fly off in the tangent. Thus, when the planet is at the point where the orbit is farthest from the sun, his action overcomes the planet's velocity, and brings it towards him with such an accelerated motion or increased speed, that at last, it overcomes the sun's attraction, and, shooting past him, gradually decreases in velocity, until it arrives at the most distant point, where the sun's attraction again prevails.[2] In this motion the *radii vectores*[3], or imaginary lines joining the centres of the sun and the planets, pass over equal areas in equal times.[4]

The mean distance of a planet from the sun is

[1] Note 37. [2] Note 38. [3] Note 39. [4] Note 40.

equal to half the major axis[1] of its orbit: if, therefore, the planet described a circle[2] round the sun at its mean distance, the motion would be uniform, and the periodic time unaltered, because the planet would arrive at the extremities of the major axis at the same instant, and would have the same velocity, whether it moved in the circular or elliptical orbit, since the curves coincide in these points. But, in every other part, the elliptical, or true motion[3], would either be faster or slower than the circular or mean motion.[4] As it is necessary to have some fixed point in the heavens from whence to estimate these motions, the vernal equinox[5] at a given epoch has been chosen. The equinoctial, which is a great circle traced in the starry heavens by the imaginary extension of the plane of the terrestrial equator, is intersected by the ecliptic, or apparent path of the sun, in two points diametrically opposite to one another, called the vernal and autumnal equinoxes. The vernal equinox is the point through which the sun passes, in going from the southern to the northern hemisphere; and the autumnal, that in which he crosses from the northern to the southern. The mean or circular motion of a body, estimated from the vernal equinox, is its mean longitude; and its elliptical, or true motion, reckoned from that point, is its true longitude[6]: both being estimated from west to east, the direction in which the bodies move. The difference between the two is called the equation of the centre[7]; which consequently vanishes at the apsides[8], and is at its maximum ninety degrees[9] distant from these points, or in quadratures[10], where it measures the eccentricity[11] of the orbit; so that the

[1] Note 41. [2] Note 42. [3] Note 43. [4] Note 44.
[5] Note 45. [6] Note 46. [7] Note 47. [8] Note 48.
[9] Note 49. [10] Note 50. [11] Note 51.

place of a planet in its elliptical orbit is obtained, by adding or subtracting the equation of the centre to or from its mean longitude.

The orbits of the planets have a very small inclination[1] to the plane of the ecliptic in which the earth moves; and on that account, astronomers refer their motions to this plane at a given epoch as a known and fixed position. The angular distance of a planet from the plane of the ecliptic is its latitude[2], which is south or north, according as the planet is south or north of that plane When the planet is in the plane of the ecliptic, its latitude is zero: it is then said to be in its nodes.[3] The ascending node is that point in the ecliptic, through which the planet passes, in going from the southern to the northern hemisphere. The descending node is a corresponding point in the plane of the ecliptic diametrically opposite to the other, through which the planet descends in going from the northern to the southern hemisphere The longitude and latitude of a planet cannot be obtained by direct observation, but are deduced from observations made from the surface of the earth, by a very simple computation. These two quantities however, will not give the place of a planet in space Its distance from the sun[4] must also be known, and, for the complete determination of its elliptical motion, the nature and position of its orbit must be ascertained by observation. This depends upon seven quantities, called the elements of the orbit.[5] These are, the length of the major axis, and the eccentricity, which determine the form of the orbit: the longitude of the planet when at its least distance from the sun, called the longitude of the perihelion; the inclination of the or-

[1] Note 52 [2] Note 53 [3] Note 54
[4] Note 55 [5] Note 56

bit to the plane of the ecliptic, and the longitude of its ascending node, — these give the position of the orbit in space, but the periodic time, and the longitude of the planet at a given instant, called the longitude of the epoch, are necessary for finding the place of the body in its orbit at all times. A perfect knowledge of these seven elements is requisite, for ascertaining all the circumstances of undisturbed elliptical motion. By such means it is found, that the paths of the planets, when their mutual disturbances are omitted, are ellipses, nearly approaching to circles, whose planes, slightly inclined to the ecliptic, cut it in straight lines, passing through the centre of the sun.[1] The orbits of the recently discovered planets deviate more from the ecliptic than those of the ancient planets that of Pallas, for instance, has an inclination of 35° to it, on which account it is more difficult to determine their motions.

Were the planets attracted by the sun only, they would always move in ellipses, invariable in form and position; and because his action is proportional to his mass, which is much larger than that of all the planets put together, the elliptical is the nearest approximation to their true motions. The true motions of the planets are extremely complicated, in consequence of their mutual attraction; so that they do not move in any known or symmetrical curve, but in paths now approaching to, now receding from, the elliptical form; and their radii vectores do not describe areas exactly proportional to the time, so that the areas become a test of disturbing forces.

To determine the motion of each body, when disturbed by all the rest, is beyond the power of analysis. It is therefore necessary to estimate the disturbing

[1] Note 57

action of one planet at a time, whence the celebrated problem of the three bodies, originally applied to the moon, the earth, and the sun, namely, the masses being given of three bodies projected from three given points, with velocities given both in quantity and direction; and, supposing the bodies to gravitate to one another with forces that are directly as their masses, and inversely as the squares of the distances, to find the lines described by these bodies, and their positions at any given instant.

By this problem the motions of translation of the celestial bodies are determined It is an extremely difficult one, and would be infinitely more so, if the disturbing action were not very small when compared with the central force; that is, if the action of the planets on one another, were not very small when compared with that of the sun. As the disturbing influence of each body may be found separately, it is assumed that the action of the whole system, in disturbing any one planet, is equal to the sum of all the particular disturbances it experiences, on the general mechanical principle, that the sum of any number of small oscillations is nearly equal to their simultaneous and joint effect.

On account of the reciprocal action of matter, the stability of the system depends upon the intensity of the primitive momentum[1] of the planets, and the ratio of their masses to that of the sun, for the nature of the conic sections in which the celestial bodies move, depends upon the velocity with which they were first propelled in space. Had that velocity been such as to make the planets move in orbits of unstable equilibrium[2],

[1] Note 58. [2] Note 59.

their mutual attractions might have changed them into parabolas, or even hyperbolas[1], so that the earth and planets might, ages ago, have been sweeping far from our sun through the abyss of space. But as the orbits differ very little from circles, the momentum of the planets, when projected, must have been exactly sufficient to ensure the permanency and stability of the system. Besides, the mass of the sun is vastly greater than that of any planet, and as their inequalities bear the same ratio to their elliptical motions, that their masses do to that of the sun, their mutual disturbances only increase or diminish the excentricities of their orbits, by very minute quantities; consequently, the magnitude of the sun's mass is the principal cause of the stability of the system. There is not in the physical world a more splendid example of the adaptation of means to the accomplishment of an end, than is exhibited in the nice adjustment of these forces, at once the cause of the variety and of the order of Nature.

[1] Note 21.

SECTION III.

PERTURBATIONS PERIODIC AND SECULAR.—DISTURBING ACTION EQUIVALENT TO THREE PARTIAL FORCES.—TANGENTIAL FORCE THE CAUSE OF THE PERIODIC INEQUALITIES IN LONGITUDE, AND SECULAR INEQUALITIES IN THE FORM AND POSITION OF THE ORBIT IN ITS OWN PLANE.—RADIAL FORCE THE CAUSE OF VARIATIONS IN THE PLANET'S DISTANCE FROM THE SUN.—IT COMBINES WITH THE TANGENTIAL FORCE TO PRODUCE THE SECULAR VARIATIONS IN THE FORM AND POSITION OF THE ORBIT IN ITS OWN PLANE.—PERPENDICULAR FORCE THE CAUSE OF PERIODIC PERTURBATIONS IN LATITUDE, AND SECULAR VARIATIONS IN THE POSITION OF THE ORBIT WITH REGARD TO THE PLANE OF THE ECLIPTIC.—MEAN MOTION AND MAJOR AXIS INVARIABLE.—STABILITY OF SYSTEM.—EFFECTS OF A RESISTING MEDIUM.—INVARIABLE PLANE OF THE SOLAR SYSTEM AND OF THE UNIVERSE.—GREAT INEQUALITY OF JUPITER AND SATURN.

THE planets are subject to disturbances of two kinds, both resulting from the constant operation of their reciprocal attraction; one kind, depending upon their positions with regard to each other, begins from zero, increases to a maximum, decreases and becomes zero again, when the planets return to the same relative positions. In consequence of these, the disturbed planet is sometimes drawn away from the sun, sometimes brought nearer to him. At one time it is drawn above the plane of its orbit, at another time below it, according to the position of the disturbing body. All such changes, being accomplished in short periods, some in a few months, others in years, or in hundreds of years, are denominated periodic inequalities.

The inequalities of the other kind, though occasioned likewise by the disturbing energy of the planets, are entirely independent of their relative positions. They

depend upon the relative positions of the orbits alone, whose forms and places in space, are altered by very minute quantities in immense periods of time, and are, therefore, called secular inequalities.

The periodical perturbations are compensated, when the bodies return to the same relative positions with regard to one another and the sun: the secular inequalities are compensated, when the orbits return to the same positions relatively to one another, and to the plane of the ecliptic.

Planetary motion, including both these kinds of disturbance, may be represented by a body revolving in an ellipse, and making small and transient deviations, now on one side of its path, and now on the other, whilst the ellipse itself is slowly, but perpetually changing both in form and position.

The periodic inequalities are merely transient deviations of the planet from its path, the most remarkable of which only lasts about 918 years; but, in consequence of the secular disturbances, the apsides, or extremities of the major axes of all the orbits, have a direct but variable motion in space, excepting those of the orbit of Venus, which are retrograde[1], and the lines of the nodes move with a variable velocity in a contrary direction. Besides these, the inclination and excentricity of every orbit are in a state of perpetual but slow change. These effects result from the disturbing action of all the planets on each. But as it is only necessary to estimate the disturbing influence of one body at a time, what follows may convey some idea of the manner in which one planet disturbs the elliptical motion of another.

Suppose two planets moving in ellipses round the sun;

[1] Note 60

if one of them attracted the other and the sun with equal intensity, and in parallel directions[1], it would have no effect in disturbing the elliptical motion at all. The inequality of this attraction is the sole cause of perturbation, and the difference between the disturbing planet's action on the sun and on the disturbed planet constitutes the disturbing force, which consequently varies in intensity and direction with every change in the relative positions of the three bodies. Although both the sun and planet are under the influence of the disturbing force, the motion of the disturbed planet is referred to the centre of the sun as a fixed point, for convenience. The whole force[2] which disturbs a planet, is equivalent to three partial forces. One of these acts on the disturbed planet, in the direction of a tangent to its orbit, and is called the tangential force: it occasions secular inequalities in the form and position of the orbit in its own plane, and is the sole cause of the periodical perturbations in the planet's longitude. Another acts upon the same body in the direction of its radius vector, that is, in the line joining the centres of the sun and planet, and is called the radial force: it produces periodical changes in the distance of the planet from the sun, and affects the form and position of the orbit in its own plane. The third, which may be called the perpendicular force, acts at right angles to the plane of the orbit, occasions the periodic inequalities in the planet's latitude, and affects the position of the orbit with regard to the plane of the ecliptic.

It has been observed, that the radius vector of a planet, moving in a perfectly elliptical orbit, passes over equal areas in equal times; a circumstance which is independent of the law of the force, and would be the

[1] Note 61. [2] Note 62.

same whether it varied inversely as the square of the distance, or not, provided only that it be directed to the centre of the sun. Hence the tangential force, not being directed to a centre, occasions [illegible] description of areas, or, what is the same thing, disturbs the motion of the planet in longitude. [illegible] tangential force sometimes accelerates the motion [illegible], sometimes retards it, and [illegible] effect at all. Were the orbits of both [illegible] a complete compensation would take place [illegible] revolution of the two planets, for [illegible] the accelerations and retardations [illegible] symmetrical on each side of the [illegible] it is clear, that, if the motion be [illegible] certain space, and then retarded [illegible] motion at the end of the time will be the same as if no change had taken place. But [illegible] planets are ellipses, this compensation [illegible] for, as the planet moves [illegible] some positions more directly [illegible] under the influence of the disturbing force than in others. And although multitudes of [illegible] compensate each other in a short period, those depending on peculiar relations among the periodic times of the planets, do not compensate each other till after one, or even till after several revolutions of both bodies. A periodic inequality of this kind in the motions of Jupiter and Saturn has a period of no less than 918 years.

The radial force, or that part of the disturbing force which acts in the direction of the line joining the centres of the sun and disturbed planet, has no effect on the areas, but is the cause of periodical changes of small extent in the distance of the planet from the sun. It has already been shown, that the force producing

perfectly elliptical motion varies inversely as the square of the distance, and that a force following any other law, would cause the body to move in a curve of a very different kind Now, the radial disturbing force varies directly as the distance, and, as it sometimes combines with, and increases the intensity of the sun's attraction on the disturbed body, and at other times opposes and consequently diminishes it, in both cases it causes the sun's attraction to deviate from the exact law of gravity, and the whole action of this compound central force on the disturbed body, is either greater or less than what is requisite for perfectly elliptical motion. When greater, the curvature of the disturbed planet's path on leaving its perihelion [1], or point nearest the sun, is greater than it would be in the ellipse, which brings the planet to its aphelion [2], or point farthest from the sun, before it has passed through 180°, as it would do if undisturbed. So that in this case, the apsides, or extremities of the major axis, advance in space. When the central force is less than the law of gravity requires, the curvature of the planet's path, is less than the curvature of the ellipse So that the planet on leaving its perihelion, would pass through more than 180° before arriving at its aphelion, which causes the apsides to recede in space. [3] Cases both of advance and recess occur during a revolution of the two planets; but those in which the apsides advance, preponderate. This, however, is not the full amount of the motion of the apsides, part arises also, from the tangential force [4], which alternately accelerates and retards the velocity of the disturbed planet. An increase in the planet's tangential velocity diminishes the curvature of its orbit, and is equivalent to a decrease of central force.

[1] Note 63. [2] Note 61 [3] Note 65. [4] Note 62

On the contrary, a decrease of the tangential velocity, which increases the curvature of the orbit, is equivalent to an increase of central force. These fluctuations, owing to the tangential force, occasion an alternate recess and advance of the apsides, after the manner already explained.[1] An uncompensated portion of the direct motion arising from this cause, conspires with that already impressed by the radial force, and in some cases, even nearly doubles the direct motion of these points. The motion of the apsides may be represented, by supposing a planet to move in an ellipse, while the ellipse itself is slowly revolving about the sun in the same plane.[2] This motion of the major axis, which is direct in all the orbits except that of the planet Venus, is irregular, and so slow, that it requires more than 114,755 years, for the major axis of the earth's orbit, to accomplish a sidereal revolution[3], that is, to return to the same stars, and 21,067 years to complete its tropical revolution[4], or to return to the same equinox. The difference between these two periods arises from a retrograde motion in the equinoctial point, which meets the advancing axis, before it has completed its revolution with regard to the stars. The major axis of Jupiter's orbit requires no less than 200,610 years to perform its sidereal revolution, and 22,748 years to accomplish its tropical revolution from the disturbing action of Saturn alone.

A variation in the eccentricity of the disturbed planet's orbit, is an immediate consequence of the deviations from elliptical curvature, caused by the action of the disturbing force. When the path of the body, in proceeding from its perihelion to its aphelion, is more curved than it ought to be from the effect of the

[1] Note 65. [2] Note 66. [3] Note 67. [4] Note 68.

disturbing forces, it falls within the elliptical orbit, the excentricity is diminished, and the orbit becomes more nearly circular; when that curvature is less than it ought to be, the path of the planet falls without its elliptical orbit[1], and the excentricity is increased; during these changes, the length of the major axis is not altered, the orbit only bulges out, or becomes more flat.[2] Thus the variation in the excentricity arises from the same cause that occasions the motion of the apsides.[3] There is an inseparable connection between these two elements: they vary simultaneously, and have the same period; so that whilst the major axis revolves in an immense period of time, the excentricity increases and decreases by very small quantities, and at length returns to its original magnitude at each revolution of the apsides. The terrestrial excentricity is decreasing at the rate of about 41 miles annually; and, if it were to decrease equably, it would be 37,527 years before the earth's orbit became a circle. The mutual action of Jupiter and Saturn occasions variations in the excentricities of both orbits, the greatest excentricity of Jupiter's orbit corresponding to the least of Saturn's. The period in which these vicissitudes are accomplished is 70,414 years, estimating the action of these two planets alone; but if the action of all the planets were estimated, the cycle would extend to millions of years.

That part of the disturbing force is now to be considered, which acts perpendicularly to the plane of the orbit, causing periodic perturbations in latitude, secular variations in the inclination of the orbit, and a retrograde motion to its nodes on the true plane of the ecliptic.[4] This force tends to pull the disturbed body above, or push[5] it below the plane of its orbit, accord-

[1] Note 65. [2] Note 67. [3] Note 68. [4] Note 70. [5] Note 71.

ing to the relative positions of the two planets with regard to the sun, considered to be fixed By this action, it sometimes makes the plane of the orbit of the disturbed body tend to coincide with the plane of the ecliptic, and sometimes increases its inclination to that plane. In consequence of which, its nodes alternately recede or advance on the ecliptic.[1] When the disturbing planet is in the line of the disturbed planet's nodes[2], it neither affects these points, the latitude, nor the inclination, because both planets are then in the same plane. When it is at right angles to the line of the nodes, and the orbit symmetrical on each side of the disturbing force, the average motion of these points, after a revolution of the disturbed body, is retrograde, and comparatively rapid; but when the disturbing planet is so situated that the orbit of the disturbed planet is not symmetrical on each side of the disturbing force, which is most frequently the case, every possible variety of action takes place Consequently, the nodes are perpetually advancing or receding with unequal velocity, but, as a compensation is not effected, their motion is, on the whole, retrograde.

With regard to the variations in the inclination, it is clear, that, when the orbit is symmetrical on each side of the disturbing force, all its variations are compensated after a revolution of the disturbed body, and are merely periodical perturbations on the planet's latitude, and no secular change is induced in the inclination of the orbit. When, on the contrary, that orbit is not symmetrical on each side of the disturbing force, although many of the variations in latitude are transient or periodical, still, after a complete revolution of the

[1] Note 72. [2] Note 73.

disturbed body, a portion remains uncompensated, which forms a secular change in the inclination of the orbit to the plane of the ecliptic. It is true, part of this secular change in the inclination is compensated by the revolution of the disturbing body, whose motion has not hitherto been taken into the account, so that perturbation compensates perturbation, but still, a comparatively permanent change is effected in the inclination, which is not compensated till the nodes have accomplished a complete revolution.

The changes in the inclination are extremely minute[1], compared with the motion of the nodes, and there is the same kind of inseparable connection between their secular changes that there is between the variations of the excentricities and the motions of the major axis. The nodes and inclinations vary simultaneously, their periods are the same, and very great. The nodes of Jupiter's orbit, from the action of Saturn alone, require 36,261 years to accomplish even a tropical revolution. In what precedes, the influence of only one disturbing body has been considered, but when the action and reaction of the whole system is taken into account, every planet is acted upon, and does itself act, in this manner, on all the others; and the joint effect keeps the inclinations and excentricities in a state of perpetual variation. It makes the major axes of all the orbits continually revolve, and causes, on an average, a retrograde motion of the nodes of each orbit upon every other. The ecliptic[2] itself is in motion from the mutual action of the earth and planets, so that the whole is a compound phenomenon of great complexity, extending through unknown ages. At the present time, the inclinations of all the orbits are decreasing, but so slowly, that the

[1] Note 71 [2] Note 70

inclination of Jupiter's orbit is only about six minutes less than it was in the age of Ptolemy.

But, in the midst of all these vicissitudes, the major axes and mean motions of the planets remain permanently independent of secular changes. They are so connected by Kepler's law, of the squares of the periodic times being proportional to the cubes of the mean distances of the planets from the sun, that one cannot vary without affecting the other. And it is proved, that any variations which do take place are transient, and depend only on the relative positions of the bodies.

It is true that, according to theory, the radial disturbing force should permanently alter the dimensions of all the orbits, and the periodic times of all the planets, to a certain degree. For example, the masses of all the planets revolving within the orbit of any one, such as Mars, by adding to the interior mass, increase the attracting force of the sun, which, therefore, must contract the dimensions of the orbit of that planet, and diminish its periodic time, whilst the planets exterior to Mars's orbit must have the contrary effect. But the mass of the whole of the planets and satellites taken together is so small, when compared with that of the sun, that these effects are quite insensible, and could only have been discovered by theory. And, as it is certain that the greater axes and mean motions are not permanently changed by any other power whatever, it may be concluded that they are invariable.

With the exception of these two elements, it appears that all the bodies are in motion, and every orbit in a state of perpetual change. Minute as these changes are, they might be supposed to accumulate in the course of ages, sufficiently to derange the whole order of nature, to alter the relative positions of the planets, to put an

end to the vicissitudes of the seasons, and to bring about collisions which would involve our whole system, now so harmonious, in chaotic confusion. It is natural to enquire, what proof exists that nature will be preserved from such a catastrophe? Nothing can be known from observation, since the existence of the human race has occupied comparatively but a point in duration, while these vicissitudes embrace myriads of ages. The proof is simple and conclusive. All the variations of the solar system, secular as well as periodic, are expressed analytically by the sines and cosines of circular arcs[1], which increase with the time, and, as a sine or cosine can never exceed the radius, but must oscillate between zero and unity, however much the time may increase, it follows that, when the variations have accumulated to a maximum, by slow changes, in however long a time, they decrease, by the same slow degrees, till they arrive at their smallest value, again to begin a new course; thus for ever oscillating about a mean value. This, however, would not be the case if the planets moved in a resisting medium[2], for then both the excentricities and the major axes of the orbits would vary with the time, so that the stability of the system would be ultimately destroyed. The existence of such a fluid is now proved, and, although it is so extremely rare that hitherto its effects on the motions of the planets have been altogether insensible, there can be no doubt, that, in the immensity of time, it will modify the forms of the planetary orbits, and may at last even cause the destruction of our system, which in itself contains no principle of decay, unless a rotatory motion from west to east has been given to this fluid by the bodies of the solar system, which have all been revolving about the

[1] Note 75. [2] Note 76.

sun in that direction for unknown ages. Such a vortex would have no effect on bodies moving with it, but it would influence the motions of those not in the same direction.

Three circumstances have generally been supposed necessary to prove the stability of the system the small excentricities of the planetary orbits, their small inclinations, and the revolutions of all the bodies, as well planets as satellites, in the same direction. These circumstances certainly afford the means of proving the variations to be confined to very narrow limits indeed: they, however, though sufficient, are not necessary conditions. The periodicity of the terms in which the inequalities are expressed is enough to assure us that, though we do not know the extent of the limits, nor the period of that grand cycle which probably embraces millions of years, yet they never will exceed what is requisite for the stability and harmony of the whole, for the preservation of which every circumstance is so beautifully and wonderfully adapted.

The plane of the ecliptic itself, though assumed to be fixed at a given epoch for the convenience of astronomical computation, is subject to a minute secular variation of $47''\cdot55$, occasioned by the reciprocal action of the planets. But, as this is also periodical, and cannot exceed $2^\circ\ 42'$, the terrestrial equator, which is inclined to it at an angle of about $23^\circ\ 27'\ 39''\cdot26$, will never coincide with the plane of the ecliptic: so there never can be perpetual spring.[1] The rotation of the earth is uniform; therefore day and night, summer and winter, will continue their vicissitudes while the system endures, or is undisturbed by foreign causes.

[1] Note 77

> Yonder starry sphere
> Of planets, and of fix'd, in all her wheels
> Resembles nearest mazes intricate,
> Eccentric, intervolved, yet regular,
> Then most, when most irregular they seem

The stability of our system was established by La Grange, "a discovery," says Professor Playfair, "that must render the name for ever memorable in science, and revered by those who delight in the contemplation of whatever is excellent and sublime." After Newton's discovery of the mechanical laws of the elliptical orbits of the planets, La Grange's discovery of their periodical inequalities is, without doubt, the noblest truth in physical astronomy, and, in respect of the doctrine of final causes, it may be regarded as the greatest of all.

Notwithstanding the permanency of our system, the secular variations in the planetary orbits would have been extremely embarrassing to astronomers when it became necessary to compare observations separated by long periods The difficulty was in part obviated, and the principle for accomplishing it established, by La Place, and has since been extended by M. Poinsot. It appears that there exists an invariable plane [1], passing through the centre of gravity of the system, about which the whole oscillates within very narrow limits, and that this plane will always remain parallel to itself, whatever changes time may induce in the orbits of the planets, in the plane of the ecliptic, or even in the law of gravitation, provided only that our system remains unconnected with any other. The position of the plane is determined by this property, — that, if each particle in the system be multiplied by the area described upon this plane in a given time, by the projection of its radius vector about the common centre of gravity of the whole,

[1] Note 76

the sum of all these products will be a maximum.[1] La Place found that the plane in question is inclined to the ecliptic at an angle of nearly 1° 35′ 31″, and that, in passing through the sun, and about midway between the orbits of Jupiter and Saturn, it may be regarded as the equator of the solar system, dividing it into two parts, which balance one another in all their motions This plane of greatest inertia, by no means peculiar to the solar system, but existing in every system of bodies submitted to their mutual attractions only, always maintains a fixed position, whence the oscillations of the system may be estimated through unlimited time Future astronomers will know, from its immutability or variation, whether the sun and his attendants are connected or not with the other systems of the universe. Should there be no link between them, it may be inferred, from the rotation of the sun, that the centre of gravity[2] of the system situate within his mass describes a straight line in this invariable plane or great equator of the solar system, which, unaffected by the changes of time, will maintain its stability through endless ages. But, if the fixed stars, comets, or any unknown and unseen bodies, affect our sun and planets, the nodes of this plane will slowly recede on the plane of that immense orbit which the sun may describe about some most distant centre, in a period which it transcends the powers of man to determine There is every reason to believe that this is the case, for it is more than probable that, remote as the fixed stars are, they in some degree influence our system, and that even the invariability of this plane is relative, only appearing fixed to creatures incapable of estimating its minute and slow changes during the small extent of time and space granted to the

[1] Note 79 [2] Note 80

human race. "The developement of such changes," as M. Poinsot justly observes, "is similar to an enormous curve, of which we see so small an arc, that we imagine it to be a straight line." If we raise our views to the whole extent of the universe, and consider the stars, together with the sun, to be wandering bodies, revolving about the common centre of creation, we may then recognise in the equatorial plane passing through the centre of gravity of the universe the only instance of absolute and eternal repose.

All the periodic and secular inequalities deduced from the law of gravitation, are so perfectly confirmed by observation, that analysis has become one of the most certain means of discovering the planetary irregularities, either when they are too small or too long in their periods to be detected by other methods. Jupiter and Saturn, however, exhibit inequalities which for a long time seemed discordant with that law. All observations, from those of the Chinese and Arabs down to the present day, prove that for ages the mean motions of Jupiter and Saturn have been affected by a great inequality of a very long period, forming an apparent anomaly in the theory of the planets. It was long known by observation that five times the mean motion of Saturn is nearly equal to twice that of Jupiter; a relation which the sagacity of La Place perceived to be the cause of a periodic irregularity in the mean motion of each of these planets, which completes its period in nearly 918 years, the one being retarded while the other is accelerated; but both the magnitude and period of these quantities vary, in consequence of the secular variations in the elements of the orbits. Suppose the two planets to be on the same side of the sun, and all three in the same straight line, they are then said to be in

conjunction.[1] Now, if they begin to move at the same time, one making exactly five revolutions in its orbit, while the other only accomplishes two, it is clear that Saturn, the slow moving body, will only have got through a part of its orbit during the time that Jupiter has made one whole revolution, and part of another, before they be again in conjunction. It is found that during this time their mutual action is such as to produce a great many perturbations which compensate each other, but that there still remains a portion outstanding, owing to the length of time during which the forces act in the same manner, and if the conjunctions always happened in the same point of the orbit, this uncompensated inequality in the mean motion, would go on increasing till the periodic times and forms of the orbits were completely and permanently changed: a case that would actually take place if Jupiter accomplished exactly five revolutions in the time that Saturn performed two. These revolutions are, however, not exactly commensurable, the points in which the conjunctions take place are in advance each time as much as 8°·37; so that the conjunctions do not happen exactly in the same points of the orbits till after a period of 850 years; and, in consequence of this small advance, the planets are brought into such relative positions, that the inequality, which seemed to threaten the stability of the system, is completely compensated, and the bodies, having returned to the same relative positions with regard to one another and the sun, begin a new course. The secular variations in the elements of the orbit increase the period of the inequality to 918 years.[2] As any perturbation which affects the mean motion affects also the major axis, the disturbing forces tend to diminish

[1] Note 81 [2] Note 82

the major axis of Jupiter's orbit, and increase that of Saturn's during one half of the period, and the contrary during the other half. This inequality is strictly periodical, since it depends upon the configuration[1] of the two planets; and theory is confirmed by observation, which shows that, in the course of twenty centuries, Jupiter's mean motion has been accelerated by about 3° 23′, and Saturn's retarded by 5° 13′. Several instances of perturbations of this kind occur in the solar system. One, in the mean motions of the Earth and Venus only amounting to a few seconds, has been recently worked out with immense labour by Professor Airy. It accomplishes its changes in 240 years, and arises from the circumstance of thirteen times the periodic time of Venus being nearly equal to eight times that of the Earth. Small as it is, it is sensible in the motions of the sun.

It might be imagined that the reciprocal action of such planets as have satellites would be different from the influence of those that have none. But the distances of the satellites from their primaries are incomparably less than the distances of the planets from the sun, and from one another. So that the system of a planet and its satellites, moves nearly as if all these bodies were united in their common centre of gravity. The action of the sun, however, in some degree disturbs the motion of the satellites about their primary.

[1] Note 83.

SECTION IV

THEORY OF JUPITER'S SATELLITES.—EFFECTS OF THE FIGURE OF JUPITER UPON HIS SATELLITES.—POSITION OF THEIR ORBITS.—SINGULAR LAWS AMONG THE MOTIONS OF THE THREE FIRST SATELLITES.—ECLIPSES OF THE SATELLITES.—VELOCITY OF LIGHT.—ABERRATION.—ETHEREAL MEDIUM.—SATELLITES OF SATURN AND URANUS.

THE changes which take place in the planetary system are exhibited on a smaller scale by Jupiter and his satellites; and, as the period requisite for the developement of the inequalities of these moons only extends to a few centuries, it may be regarded as an epitome of that grand cycle which will not be accomplished by the planets in myriads of ages. The revolutions of the satellites about Jupiter are precisely similar to those of the planets about the sun; it is true they are disturbed by the sun, but his distance is so great, that their motions are nearly the same as if they were not under his influence. The satellites, like the planets, were probably projected in elliptical orbits: but the compression of Jupiter's spheroid is very great, in consequence of his rapid rotation, his equatorial diameter exceeding his polar diameter by no less than 6000 miles; and, as the masses of the satellites are nearly 100,000 times less than that of Jupiter, the immense quantity of prominent matter at his equator, must soon have given the circular form observed in the orbits of the first and second satellites, which its superior attraction will always maintain. The third and fourth satellites being farther removed from its influence, revolve in orbits with a very small

excentricity. And although the two first sensibly move in circles, their orbits acquire a small ellipticity from the disturbances they experience.[1]

It has been stated, that the attraction of a sphere on an exterior body, is the same, as if its mass were united in one particle in its centre of gravity, and therefore inversely as the square of the distance. In a spheroid, however, there is an additional force arising from the bulging mass at its equator, which, not following the exact law of gravity, acts as a disturbing force. One effect of this disturbing force in the spheroid of Jupiter is, to occasion a direct motion in the greater axes of the orbits of all his satellites, which is more rapid the nearer the satellite is to the planet, and very much greater than that part of their motion which arises from the disturbing action of the sun. The same cause occasions the orbits of the satellites to remain nearly in the plane of Jupiter's equator[2], on account of which the satellites are always seen nearly in the same line[3], and the powerful action of that quantity of prominent matter, is the reason why the motions of the nodes of these small bodies is so much more rapid than those of the planet. The nodes of the fourth satellite accomplish a tropical revolution in 531 years, while those of Jupiter's orbit require no less than 36,261 years,—a proof of the reciprocal attraction between each particle of Jupiter's equator and of the satellites. In fact, if the satellites moved exactly in the plane of Jupiter's equator, they would not be pulled out of that plane, because his attraction would be equal on both sides of it. But, as their orbits have a small inclination to the plane of the planet's equator, there is a want of symmetry, and the action of the pro-

[1] Note 84. [2] Note 85. [3] Note 86.

tuberant matter tends to make the nodes regress by pulling the satellites above or below the planes of their orbits, an action which is so great on the interior satellites, that the motions of their nodes are nearly the same as if no other disturbing force existed.

The orbits of the satellites do not retain a permanent inclination, either to the plane of Jupiter's equator, or to that of his orbit, but to certain planes passing between the two, and through their intersection. These have a greater inclination to his equator the farther the satellite is removed, owing to the influence of Jupiter's compression, and they have a slow motion corresponding to secular variations in the planes of Jupiter's orbit and equator.

The satellites are not only subject to periodic and secular inequalities from their mutual attraction, similar to those which affect the motions and orbits of the planets, but also to others peculiar to themselves. Of the periodic inequalities arising from their mutual attraction the most remarkable take place in the angular motions[1] of the three nearest to Jupiter, the second of which receives from the first a perturbation similar to that which it produces in the third, and it experiences from the third a perturbation similar to that which it communicates to the first. In the eclipses these two inequalities are combined into one, whose period is 437·659 days. The variations peculiar to the satellites, arise from the secular inequalities occasioned by the action of the planets in the form and position of Jupiter's orbit, and from the displacement of his equator. It is obvious that whatever alters the relative positions of the sun, Jupiter, and his satellites, must occasion a change in the directions and intensities of the forces, which will

[1] Note 87.

affect the motions and orbits of the satellites. For this reason the secular variations in the excentricity of Jupiter's orbit occasion secular inequalities in the mean motions of the satellites, and in the motions of the nodes and apsides of their orbits. The displacement of the orbit of Jupiter, and the variation in the position of his equator, also affect these small bodies.[1] The plane of Jupiter's equator is inclined to the plane of his orbit at an angle of 3° 5′ 30″, so that the action of the sun and of the satellites themselves produces a nutation and precession[2] in his equator, precisely similar to that which takes place in the rotation of the earth, from the action of the sun and moon. Hence the protuberant matter at Jupiter's equator is continually changing its position with regard to the satellites, and produces corresponding mutations in their motions. And, as the cause must be proportional to the effect, these inequalities afford the means, not only of ascertaining the compression of Jupiter's spheroid, but they prove that his mass is not homogeneous. Although the apparent diameters of the satellites are too small to be measured, yet their perturbations give the values of their masses with considerable accuracy,—a striking proof of the power of analysis.

A singular law obtains among the mean motions and mean longitudes of the three first satellites. It appears from observation that the mean motion of the first satellite, plus twice that of the third, is equal to three times that of the second, and that the mean longitude of the first satellite, minus three times that of the second, plus twice that of the third, is always equal to two right angles. It is proved by theory, that if these relations had only been approximate when the satellites

[1] Note 88. [2] Note 89.

were first launched into space, their mutual attractions would have established and maintained them, notwithstanding the secular inequalities to which they are liable. They extend to the synodic motions[1] of the satellites, consequently they affect their eclipses, and have a very great influence on their whole theory. The satellites move so nearly in the plane of Jupiter's equator, which has a very small inclination to his orbit, that the three first are eclipsed at each revolution by the shadow of the planet, which is much larger than the shadow of the moon; the fourth satellite is not eclipsed so frequently as the others. The eclipses take place close to the disc of Jupiter when he is near opposition[2], but at times his shadow is so projected with regard to the earth, that the third and fourth satellites vanish and re-appear on the same side of the disc.[3] These eclipses are in all respects similar to those of the moon; but, occasionally, the satellites eclipse Jupiter, sometimes passing like obscure spots across his surface, and resembling annular eclipses of the sun, and sometimes like a bright spot traversing one of his dark belts. Before opposition, the shadow of the satellite, like a round black spot, precedes its passage over the disc of the planet, and after opposition, the shadow follows the satellite.

In consequence of the relations already mentioned in the mean motions and mean longitudes of the three first satellites, they never can be all eclipsed at the same time. For when the second and third are in one direction, the first is in the opposite direction; consequently, when the first is eclipsed, the other two must be between the sun and Jupiter. The instant of the beginning or end of an eclipse of a satellite marks the same instant of absolute time to all the inhabitants of the

[1] Note 90. [2] Note 91. [3] Note 92.

earth; therefore, the time of these eclipses observed by a traveller, when compared with the time of the eclipse computed for Greenwich, or any other fixed meridian[1], gives the difference of the meridians in time, and consequently the longitude of the place of observation. The eclipses of Jupiter's satellites have been the means of a discovery which, though not so immediately applicable to the wants of man, unfolds one of the properties of light,—that medium without whose cheering influence all the beauties of the creation would have been to us a blank. It is observed, that those eclipses of the first satellite, which happen when Jupiter is near conjunction[2], are later by $16^m\ 26^s{\cdot}6$ than those which take place when the planet is in opposition. But, as Jupiter is nearer to us when in opposition by the whole breadth of the earth's orbit than when in conjunction, this circumstance was attributed to the time employed by the rays of light in crossing the earth's orbit, a distance of about 190,000,000 of miles; whence it is estimated that light travels at the rate of 190,000 miles in one second. Such is its velocity, that the earth, moving at the rate of nineteen miles in a second, would take two months to pass through a distance which a ray of light would dart over in eight minutes. The subsequent discovery of the aberration of light confirmed this astonishing result.

Objects appear to be situate in the direction of the rays which proceed from them. Were light propagated instantaneously, every object, whether at rest or in motion, would appear in the direction of these rays; but as light takes some time to travel, we see Jupiter in conjunction, by means of rays that left him $16^m\ 26^s{\cdot}6$ before; but, during that time, we have changed our

[1] Note 93. [2] Note 94.

position, in consequence of the motion of the earth in its orbit; consequently we refer Jupiter to a place in which he is not. His true position is in the diagonal[1] of the parallelogram, whose sides are in the ratio of the velocity of light to the velocity of the earth in its orbit, which is as 190,000 to 19, or 10,000 to 1. In consequence of the aberration of light, the heavenly bodies seem to be in places in which they are not. In fact, if the earth were at rest, rays from a star would pass along the axis of a telescope directed to it: but if the earth were to begin to move in its orbit, with its usual velocity, these rays would strike against the side of the tube; it would, therefore, be necessary to incline the telescope a little, in order to see the star. The angle contained between the axis of the telescope and a line drawn to the true place of the star, is its aberration, which varies in quantity and direction in different parts of the earth's orbit; but as it is only 20″.37, or 20″.5, it is insensible in ordinary cases.[2]

The velocity of light deduced from the observed aberration of the fixed stars, perfectly corresponds with that given by the eclipses of the first satellite. The same result, obtained from sources so different, leaves not a doubt of its truth. Many such beautiful coincidences, derived from circumstances apparently the most unpromising and dissimilar, occur in physical astronomy, and prove connexions, which we might otherwise be unable to trace. The identity of the velocity of light, at the distance of Jupiter, and on the earth's surface, shows that its velocity is uniform; and if light consists in the vibrations of an elastic fluid or ether filling space, an hypothesis which accords best with observed phenomena, the uniformity of its velocity

[1] Note 95. [2] Note 96.

shows that the density of the fluid throughout the whole extent of the solar system must be proportional to its elasticity.[1] Among the fortunate conjectures which have been confirmed by subsequent experience, that of Bacon is not the least remarkable. "It produces in me," says the restorer of true philosophy, "a doubt whether the face of the serene and starry heavens be seen at the instant it really exists, or not till some time later, and whether there be not, with respect to the heavenly bodies, a true time and an apparent time, no less than a true place and an apparent place, as astronomers say, on account of parallax. For it seems incredible that the species or rays of the celestial bodies can pass through the immense interval between them and us in an instant, or that they do not even require some considerable portion of time."

As great discoveries generally lead to a variety of conclusions, the aberration of light affords a direct proof of the motion of the earth in its orbit, and its rotation is proved by the theory of falling bodies, since the centrifugal force it induces, retards the oscillations of the pendulum[2] in going from the pole to the equator. Thus a high degree of scientific knowledge has been requisite to dispel the errors of the senses.

The little that is known of the theories of the satellites of Saturn and Uranus is, in all respects, similar to that of Jupiter. Saturn is accompanied by seven satellites, the most distant of which is about the size of the planet Mars. Its orbit has a sensible inclination to the plane of the ring, but the great compression of Saturn occasions the other satellites to move nearly in the plane of his equator. So many circumstances must concur to render the two interior satellites visible, that

[1] Note 97. [2] Note 98.

they have very rarely been seen. They move exactly at the edge of the ring, and their orbits never deviate from its plane. In 1789, Sir William Herschel saw them like beads, threading the slender line of light which the ring is reduced to, when seen edgewise from the earth. And for a short time he perceived them advancing off it at each end, when turning round in their orbits. The eclipses of the exterior satellites only take place when the ring is in this position. Of the situation of the equator of Uranus we know nothing, nor of his compression; but the orbits of his satellites are nearly perpendicular to the plane of the ecliptic, and by analogy they ought to be in the plane of his equator. Their motions offer the singular phenomenon of being retrograde, or from east to west, while all the planets and the other satellites revolve in the contrary direction.

SECTION V.

LUNAR THEORY.—PERIODIC PERTURBATIONS OF THE MOON.—EQUATION OF CENTRE.—EVECTION.—VARIATION.—ANNUAL EQUATION.—DIRECT AND INDIRECT ACTION OF PLANETS.—MOON'S ACTION ON EARTH DISTURBS HER OWN MOTION.—EXCENTRICITY AND INCLINATION OF LUNAR ORBIT INVARIABLE.—ACCELERATION.—SECULAR VARIATION IN NODES AND PERIGEE.—MOTION OF NODES AND PERIGEE INSEPARABLY CONNECTED WITH THE ACCELERATION.—NUTATION OF LUNAR ORBIT.—FORM AND INTERNAL STRUCTURE OF EARTH DETERMINED FROM IT.—LUNAR, SOLAR, AND PLANETARY ECLIPSES.—OCCULTATIONS AND LUNAR DISTANCES.—MEAN DISTANCE OF THE SUN FROM THE EARTH OBTAINED FROM LUNAR THEORY.—ABSOLUTE DISTANCES OF THE PLANETS, HOW FOUND.

OUR constant companion, the moon, next claims our attention. Several circumstances concur to render her motions the most interesting, and at the same time the most difficult to investigate, of all the bodies of our system. In the solar system, planet troubles planet; but in the lunar theory, the sun is the great disturbing cause, his vast distance being compensated by his enormous magnitude, so that the motions of the moon are more irregular than those of the planets; and, on account of the great ellipticity of her orbit, and the size of the sun, the approximations to her motions are tedious and difficult, beyond what those unaccustomed to such investigations could imagine. The average distance of the moon from the centre of the earth is only 237,360 miles, so that her motion among the stars is perceptible in a few hours. She completes a circuit of the heavens in $27^d\ 7^h\ 43^m\ 11^s{\cdot}5$, moving in an orbit whose excentricity is about

12,985 miles. The moon is about four hundred times nearer to the earth than the sun. The proximity of the moon to the earth keeps them together. For so great is the attraction of the sun, that if the moon were farther from the earth, she would leave it altogether, and would revolve as an independent planet about the sun.

The disturbing action[1] of the sun on the moon, is equivalent to three forces. The first, acting in the direction of the line joining the moon and earth, increases or diminishes her gravity to the earth. The second, acting in the direction of a tangent to her orbit, disturbs her motion in longitude. And the third, acting perpendicularly to the plane of her orbit, disturbs her motion in latitude; that is, it brings her nearer to, or removes her farther from the plane of the ecliptic than she would otherwise be. The periodic perturbations in the moon arising from these forces, are perfectly similar to the periodic perturbations of the planets. But they are much greater and more numerous, because the sun is so large, that many inequalities that are quite insensible in the motions of the planets, are of great magnitude in those of the moon. Among the innumerable periodic inequalities to which the moon's motion in longitude is liable, the most remarkable are, the Equation of the Centre, which is the difference between the moon's mean and true longitude, the Evection, the Variation, and the Annual Equation. The disturbing force which acts in the line joining the moon and earth produces the *Evection*: it diminishes the eccentricity of the lunar orbit in conjunction and opposition, thereby making it more circular, and augments it in quadrature, which con-

[1] Note 93.

sequently renders it more elliptical. The period of this inequality is less than thirty-two days. Were the increase and diminution always the same, the evection would only depend upon the distance of the moon from the sun; but its absolute value also varies with her distance from the perigee[1] of her orbit. Ancient astronomers, who observed the moon solely with a view to the prediction of eclipses, which can only happen in conjunction and opposition, where the excentricity is diminished by the evection, assigned too small a value to the ellipticity of her orbit.[2] The Variation produced by the tangential disturbing force, which is at its maximum when the moon is 45° distant from the sun, vanishes when that distance amounts to a quadrant, and also when the moon is in conjunction and opposition; consequently, that inequality never could have been discovered from the eclipses: its period is half a lunar month.[3] The Annual Equation depends upon the sun's distance from the earth: it arises from the moon's motion being accelerated when that of the earth is retarded, and *vice versâ* — for, when the earth is in its perihelion, the lunar orbit is enlarged by the action of the sun; therefore, the moon requires more time to perform her revolution. But, as the earth approaches its aphelion, the moon's orbit contracts, and less time is necessary to accomplish her motion, — its period, consequently, depends upon the time of the year. In the eclipses, the Annual Equation combines with the equation of the centre of the terrestrial orbit, so that ancient astronomers imagined the earth's orbit to have a greater excentricity than modern astronomers assign to it.

The planets disturb the motion of the moon both

[1] Note 100 [2] Note 101 [3] Note 102

directly and indirectly; their action on the earth alters its relative position with regard to the sun and moon, and occasions inequalities in the moon's motion, which are more considerable than those arising from their direct action; for the same reason the moon, by disturbing the earth, indirectly disturbs her own motion. Neither the excentricity of the lunar orbit, nor its mean inclination to the plane of the ecliptic, have experienced any changes from secular inequalities; for, although the mean action of the sun on the moon, depends upon the inclination of the lunar orbit to the ecliptic, and that the position of the ecliptic is subject to a secular inequality, yet analysis shows, that it does not occasion a secular variation in the inclination of the lunar orbit, because the action of the sun constantly brings the moon's orbit to the same inclination to the ecliptic. The mean motion, the nodes, and the perigee, however, are subject to very remarkable variations.

From an eclipse observed by the Chaldeans at Babylon, on the 19th of March, seven hundred and twenty-one years before the Christian era, the place of the moon is known from that of the sun at the instant of opposition [1], whence her mean longitude may be found. But the comparison of this mean longitude with another mean longitude, computed back for the instant of the eclipse from modern observations, shows that the moon performs her revolution round the earth more rapidly and in a shorter time now, than she did formerly; and that the acceleration in her mean motion has been increasing from age to age, as the square of the time.[2] All ancient and intermediate eclipses confirm this result. As the mean motions of the planets have no secular inequalities,

[1] Note 81 [2] Note 106

this seemed to be an unaccountable anomaly. It was at one time attributed to the resistance of an etherial medium pervading space, and at another to the successive transmission of the gravitating force But as La Place proved that neither of these causes, even if they exist, have any influence on the motions of the lunar perigee [1] or nodes, they could not affect the mean motion, a variation in the mean motion from such causes, being inseparably connected with variations in the motions of the perigee and nodes. That great mathematician, in studying the theory of Jupiter's satellites, perceived that the secular variation in the elements of Jupiter's orbit, from the action of the planets, occasions corresponding changes in the motions of the satellites, which led him to suspect that the acceleration in the mean motion of the moon might be connected with the secular variation in the excentricity of the terrestrial orbit. Analysis has shown that he assigned the true cause of the acceleration.

It is proved that the greater the excentricity of the terrestrial orbit, the greater is the disturbing action of the sun on the moon. Now as the excentricity has been decreasing for ages, the effect of the sun in disturbing the moon has been diminishing during that time. Consequently the attraction of the earth has had a more and more powerful effect on the moon, and has been continually diminishing the size of the lunar orbit. So that the moon's velocity has been gradually augmenting for many centuries to balance the increase of the earth's attraction. This secular increase in the moon's velocity, is called the Acceleration, a name peculiarly appropriate at present, and which will continue to be so for a vast number of ages to come; because, as long as the earth's

[1] Note 100

excentricity diminishes, the moon's mean motion will be accelerated, but when the excentricity has passed its minimum, and begins to increase, the mean motion will be retarded from age to age. The secular acceleration is now about 11″·209, but its effect on the moon's place increases as the square of the time. It is remarkable that the action of the planets, thus reflected by the sun to the moon, is much more sensible than their direct action either on the earth or moon. The secular diminution in the excentricity, which has not altered the equation of the centre of the sun by eight minutes since the earliest recorded eclipses, has produced a variation of about 1° 48′ in the moon's longitude, and of 7° 12′ in her mean anomaly.[1]

The action of the sun occasions a rapid but variable motion in the nodes and perigee of the lunar orbit. Though the nodes recede during the greater part of the moon's revolution, and advance during the smaller, they perform their sidereal revolution in 6793d 6h 41m 45s·6 and the perigee accomplishes a revolution in 3232d 13h 48m 29s·4, or a little more than nine years, notwithstanding its motion is sometimes retrograde and sometimes direct. but such is the difference between the disturbing energy of the sun and that of all the planets put together, that it requires no less than 109,830 years for the greater axis of the terrestrial orbit to do the same, moving at the rate of 11″·8 annually. The form of the earth has no sensible effect either on the lunar nodes or apsides. It is evident that the same secular variation which changes the sun's distance from the earth, and occasions the acceleration in the moon's mean motion, must affect the nodes and perigee. It consequently appears, from theory as well

[1] Note 104

as observation, that both these elements are subject to a secular inequality arising from the variation in the eccentricity of the earth's orbit, which connects them with the Acceleration, so that both are retarded when the mean motion is anticipated The secular variations in these three elements are in the ratio of the numbers 3, 0·735, and 1, whence the three motions of the moon, with regard to the sun, to her perigee, and to her nodes, are continually accelerated, and their secular equations are as the numbers 1, 4·702, and 0 612 A comparison of ancient eclipses observed by the Arabs, Greeks, and Chaldeans, imperfect as they are, with modern observations, confirms these results of analysis Future ages will develop these great inequalities, which at some most distant period will amount to many circumferences.[1] They are, indeed, periodic, but who shall tell their period? Millions of years must elapse before that great cycle is accomplished

The moon is so near, that the excess of matter at the earth's equator, occasions periodic variations in her longitude, and also that remarkable inequality in her latitude, already mentioned as a nutation in the lunar orbit, which diminishes its inclination to the ecliptic, when the moon's ascending node coincides with the equinox of spring, and augments it when that node coincides with the equinox of autumn. As the cause must be proportional to the effect, a comparison of these inequalities, computed from theory, with the same given by observation, shows that the compression of the terrestrial spheroid, or the ratio of the difference between the polar and equatorial diameters, to the diameter of the equator, is $\frac{1}{305 \cdot 05}$. It is proved analytically, that if a fluid mass of homogeneous matter, whose particles

[1] Note 105

attract each other inversely as the square of the distance, were to revolve about an axis as the earth does, it would assume the form of a spheroid whose compression is $\frac{1}{230}$, whence it appears that the earth is not homogeneous, but decreases in density from its centre to its circumference. Thus the moon's eclipses show the earth to be round, and her inequalities not only determine the form, but the internal structure of our planet; results of analysis which could not have been anticipated. Similar inequalities in the motions of Jupiter's satellites prove that his mass is not homogeneous, and that his compression is $\frac{1}{13\cdot8}$. His equatorial diameter exceeds his polar diameter by about 6000 miles.

The phases[1] of the moon, which vary from a slender silvery crescent soon after conjunction to a complete circle of light in opposition, decrease by the same degrees till the moon is again enveloped in the morning beams of the sun. These changes regulate the returns of the eclipses. Those of the sun can only happen in conjunction, when the moon, coming between the earth and the sun, intercepts his light. Those of the moon are occasioned by the earth intervening between the sun and moon when in opposition. As the earth is opaque and nearly spherical, it throws a conical shadow on the side of the moon opposite to the sun, the axis of which passes through the centres of the sun and earth.[2] The length of the shadow terminates at the point where the apparent diameters[3] of the sun and earth would be the same. When the moon is in opposition, and at her mean distance, the diameter of the sun would be seen from her centre under an angle of 1918″·1. That of the earth would appear under an

[1] Note 106. [2] Note 107. [3] Note 108.

angle of 6908″·3. So that the length of the shadow is at least three times and a half greater than the distance of the moon from the earth, and the breadth of the shadow, where it is traversed by the moon, is about eight thirds of the lunar diameter. Hence the moon would be eclipsed every opposition, were it not for the inclination of her orbit to the plane of the ecliptic, in consequence of which the moon in opposition is either above or below the cone of the earth's shadow, except when in or near her nodes. Her position with regard to them occasions all the varieties in the lunar eclipses. Every point of the moon's surface successively loses the light of different parts of the sun's disc before being eclipsed. Her brightness therefore gradually diminishes before she plunges into the earth's shadow. The breadth of the space occupied by the penumbra[1] is equal to the apparent diameter of the sun, as seen from the centre of the moon. The mean duration of a revolution of the sun, with regard to the node of the lunar orbit, is to the duration of a synodic revolution[2] of the moon as 223 to 19. So that, after a period of 223 lunar months, the sun and moon would return to the same relative position to the node of the moon's orbit, and therefore the eclipses would recur in the same order, were not the periods altered by irregularities in the motions of the sun and moon. In lunar eclipses, our atmosphere bends the sun's rays which pass through it all round into the cone of the earth's shadow. And as the horizontal refraction[3] or bending of the rays surpasses half the sum of the semidiameters of the sun and moon, divided by their mutual distance, the centre of the lunar disc, supposed to be in the axis of the shadow, would receive the rays from the same point

[1] Note 109. [2] Note 110. [3] Note 111.

of the sun, round all sides of the earth, so that it would be more illuminated than in full moon, if the greater portion of the light were not stopped or absorbed by the atmosphere. Instances are recorded where this feeble light has been entirely absorbed, so that the moon has altogether disappeared in her eclipses.

The sun is eclipsed when the moon intercepts his rays.[1] The moon, though incomparably smaller than the sun, is so much nearer the earth, that her apparent diameter differs but little from his, but both are liable to such variations, that they alternately surpass one another. Were the eye of a spectator in the same straight line with the centres of the sun and moon, he would see the sun eclipsed. If the apparent diameter of the moon surpassed that of the sun, the eclipse would be total. If it were less, the observer would see a ring of light round the disc of the moon, and the eclipse would be annular. If the centre of the moon should not be in the straight line joining the centres of the sun and the eye of the observer, the moon might only eclipse a part of the sun. The variation, therefore, in the distances of the sun and moon from the centre of the earth, and of the moon from her node at the instant of conjunction, occasions great varieties in the solar eclipses. Besides, the height of the moon above the horizon changes her apparent diameter, and may augment or diminish the apparent distances of the centres of the sun and moon, so that an eclipse of the sun may occur to the inhabitants of one country, and not to those of another. In this respect the solar eclipses differ from the lunar, which are the same for every part of the earth where the sun and moon are above the horizon. In solar eclipses, the light reflected

[1] Note 112.

by the atmosphere diminishes the obscurity they produce. Even in total eclipses the higher part of the atmosphere is enlightened by a part of the sun's disc, and reflects its rays to the earth. The whole disc of the new moon is frequently visible from atmospheric reflection.

Planets sometimes eclipse one another. On the 17th of May, 1737, Mercury was eclipsed by Venus near their inferior conjunction; Mars passed over Jupiter on the 9th of January, 1591, and on the 30th of October, 1825, the moon eclipsed Saturn. These phenomena, however, happen very seldom, because all the planets, or even a part of them, are very rarely seen in conjunction at once; that is, in the same part of the heavens at the same time. More than 2500 years before our era, the five great planets were in conjunction. On the 15th of September, 1186, a similar assemblage took place between the constellations of Virgo and Libra; and in 1801, the Moon, Jupiter, Saturn, and Venus were united in the heart of the Lion. These conjunctions are so rare, that Lalande has computed that more than seventeen millions of millions of years separate the epochs of the contemporaneous conjunctions of the six great planets.

The motions of the moon have now become of more importance to the navigator and geographer than those of any other heavenly body, from the precision with which terrestrial longitude is determined by the occultations of stars and lunar distances. In consequence of the retrograde motion of the nodes of the lunar orbit, at the rate of $3' 10''\cdot64$ daily, these points make a tour of the heavens in a little more than eighteen years and a half. This causes the moon to move round the earth, in a kind of spiral, so that her disc at different times

passes over every point in a zone of the heavens extending rather more than $5° 9'$ on each side of the ecliptic. It is therefore evident, that at one time or other, she must eclipse every star and planet she meets with in this space. Therefore the occultation of a star by the moon is a phenomenon of frequent occurrence The moon seems to pass over the star, which almost instantaneously vanishes at one side of her disc, and after a short time as suddenly reappears on the other A lunar distance is the observed distance of the moon from the sun, or from a particular star or planet, at any instant. The lunar theory is brought to such perfection, that the times of these phenomena, observed under any meridian, when compared with those computed for Greenwich in the Nautical Almanac, give the longitude of the observer within a few miles [1]

From the lunar theory, the mean distance of the sun from the earth, and thence the whole dimensions of the solar system, are known. For the forces which retain the earth and moon in their orbits are respectively proportional to the radii vectores of the earth and moon, each being divided by the square of its periodic time. And as the lunar theory gives the ratio of the forces, the ratio of the distances of the sun and moon from the earth is obtained. Hence it appears that the sun's mean distance from the earth is 396 or nearly 400 times greater than that of the moon. The method, of finding the absolute distances of the celestial bodies in miles, is in fact the same with that employed in measuring the distances of terrestrial objects. From the extremities of a known base [2], the angles which the visual rays from the object form with it, are measured; their sum subtracted from two right angles gives the

[1] Note 93 [2] Note 113

angle opposite the base, therefore, by trigonometry, all the angles and sides of the triangle may be computed — consequently the distance of the object is found. The angle under which the base of the triangle is seen from the object, is the parallax of that object. It evidently increases and decreases with the distance Therefore the base must be very great indeed to be visible from the celestial bodies The globe itself, whose dimensions are obtained by actual admeasurement, furnishes a standard of measures, with which we compare the distances, masses, densities, and volumes of the sun and planets

SECTION VI.

FORM OF EARTH AND PLANETS.—FIGURE OF A HOMOGENEOUS SPHEROID IN ROTATION.—FIGURE OF A SPHEROID OF VARIABLE DENSITY.—FIGURE OF THE EARTH, SUPPOSING IT TO BE AN ELLIPSOID OF REVOLUTION.—MENSURATION OF A DEGREE OF THE MERIDIAN.—COMPRESSION AND SIZE OF THE EARTH FROM DEGREES OF MERIDIAN.—FIGURE OF EARTH FROM THE PENDULUM.

THE theoretical investigation of the figure of the earth and planets is so complicated, that neither the geometry of Newton, nor the refined analyses of La Place, have attained more than an approximation. It is only within a few years that a complete and finite solution of that difficult problem has been accomplished, by our distinguished countryman Mr Ivory. The investigation has been conducted by successive steps, beginning with a simple case, and then proceeding to the more difficult. But in all, the forces which occasion the revolutions of the earth and planets are omitted, because, by acting equally upon all the particles, they do not disturb their mutual relations. A fluid mass of uniform density, whose particles mutually gravitate to each other, will assume the form of a sphere when at rest. But if the sphere begins to revolve, every particle will describe a circle[1], having its centre in the axis of revolution. The planes of all these circles will be parallel to one another, and perpendicular to the axis, and the particles will have a tendency to fly from that axis, in consequence of the centrifugal force arising from the velocity of rotation. The force of gravity is everywhere perpendicular to the surface[2], and tends to the interior of

[1] Note 114. [2] Note 115.

the fluid mass, whereas the centrifugal force acts perpendicularly to the axis of rotation, and is directed to the exterior. And as its intensity diminishes with the distance from the axis of rotation, it decreases from the equator to the poles, where it ceases. Now it is clear that these two forces are in direct opposition to each other in the equator alone, and that gravity is there diminished by the whole effect of the centrifugal force, whereas, in every other part of the fluid, the centrifugal force is resolved into two parts, one of which, being perpendicular to the surface, diminishes the force of gravity, but the other, being at a tangent to the surface, urges the particles towards the equator, where they accumulate till their numbers compensate the diminution of gravity, which makes the mass bulge at the equator, and become flattened at the poles. It appears, then, that the influence of the centrifugal force is most powerful at the equator, not only because it is actually greater there than elsewhere, but because its whole effect is employed in diminishing gravity, whereas, in every other point of the fluid mass, it is only a resolved part that is so employed. For both these reasons, it gradually decreases towards the poles, where it ceases. On the contrary, gravity is least at the equator, because the particles are farther from the centre of the mass, and increases towards the poles, where it is greatest. It is evident, therefore, that, as the centrifugal force is much less than the force of gravity, — gravitation, which is the difference between the two, is least at the equator, and continually increases towards the poles, where it is a maximum. On these principles Sir Isaac Newton proved, that a homogeneous fluid[1] mass in rotation, assumes the form of an ellipsoid

[1] Note 110

of revolution[1], whose compression is $\frac{1}{230}$. Such, however, cannot be the form of the earth, because the strata increase in density towards the centre. The lunar inequalities also prove the earth to be so constructed; it was requisite, therefore, to consider the fluid mass to be of variable density. Including this condition, it has been found that the mass, when in rotation, would still assume the form of an ellipsoid of revolution; that the particles of equal density would arrange themselves in concentric elliptical strata[2], the most dense being in the centre; but that the compression or flattening would be less than in the case of the homogeneous fluid. The compression is still less when the mass is considered to be, as it actually is, a solid nucleus, decreasing regularly in density from the centre to the surface, and partially covered by the ocean, because the solid parts, by their cohesion, nearly destroy that part of the centrifugal force which gives the particles a tendency to accumulate at the equator, though not altogether; otherwise the sea, by the superior mobility of its particles, would flow towards the equator and leave the poles dry. Besides, it is well known that the continents at the equator, are more elevated than they are in higher latitudes. It is also necessary for the equilibrium of the ocean, that its density should be less than the mean density of the earth, otherwise the continents would be perpetually liable to inundations from storms and other causes. On the whole, it appears, from theory, that a horizontal line passing round the earth, through both poles, must be nearly an ellipse, having its major axis in the plane of the equator, and its minor axis coincident with the axis of the earth's rotation.[3] It is easy to show, in a spheroid whose

[1] Note 117. [2] Note 118. [3] Note 119.

of revolution[1], whose compression is $\frac{1}{230}$. Such, however, cannot be the form of the earth, because the strata increase in density towards the centre. The lunar inequalities also prove the earth to be so constructed; it was requisite, therefore, to consider the fluid mass to be of variable density. Including this condition, it has been found that the mass, when in rotation, would still assume the form of an ellipsoid of revolution; that the particles of equal density would arrange themselves in concentric elliptical strata[2], the most dense being in the centre; but that the compression or flattening would be less than in the case of the homogeneous fluid. The compression is still less when the mass is considered to be, as it actually is, a solid nucleus, decreasing regularly in density from the centre to the surface, and partially covered by the ocean, because the solid parts, by their cohesion, nearly destroy that part of the centrifugal force which gives the particles a tendency to accumulate at the equator, though not altogether; otherwise the sea, by the superior mobility of its particles, would flow towards the equator and leave the poles dry. Besides, it is well known that the continents at the equator are more elevated than they are in higher latitudes. It is also necessary for the equilibrium of the ocean, that its density should be less than the mean density of the earth, otherwise the continents would be perpetually liable to inundations from storms and other causes. On the whole, it appears, from theory, that a horizontal line passing round the earth, through both poles, must be nearly an ellipse, having its major axis in the plane of the equator, and its minor axis coincident with the axis of the earth's rotation[3]. It is easy to show, in a spheroid whose

[1] Note 117. [2] Note 118. [3] Note 119.

strata are elliptical, that the increase in the length of the radii[1], the decrease of gravitation, and the increase in the lengths of the arcs of the meridian, corresponding to angles of one degree, from the poles to the equator, are all proportional to the square of the cosine of the latitude.[2] These quantities are so connected with the ellipticity of the spheroid, that the total increase in the length of the radii is equal to the compression or flattening, and the total diminution in the length of the arcs is equal to the compression, multiplied by three times the length of an arc of one degree at the equator. Hence, by measuring the meridian curvature of the earth, the compression, and consequently its figure, become known. This, indeed, is assuming the earth to be an ellipsoid of revolution, but the actual measurement of the globe will show how far it corresponds with that solid in figure and constitution.

The courses of the great rivers, which are in general navigable to a considerable extent, prove that the curvature of the land differs but little from that of the ocean; and as the heights of the mountains and continents are inconsiderable when compared with the magnitude of the earth, its figure is understood to be determined by a surface at every point perpendicular to the direction of gravitation, or of the plumb-line, and is the same which the sea would have, if it were continued all round the earth beneath the continents. Such is the figure that has been measured in the following manner:—

A terrestrial meridian is a line passing through both poles, all the points of which have their noon contemporaneously. Were the lengths and curvatures of different meridians known, the figure of the earth might

[1] Note 120. [2] Note 121.

be determined. But the length of one degree is sufficient to give the figure of the earth, if it be measured on different meridians, and in a variety of latitudes. For if the earth were a sphere, all degrees would be of the same length, but if not, the lengths of the degrees will be greater, exactly in proportion as the curvature is less. A comparison of the lengths of a degree in different parts of the earth's surface, will therefore determine its size and form.

An arc of the meridian may be measured, by observing the latitude of its extreme points [1], and then measuring the distance between them in feet or fathoms. The distance thus determined on the surface of the earth, divided by the degrees and parts of a degree contained in the difference of the latitudes, will give the exact length of one degree, the difference of the latitudes being the angle contained between the verticals at the extremities of the arc. This would be easily accomplished were the distance unobstructed, and on a level with the sea. But, on account of the innumerable obstacles on the surface of the earth, it is necessary to connect the extreme points of the arc by a series of triangles [2], the sides and angles of which are either measured or computed, so that the length of the arc is ascertained with much laborious computation. In consequence of the irregularities of the surface, each triangle is in a different plane. They must therefore be reduced by computation, to what they would have been had they been measured on the surface of the sea. And as the earth may in this case be esteemed spherical, they require a correction to reduce them to spherical triangles. The gentlemen who conduct the trigonometrical survey, in measuring 500 feet of a base in Ire-

[1] Note 122 [2] Note 123

land twice over, found that the difference in the two measurements did not amount to the 800th part of an inch. Such is the accuracy with which these operations are conducted, and which they require.

Arcs of the meridian have been measured in a variety of latitudes north and south, as well as arcs perpendicular to the meridian. From these measurements it appears, that the lengths of the degrees increase from the equator to the poles, nearly in proportion to the square of the sine of the latitude.[1] Consequently, the convexity of the earth diminishes from the equator to the poles.

Were the earth an ellipsoid of revolution, the meridians would be ellipses whose lesser axes would coincide with the axis of rotation, and all the degrees measured between the pole and the equator would give the same compression when combined two and two. That, however, is far from being the case. Scarcely any of the measurements give exactly the same results, chiefly on account of local attractions, which cause the plumb-line to deviate from the vertical. The vicinity of mountains has that effect. But one of the most remarkable, though not unprecedented anomalies, takes place in the plains in the north of Italy, where the action of some dense subterraneous matter, causes the plumb-line to deviate seven or eight times more than it did from the attraction of Chimborazo during the experiments of Bouguer, while measuring a degree of the meridian at the equator. In consequence of this local attraction, the degrees of the meridian in that part of Italy, seem to increase towards the equator through a small space, instead of decreasing, as if the earth was drawn out at the poles, instead of being flattened.

Many other discrepances occur, but from the mean

[1] Note 121.

of the five principal measurements of arcs in Peru, India, France, England, and Lapland, Mr. Ivory has deduced that the figure which most nearly follows this law is an ellipsoid of revolution whose equatorial radius is 3962·824 miles, and the polar radius 3949·585 miles. The difference, or 13·239 miles, divided by the equatorial radius, is $\frac{1}{300}$ nearly. This fraction is called the compression of the earth, because, according as it is greater or less, the terrestrial ellipsoid is more or less flattened at the poles. It does not differ much from that given by the lunar inequalities. If we assume the earth to be a sphere, the length of a degree of the meridian is $69\frac{1}{22}$ British miles. Therefore, 360 degrees, or the whole circumference of the globe, is 24,856 miles, and the diameter, which is something less than a third of the circumference, is about 7912 or 8000 miles nearly. Eratosthenes, who died 194 years before the Christian era, was the first to give an approximate value of the earth's circumference, by the measurement of an arc between Alexandria and Syene.

There is another method of finding the figure of the earth, totally different from the preceding, and only depending upon the increase of gravitation from the equator to the pole. The force of gravitation at any place, is measured by the descent of a heavy body during the first second of its fall. And the intensity of the centrifugal force, is measured by the deflection of any point from the tangent in a second. For, since the centrifugal force balances the attraction of the earth, it is an exact measure of the gravitating force. Were the attraction to cease, a body on the surface of the earth would fly off in the tangent by the centrifugal force, instead of bending round in the circle of rotation. Therefore, the deflection of the circle from the tangent

during any given time, such as a second, measures the intensity of the earth's attraction, and is equal to the versed sine of the arc described during that time, a quantity easily determined from the known velocity of the earth's rotation. Whence it has been found, that at the equator the centrifugal force is equal to the 289th part of gravity. Now, it is proved by analysis, that whatever the constitution of the earth and planets may be, if the intensity of gravitation at the equator be taken equal to unity, the sum of the compression of the ellipsoid, and the whole increase of gravitation from the equator to the pole, is equal to five halves of the ratio of the centrifugal force to gravitation at the equator. This quantity with regard to the earth is $\frac{5}{2}$ of $\frac{1}{289}$, or $\frac{1}{115.6}$. Consequently, the compression of the earth is equal to $\frac{1}{115.6}$ diminished by the whole increase of gravitation. So that its form will be known, if the whole increase of gravitation from the equator to the pole, can be determined by experiment. This has been accomplished by a method founded upon the following considerations.—If the earth were a homogeneous sphere without rotation, its attraction on bodies at its surface would be everywhere the same. If it be elliptical and of variable density, the force of gravity, theoretically, ought to increase from the equator to the pole, as unity *plus* a constant quantity multiplied into the square of the sine of the latitude.[1] But for a spheroid in rotation, the centrifugal force varies, by the laws of mechanics, as the square of the sine of the latitude, from the equator, where it is greatest, to the pole, where it vanishes. And as it tends to make bodies fly off the surface, it diminishes the force of gravity by a small quantity. Hence, by gravitation, which is the differ-

[1] Note 124.

ence of these two forces, the fall of bodies ought to be accelerated from the equator to the poles, proportionably to the square of the sine of the latitude; and the weight of the same body ought to increase in that ratio. This is directly proved by the oscillations of the pendulum[1], which, in fact, is a falling body; for if the fall of bodies be accelerated, the oscillations will be more rapid: in order, therefore, that they may always be performed in the same time, the length of the pendulum must be altered. By numerous and careful experiments, it is proved that a pendulum which oscillates 86,400 times in a mean day at the equator, will do the same at every point of the earth's surface, if its length be increased progressively to the pole, as the square of the sine of the latitude.

From the mean of these it appears that the whole decrease of gravitation from the poles to the equator is 0.0051449, which, subtracted from $\frac{1}{115.2}$, shows that the compression of the terrestrial spheroid is about $\frac{1}{285.26}$. This value has been deduced by Mr. Baily, President of the Astronomical Society, who has devoted much attention to this subject; at the same time, it may be observed, that no two sets of pendulum experiments give the same result, probably from local attractions. Therefore, the question cannot be considered as definitively settled, though the differences are very small. The compression obtained by this method does not differ much from that given by the lunar inequalities, nor from the arcs in the direction of the meridian, and those perpendicular to it. The near coincidence of these three values, deduced by methods so entirely independent of each other, shows that the mutual tendencies of the centres of the celestial bodies to one

[1] Note 125

another, and the attraction of the earth for bodies at its surface, result from the reciprocal attraction of all their particles. Another proof may be added. The nutation of the earth's axis, and the precession of the equinoxes[1], are occasioned by the action of the sun and moon on the protuberant matter at the earth's equator. And although these inequalities do not give the absolute value of the terrestrial compression, they show that the fraction expressing it is comprised between the limits $\frac{1}{370}$ and $\frac{1}{571}$.

It might be expected that the same compression should result from each, if the different methods of observation could be made without error. This, however, is not the case; for, after allowance has been made for every cause of error, such discrepancies are found, both in the degrees of the meridian and in the length of the pendulum, as show that the figure of the earth is very complicated. But they are so small, when compared with the general results, that they may be disregarded. The compression deduced from the mean of the whole appears not to differ much from $\frac{1}{300}$; that given by the lunar theory has the advantage, of being independent of the irregularities of the earth's surface and of local attractions. The regularity with which the observed variation in the length of the pendulum, follows the law of the square of the sine of the latitude, proves the strata to be elliptical, and symmetrically disposed round the centre of gravity of the earth, which affords a strong presumption in favour of its original fluidity. It is remarkable how little influence the sea has, on the variation of the lengths of the arcs of the meridian or on gravitation; neither does it much affect the lunar inequalities, from its density being only about a fifth of

[1] Note 141.

the mean density of the earth. For, if the earth were to become fluid after being stripped of the ocean, it would assume the form of an ellipsoid of revolution whose compression is $\frac{1}{3018}$, which differs very little from that determined by observation, and proves, not only that the density of the ocean is inconsiderable, but that its mean depth is very small. There may be profound cavities in the bottom of the sea, but its mean depth probably does not much exceed the mean height of the continents and islands above its level. On this account, immense tracts of land may be deserted or overwhelmed by the ocean, as appears really to have been the case, without any great change in the form of the terrestrial spheroid. The variation in the length of the pendulum was first remarked by Richter in 1672, while observing transits of the fixed stars across the meridian at Cayenne, about five degrees north of the equator He found that his clock lost at the rate of $2^m\ 28^s$ daily, which induced him to determine the length of a pendulum beating seconds in that latitude, and repeating the experiments on his return to Europe, he found the seconds pendulum at Paris, to be more than the twelfth of an inch longer than that at Cayenne. The form and size of the earth being determined, it furnishes a standard of measure with which the dimensions of the solar system may be compared.

SECTION VII.

PARALLAX.—LUNAR PARALLAX FOUND FROM DIRECT OBSERVATION.—SOLAR PARALLAX DEDUCED FROM THE TRANSIT OF VENUS.—DISTANCE OF THE SUN FROM THE EARTH.—ANNUAL PARALLAX.—DISTANCE OF THE FIXED STARS.

THE parallax of a celestial body is the angle under which the radius of the earth would be seen, if viewed from the centre of that body; it affords the means of ascertaining the distances of the sun, moon, and planets.[1] When the moon is in the horizon at the instant of rising or setting, suppose lines to be drawn from her centre to the spectator and to the centre of the earth; these would form a right-angled triangle with the terrestrial radius, which is of a known length; and as the parallax or angle at the moon can be measured, all the angles and one side are given; whence the distance of the moon from the centre of the earth may be computed. The parallax of an object may be found, if two observers under the same meridian, but at a very great distance from one another, observe its zenith distances on the same day at the time of its passage over the meridian. By such contemporaneous observations at the Cape of Good Hope and at Berlin, the mean horizontal parallax of the moon was found to be 3459″, whence the mean distance of the moon is about sixty times the mean terrestrial radius, or 237,360 miles nearly. Since the parallax is equal to the radius of the earth divided by the distance of the moon, it varies with the distance of the moon from the earth under the same parallel of latitude, and proves the ellipticity of the lunar orbit.

[1] Note 126.

When the moon is at her mean distance, it varies with the terrestrial radii, thus showing that the earth is not a sphere [1]

Although the method described is sufficiently accurate for finding the parallax of an object so near as the moon, it will not answer for the sun, which is so remote that the smallest error in observation would lead to a false result But that difficulty is obviated by the transits of Venus When that planet is in her nodes [2], or within $1\frac{1}{4}^{\circ}$ of them, that is, in, or nearly in, the plane of the ecliptic, she is occasionally seen to pass over the sun like a black spot If we could imagine that the sun and Venus had no parallax, the line described by the planet on his disc and the duration of the transit would be the same to all the inhabitants of the earth. But as the semi-diameter of the earth has a sensible magnitude when viewed from the centre of the sun, the line described by the planet in its passage over his disc appears to be nearer to his centre, or farther from it, according to the position of the observer; so that the duration of the transit varies with the different points of the earth's surface at which it is observed.[3] This difference of time, being entirely the effect of parallax, furnishes the means of computing it from the known motions of the earth and Venus, by the same method as for the eclipses of the sun. In fact, the ratio of the distances of Venus and the sun from the earth at the time of the transit are known from the theory of their elliptical motion. Consequently the ratio of the parallaxes of these two bodies, being inversely as their distances, is given; and as the transit gives the difference of the parallaxes, that of the sun is obtained. In 1769, the parallax of the sun was determined by observations of a transit of Venus made

[1] Note 127. [2] Note 128. [3] Note 129.

at Wardhus in Lapland, and at Otaheite in the South Sea. The latter observation was the object of Cook's first voyage. The transit lasted about six hours at Otaheite, and the difference in duration at these two stations was eight minutes, whence the sun's horizontal parallax was found to be 8″ 72 But by other considerations it has been reduced to 8″ 5776, from which the mean distance of the sun appears to be about 95,070,500 miles, or ninety-five millions of miles nearly This is confirmed by an inequality in the motion of the moon, which depends upon the parallax of the sun, and which, when compared with observation, gives 8″ 6 for the sun's parallax

The parallax of Venus is determined by her transits, that of Mars by direct observation, and it is found to be nearly double that of the sun, when the planet is in opposition. The distances of these two planets from the earth are therefore known in terrestrial radii, consequently their mean distances from the sun may be computed, and as the ratios of the distances of the planets from the sun, are known by Kepler's law of the squares of the periodic times of any two planets being as the cubes of their mean distances from the sun, their absolute distances in miles are easily found [1] This law is very remarkable, in thus uniting all the bodies of the system, and extends to the satellites as well as the planets.

Far as the earth seems to be from the sun, Uranus is no less than nineteen times farther. Situate on the verge of the system, the sun must appear to it not much larger than Venus does to us. The earth cannot even be visible as a telescopic object to a body so remote. Yet man, the inhabitant of the earth, soars beyond the vast dimensions of the system to which his planet belongs, and

[1] Note 130

assumes the diameter of its orbit as the base of a triangle, whose apex extends to the stars.

Sublime as the idea is, this assumption proves ineffectual, for the apparent places of the fixed stars are not sensibly changed by the earth's annual revolution With the aid derived from the refinements of modern astronomy, and of the most perfect instruments, it is still a matter of doubt, whether a sensible parallax has been detected even in the nearest of these remote suns. If a fixed star had the parallax of one second, it would be 215,789 times farther from the sun than the earth is. At such a distance not only the terrestrial orbit shrinks to a point, but the whole solar system seen in the focus of the most powerful telescope, might be covered by the thickness of a spider's thread. Light flying at the rate of 200,000 miles in a second, would take three years and seven days to travel over that space One of the nearest stars may therefore have been kindled or extinguished more than three years, before we could have been aware of so mighty an event. But this distance must be small, when compared with that of the most remote of the bodies which are visible in the heavens. The fixed stars are undoubtedly luminous like the sun, it is therefore probable that they are not nearer to one another than the sun is to the nearest of them In the milky way and the other starry nebulæ, some of the stars that seem to us to be close to others, may be far behind them in the boundless depth of space, nay, may be rationally supposed to be situate many thousand times farther off. Light would therefore require thousands of years to come to the earth from those myriads of suns, of which our own is but "the dim and remote companion."

SECTION VIII.

MASSES OF PLANETS THAT HAVE NO SATELLITES DETERMINED FROM THEIR PERTURBATIONS.—MASSES OF THE OTHERS OBTAINED FROM THE MOTIONS OF THEIR SATELLITES.—MASSES OF THE SUN, THE EARTH, OF JUPITER, AND OF THE JOVIAL SYSTEM.—MASS OF THE MOON.—REAL DIAMETERS OF PLANETS, HOW OBTAINED.—SIZE OF SUN.—DENSITIES OF THE HEAVENLY BODIES.—FORMATION OF ASTRONOMICAL TABLES.—REQUISITE DATA AND MEANS OF OBTAINING THEM.

THE masses of such planets as have no satellites, are known by comparing the inequalities they produce in the motions of the earth and of each other, determined theoretically, with the same inequalities given by observation; for the disturbing cause must necessarily be proportional to the effect it produces. The masses of the satellites themselves may also be compared with that of the sun by their perturbations. Thus, it is found, from the comparison of a vast number of observations, with La Place's theory of Jupiter's satellites, that the mass of the sun is no less than 65,000,000 times greater than the least of these moons. But as the quantities of matter in any two primary planets, are directly as the cubes of the mean distances at which their satellites revolve, and inversely as the squares of their periodic times[1], the mass of the sun and of any planets which have satellites, may be compared with the mass of the earth. In this manner it is computed that the mass of the sun is 354,936 times that of the earth; whence the great perturbations of the moon, and the rapid motion of the perigee and nodes of her orbit. Even Jupiter, the largest of the planets, has recently been found by

[1] Note 131.

Professor Airy to be 1048·69 times less than the sun, and, indeed, the mass of the whole Jovial System is not more than the 1047·7th part of that of the sun So that the mass of the satellites bears a very small proportion to that of their primary The mass of the moon is determined from several sources,—from her action on the terrestrial equator, which occasions the nutation in the axis of rotation, from her horizontal parallax, from an inequality she produces in the sun's longitude, and from her action on the tides The three first quantities, computed from theory and compared with their observed values, give her mass respectively equal to the $\frac{1}{71}$, $\frac{1}{74 \cdot 2}$, and $\frac{1}{69 \cdot 2}$ part of that of the earth, which do not differ much from each other Dr Brinkley, Bishop of Cloyne, has found it to be $\frac{1}{80}$ from the constant of lunar nutation, but from the moon's action in raising the tides, her mass appears to be about the seventy-fifth part of that of the earth, a value that cannot differ much from the truth

The apparent diameters of the sun, moon, and planets are determined by measurement, therefore their real diameters may be compared with that of the earth, for the real diameter of a planet, is to the real diameter of the earth, or 7912 miles, as the apparent diameter of the planet to the apparent diameter of the earth as seen from the planet, that is, to twice the parallax of the planet. The mean apparent diameter of the sun is 1922″·8, and with the solar parallax 8″·5776, it will be found that the diameter of the sun is about 886,800 miles Therefore if the centre of the sun were to coincide with the centre of the earth, his volume would not only include the orbit of the moon, but would extend nearly as far again, for the moon's

mean distance from the earth is about sixty times the earth's mean radius, or 237,360 miles: so that twice the distance of the moon is 474,720 miles, which differs but little from the solar radius; his equatorial radius is probably not much less than the major axis of the lunar orbit. The diameter of the moon is only 2160 miles; and Jupiter's diameter of 87,000 miles is very much less than that of the sun; the diameter of Pallas does not much exceed 79 miles, so that an inhabitant of that planet, in one of our steam carriages, might go round his world in a few hours.

The densities of bodies are proportional to their masses, divided by their volumes. Hence, if the sun and planets be assumed to be spheres, their volumes will be as the cubes of their diameters. Now, the apparent diameters of the sun and earth, at their mean distance, are 1922″·8 and 17″·1552, and the mass of the earth is the 354,936th part of that of the sun taken as the unit. It follows, therefore, that the earth is nearly four times as dense as the sun. But the sun is so large, that his attractive force would cause bodies to fall through about 334·65 feet in a second. Consequently, if he were habitable by human beings, they would be unable to move, since their weight would be thirty times as great as it is here. A man of moderate size would weigh about two tons at the surface of the sun; whereas, at the surface of the four new planets, he would be so light, that it would be impossible to stand steady, since he would only weigh a few pounds. All the planets and satellites appear to be of less density than the earth. The motions of Jupiter's satellites show that his density increases towards his centre. Were his mass homogeneous, his equatorial and polar axes would be in the ratio of 41 to 36, whereas they are

observed to be only as 41 to 38. The singular irregularities in the form of Saturn, and the great compression of Mars, prove the internal structure of these two planets to be very far from uniform.

Before entering on the theory of rotation, it may not be thought foreign to the subject, to give some idea of the methods of computing the places of the planets, and of forming astronomical tables. Astronomy is now divided into the three distinct departments, of theory, observation, and computation. Since the problem of the three bodies can only be solved by approximation, the analytical astronomer determines the position of a planet in space, by a series of corrections. Its place in its circular orbit is first found, then the addition or subtraction of the equation of the centre to or from its mean place, gives its position in the ellipse. This again is corrected by the application of the principal periodic inequalities. But as these are determined for some particular position of the three bodies, they require to be corrected to suit other relative positions. This process is continued till the corrections become less than the errors of observation, when it is obviously unnecessary to carry the approximation further. The true latitude and distance of the planet from the sun are obtained, by methods similar to those employed for the longitude.

Since the earth revolves equably about its axis in 24 hours, at the rate of 15° in an hour, time becomes a measure of angular motion, and the principal element in astronomy, where the object is to determine the exact state of the heavens, and the successive changes it undergoes in all ages, past, present, and to come. Now the longitude, latitude, and distance of a planet from the sun, are given in terms of the time, by general

analytical formulæ. These formulæ will consequently give the exact place of the body in the heavens, for any time assumed at pleasure, provided they can be reduced to numbers. But before the calculator begins his task, the observer must furnish the necessary data, which are obviously, the forms of the orbits, and their positions with regard to the plane of the ecliptic[1] It is therefore necessary to determine by observation for each planet, the length of the major axis of its orbit, the excentricity, the inclination of the orbit to the plane of the ecliptic, the longitudes of its perihelion and ascending node at a given time, the periodic time of the planet, and its longitude at any instant arbitrarily assumed, as an origin from whence all its subsequent and antecedent longitudes are estimated. Each of these quantities is determined from that position of the planet on which it has most influence For example, the sum of the greatest and least distances of the planet from the sun is equal to the major axis of the orbit, and their difference is equal to the excentricity. The longitude of the planet when at its least distance from the sun, is the same with the longitude of the perihelion; the greatest latitude of the planet is equal to the inclination of the orbit; the longitude of the planet, when in the plane of the ecliptic in passing towards the north, is the longitude of the ascending node, and the periodic time is the interval between two consecutive passages of the planet through the same node, a small correction being made for the precession of the node, during the revolution of the planet.[2] But, notwithstanding the excellence of instruments and the accuracy of the modern observers, the unavoidable errors

[1] Note 56 [2] Note 132

of observation can only be compensated by finding the value of each element from the mean of, perhaps, a thousand, or even many thousands of observations. For as it is probable that the errors are not all in one direction, but that some are in excess and others in defect, they will compensate each other when combined.

However, the values of the elements determined separately can only be regarded as approximate, because they are so connected, that the estimation of any one independently, will induce errors in the others. The excentricity depends upon the longitude of the perihelion, the mean motion depends upon the major axis, the longitude of the node upon the inclination of the orbit, and *vice versâ*. Consequently, the place of a planet computed with the approximate data will differ from its observed place. Then, the difficulty is to ascertain what elements are most in fault, since the difference in question is the error of all; but that is obviated by finding the errors of some thousands of observations, and combining them, so as to correct the elements simultaneously, and to make the sum of the squares of the errors a minimum with regard to each element.[1] The method of accomplishing this depends upon the Theory of Probabilities; a subject fertile in most important results in the various departments of science and of civil life, and quite indispensable in the determination of astronomical data. A series of observations continued for some years, will give approximate values of the secular and periodic inequalities, which must be corrected from time to time, till theory and observation agree. And these again will give values of the masses of the bodies forming the solar system, which are important data in computing their motions. When all these quanti-

[1] Note 189.

ties are determined in numbers, the longitude, latitude, and distances of the planet from the sun are computed for stated intervals, and formed into tables, arranged according to the time estimated from a given epoch, so that the place of the body may be determined from them by inspection alone, at any instant, for perhaps a thousand years before and after that epoch. By this tedious process, tables have been computed for eleven planets, besides the moon and the satellites of Jupiter. Those of the four new planets are astonishingly perfect, considering that these bodies have not been discovered more than thirty years, and a much longer time is requisite to develope their inequalities

SECTION IX.

ROTATION OF THE SUN AND PLANETS.—SATURN'S RINGS.—PERIODS OF THE ROTATION OF THE MOON AND OTHER SATELLITES EQUAL TO THE PERIODS OF THEIR REVOLUTIONS.—FORM OF LUNAR SPHEROID.—LIBRATION, ASPECT, AND CONSTITUTION OF THE MOON.—ROTATION OF JUPITER'S SATELLITES.

THE oblate form of several of the planets indicates rotatory motion. This has been confirmed, in most cases, by tracing spots on their surface, by which their poles and times of rotation have been determined. The rotation of Mercury is unknown, on account of his proximity to the sun; and that of the new planets has not yet been ascertained. The sun revolves in twenty-five days and ten hours about an axis which is directed towards a point half-way between the pole-star and Lyra, the plane of rotation being inclined by 7° 30′, or a little more than seven degrees, to the plane of the ecliptic: it may therefore be concluded that the sun's mass is a spheroid, flattened at the poles. From the rotation of the sun, there is every reason to believe that he has a progressive motion in space, although the direction to which he tends is unknown. But, in consequence of the reaction of the planets, he describes a small irregular orbit about the centre of gravity of the system, never deviating from his position by more than twice his own diameter, or a little more than seven times the distance of the moon from the earth. The sun and all his attendants rotate from west to east, on axes that remain nearly parallel to themselves[1] in every point of their orbit, and with angular velocities that are sensibly uniform.[2] Although the uniformity

[1] Note 134. [2] Note 135.

in the direction of their rotation is a circumstance hitherto unaccounted for in the economy of nature, yet from the design and adaptation of every other part to the perfection of the whole, a coincidence so remarkable cannot be accidental And as the revolutions of the planets and satellites are also from west to east, it is evident that both must have arisen from the primitive cause which has determined the planetary motions. Indeed, La Place has computed the probability to be as four millions to one, that all the motions of the planets, both of rotation and revolution, were at once imparted by an original common cause, but of which we know neither the nature nor the epoch.

The larger planets rotate in shorter periods than the smaller planets and the earth. Their compression is consequently greater, and the action of the sun and of their satellites occasions a nutation in their axes, and a precession of their equinoxes[1] similar to that which obtains in the terrestrial spheroid, from the attraction of the sun and moon on the prominent matter at the equator. Jupiter revolves in less than ten hours about an axis at right angles to certain dark belts, or bands, which always cross his equator. This rapid rotation occasions a very great compression in his form. His equatorial axis exceeds his polar axis by 6000 miles, whereas the difference in those of the earth is only about twenty-six and a half It is an evident consequence of Kepler's law of the squares of the periodic times of the planets being as the cubes of the major axes of their orbits, that the heavenly bodies move slower the farther they are from the sun In comparing the periods of the revolutions of Jupiter and Saturn with the times of their rotation, it appears that a year of Jupiter contains

[1] Note 142.

nearly ten thousand of his days, and that of Saturn about thirty thousand Saturnian days.

The appearance of Saturn is unparalleled in the system of the world. He is a spheroid nearly 1000 times larger than the earth, surrounded by a ring even brighter than himself, which always remains suspended in the plane of his equator; and, viewed with a very good telescope, it is found to consist of two concentric rings, divided by a dark band. The mean distance of the interior part of this double ring from the surface of the planet is about 22,240 miles, it is no less than 33,360 miles broad, but, by the estimation of Sir John Herschel, its thickness does not much exceed 100 miles, so that it appears like a plane. By the laws of mechanics, it is impossible that this body can retain its position by the adhesion of its particles alone. It must necessarily revolve with a velocity that will generate a centrifugal force sufficient to balance the attraction of Saturn. Observation confirms the truth of these principles, showing that the rings rotate about the planet in ten hours and a half, which is considerably less than the time a satellite would take to revolve about Saturn at the same distance. Their plane is inclined to the ecliptic, at an angle of 28° 39′ 45″; and, in consequence of this obliquity of position, they always appear elliptical to us, but with an eccentricity so variable, as even to be occasionally like a straight line drawn across the planet. In the beginning of October, 1832, the plane of the rings passed through the centre of the earth; in that position they are only visible with very superior instruments, and appear like a fine line across the disc of Saturn. About the middle of December, in the same year, the rings became invisible, with ordinary instruments, on account of their plane passing through the sun. In the

end of April, 1833, the rings vanished a second time, and re-appeared in June of that year

It is a singular result of theory, that the rings could not maintain their stability of rotation if they were every where of uniform thickness, for the smallest disturbance would destroy the equilibrium, which would become more and more deranged, till, at last, they would be precipitated on the surface of the planet. The rings of Saturn must therefore be irregular solids, of unequal breadth in different parts of the circumference, so that their centres of gravity do not coincide with the centres of their figures Professor Struve has also discovered that the centre of the ring is not concentric with the centre of Saturn. The interval between the outer edge of the globe of the planet, and the outer edge of the ring on one side, is 11″ 073, and, on the other side, the interval is 11″ 288, consequently there is an excentricity of the globe in the ring of 0″·215. If the rings obeyed different forces, they would not remain in the same plane, but the powerful attraction of Saturn always maintains them and his satellites in the plane of his equator. The rings, by their mutual action, and that of the sun and satellites, must oscillate about the centre of Saturn, and produce phenomena of light and shadow whose periods extend to many years.

The periods of rotation of the moon and the other satellites are equal to the times of their revolutions, consequently these bodies always turn the same face to their primaries. However, as the mean motion of the moon is subject to a secular inequality, which will ultimately amount to many circumferences [1], if the rotation of the moon were perfectly uniform, and not affected

[1] Note 105.

by the same inequalities, it would cease exactly to counterbalance the motion of revolution; and the moon, in the course of ages, would successively and gradually discover every point of her surface to the earth. But theory proves that this never can happen; for the rotation of the moon, though it does not partake of the periodic inequalities of her revolution, is affected by the same secular variations, so that her motions of rotation and revolution round the earth will always balance each other, and remain equal. This circumstance arises from the form of the lunar spheroid, which has three principal axes of different lengths at right angles to each other.

The moon is flattened at her poles from her centrifugal force, therefore her polar axis is the least. The other two are in the plane of her equator, but that directed towards the earth is the greatest.[1] The attraction of the earth, as if it had drawn out that part of the moon's equator, constantly brings the greatest axis, and consequently the same hemisphere, towards us, which makes her rotation participate in the secular variations in her mean motion of revolution. Even if the angular velocities of rotation and revolution had not been nicely balanced in the beginning of the moon's motion, the attraction of the earth would have recalled the greatest axis to the direction of the line joining the centres of the moon and earth; so that it would have vibrated on each side of that line, in the same manner as a pendulum oscillates on each side of the vertical from the influence of gravitation. No such libration is perceptible; and as the smallest disturbance would make it evident, it is clear that, if the moon has ever been touched by a comet, the mass of the latter must

[1] Note 157.

have been extremely small If it had been only the hundred thousandth part of that of the earth, it would have rendered the libration sensible. According to analysis, a similar libration exists in the motions of Jupiter's satellites, which still remains insensible to observation.

It is true the moon is liable to librations depending upon the position of the spectator. At her rising, part of the western edge of her disc is visible, which is invisible at her setting, and the contrary takes place with regard to her eastern edge. There are also librations arising from the relative positions of the earth and moon in their respective orbits, but as they are only optical appearances, one hemisphere will be eternally concealed from the earth. For the same reason, the earth, which must be so splendid an object to one lunar hemisphere, will be for ever veiled from the other. On account of these circumstances, the remoter hemisphere of the moon has its day a fortnight long, and a night of the same duration, not even enlightened by a moon, while the favoured side is illuminated by the reflection of the earth during its long night. A planet exhibiting a surface thirteen times larger than that of the moon, with all the varieties of clouds, land, and water coming successively into view, must be a splendid object to a lunar traveller in a journey to his antipodes. The great height of the lunar mountains probably has a considerable influence on the phenomena of her motion, the more so as her compression is small, and her mass considerable In the curve passing through the poles, and that diameter of the moon which always points to the earth, nature has furnished a permanent meridian, to which the different spots on her surface have been referred, and their positions are determined with as much

accuracy, as those of many of the most remarkable places on the surface of our globe.

The distance and minuteness of Jupiter's satellites render it extremely difficult to ascertain their rotation. It was, however, accomplished by Sir William Herschel from their relative brightness He observed that they alternately exceed each other in brilliancy, and, by comparing the maxima and minima of their illumination with their positions relatively to the sun and to their primary, he found that, like the moon, the time of their rotation is equal to the period of their revolution about Jupiter. Miraldi was led to the same conclusion with regard to the fourth satellite, from the motion of a spot on its surface.

SECTION X.

ROTATION OF THE EARTH INVARIABLE.—DECREASE IN THE EARTH'S MEAN TEMPERATURE.—EARTH ORIGINALLY IN A STATE OF FUSION.—LENGTH OF DAY CONSTANT.—DECREASE OF TEMPERATURE ASCRIBED BY SIR JOHN HERSCHEL TO THE VARIATION IN THE EXCENTRICITY OF THE TERRESTRIAL ORBIT.—DIFFERENCE IN THE TEMPERATURE OF THE TWO HEMISPHERES, ERRONEOUSLY ASCRIBED TO THE EXCESS IN THE LENGTH OF SPRING AND SUMMER IN THE SOUTHERN HEMISPHERE, ATTRIBUTED BY MR. LYELL TO THE OPERATION OF EXISTING CAUSES.—THREE PRINCIPAL AXES OF ROTATION.—POSITION OF THE AXIS OF ROTATION ON THE SURFACE OF THE EARTH INVARIABLE.—OCEAN NOT SUFFICIENT TO RESTORE THE EQUILIBRIUM OF THE EARTH IF DERANGED.—ITS DENSITY AND MEAN DEPTH.—INTERNAL STRUCTURE OF THE EARTH.

THE rotation of the earth, which determines the length of the day, may be regarded as one of the most important elements in the system of the world. It serves as a measure of time, and forms the standard of comparison for the revolutions of the celestial bodies, which, by their proportional increase or decrease, would soon disclose any changes it might sustain. Theory and observation concur in proving that, among the innumerable vicissitudes which prevail throughout creation, the period of the earth's diurnal rotation is immutable. The water of rivers, falling from a higher to a lower level, carries with it the velocity due to its revolution with the earth, at a greater distance from the centre, it will therefore accelerate, although to an almost infinitesimal extent, the earth's daily rotation. The sum of all these increments of velocity, arising from the descent of all the rivers on the earth's surface, would in time become perceptible, did not nature, by the process of evaporation, raise the

waters back to their sources, and thus, by again removing matter to a greater distance from the centre, destroy the velocity generated by its previous approach; so that the descent of rivers does not affect the earth's rotation. Enormous masses projected by volcanos from the equator to the poles, and the contrary, would, indeed, affect it, but there is no evidence of such convulsions. The disturbing action of the moon and planets, which has so powerful an effect on the revolution of the earth, in no way influences its rotation. The constant friction of the trade-winds on the mountains and continents between the tropics does not impede its velocity, which theory even proves to be the same, as if the sea together with the earth, formed one solid mass. But although these circumstances be inefficient, a variation in the mean temperature would certainly occasion a corresponding change in the velocity of rotation. In the science of dynamics, it is a principle in a system of bodies, or of particles revolving about a fixed centre, that the momentum, or sum of the products of the mass of each into its angular velocity and distance from the centre, is a constant quantity, if the system be not deranged by a foreign cause. Now, since the number of particles in the system is the same, whatever its temperature may be, when their distances from the centre are diminished, their angular velocity must be increased, in order that the preceding quantity may still remain constant. It follows then, that, as the primitive momentum of rotation with which the earth was projected into space must necessarily remain the same, the smallest decrease in heat, by contracting the terrestrial spheroid, would accelerate its rotation, and consequently diminish the length of the day. Notwithstanding the constant accession of heat from the sun's rays, geologists have been

induced to believe, from the fossil remains, that the mean temperature of the globe is decreasing.

The high temperature of mines, hot springs, and, above all, the internal fires which have produced and do still occasion such devastation on our planet, indicate an augmentation of heat towards its centre. The increase of density, corresponding to the depth and the form of the spheroid, being what theory assigns to a fluid mass in rotation, concur to induce the idea that the temperature of the earth was originally so high, as to reduce all the substances of which it is composed to a state of fusion, or of vapour, and that in the course of ages, it has cooled down to its present state, that it is still becoming colder, and that it will continue to do so, till the whole mass arrives at the temperature of the medium in which it is placed, or, rather, at a state of equilibrium between this temperature, the cooling power of its own radiation, and the heating effect of the sun's rays

Previous to the formation of ice at the poles, the ancient lands of northern latitudes might, no doubt, have been capable of producing those tropical plants preserved in the coal measures, if indeed such plants could flourish without the intense light of a tropical sun. But, even if the decreasing temperature of the earth be sufficient to produce the observed effects, it must be extremely slow in its operation; for, in consequence of the rotation of the earth being a measure of the periods of the celestial motions, it has been proved that, if the length of the day had decreased by the three thousandth part of a second since the observations of Hipparchus two thousand years ago, it would have diminished the secular equation of the moon by 4″·4. It is therefore beyond a doubt that the mean temperature of

the earth cannot have sensibly varied during that time. If, then, the appearances exhibited by the strata are really owing to a decrease of internal temperature, it either shows the immense periods requisite to produce geological changes, to which two thousand years are as nothing, or that the mean temperature of the earth had arrived at a state of equilibrium before these observations.

However strong the indications of the primitive fluidity of the earth, as there is no direct proof of it, the hypothesis can only be regarded as very probable. But one of the most profound philosophers and elegant writers of modern times, has found in the secular variation of the excentricity of the terrestrial orbit, an evident cause of decreasing temperature. That accomplished author, in pointing out the mutual dependences of phenomena, says, "It is evident that the mean temperature of the whole surface of the globe, in so far as it is maintained by the action of the sun at a higher degree than it would have were the sun extinguished, must depend on the mean quantity of the sun's rays which it receives, or—which comes to the same thing—on the total quantity received in a given invariable time; and the length of the year being unchangeable in all the fluctuations of the planetary system, it follows that the total amount of solar radiation will determine, *cæteris paribus*, the general climate of the earth. Now, it is not difficult to show that this amount is inversely proportional to the minor axis of the ellipse described by the earth about the sun[1], regarded as slowly variable; and that, therefore, the major axis remaining, as we know it to be, constant, and the orbit being actually

[1] Note 138

in a state of approach to a circle, and consequently the minor axis being on the increase, the mean annual amount of solar radiation received by the whole earth, must be actually on the decrease. We have therefore an evident real cause to account for the phenomenon." The limits of the variation in the excentricity of the earth's orbit are unknown. But if its ellipticity has ever been as great as that of the orbit of Mercury or Pallas, the mean temperature of the earth must have been sensibly higher than it is at present. Whether it was great enough to render our northern climates fit for the production of tropical plants, and for the residence of the elephant and other animals now inhabitants of the torrid zone, it is impossible to say.

Of the decrease in temperature of the northern hemisphere, there is abundant evidence in the fossil plants discovered in very high latitudes, which could only have existed in a tropical climate, and which must have grown near the spot where they are found, from the delicacy of their structure and the perfect state of their preservation. This change of temperature has been erroneously ascribed to an excess in the duration of spring and summer in the northern hemisphere, in consequence of the excentricity of the solar ellipse. The length of the seasons varies with the position of the perihelion[1] of the earth's orbit, for two reasons. On account of the excentricity, small as it is, any line passing through the centre of the sun divides the terrestrial ellipse into two unequal parts, and, by the laws of elliptical motion, the earth moves through these two portions with unequal velocities. The perihelion always lies in the smaller portion, and there the earth's motion is the most rapid.

[1] Note 69

In the present position of the perihelion, spring and summer, north of the equator, exceed by about eight days the duration of the same seasons south of it. And 10,468 years ago the southern hemisphere enjoyed the advantage we now possess from the secular variation of the perihelion. Yet Sir John Herschel has shown, that by this alteration neither hemisphere acquires any excess of light or heat above the other, for, although the earth is nearer to the sun, while moving through that part of its orbit in which the perihelion lies than in the other part, and consequently receives a greater quantity of light and heat, yet, as it moves faster, it is exposed to the heat for a shorter time. In the other part of the orbit, on the contrary, the earth, being farther from the sun, receives fewer of his rays, but, because its motion is slower it is exposed to them for a longer time. And as in both cases the quantity of heat and the angular velocity vary exactly in the same proportion, a perfect compensation takes place.[1] So that the eccentricity of the earth's orbit has little or no effect on the temperature corresponding to the difference of the seasons, and none whatever on the general mean temperature of the globe.

Mr. Lyell, in his excellent work on Geology, refers the increased cold of the northern hemisphere to the operation of existing causes, with more probability than most theories that have been advanced in solution of this difficult subject. The loftiest mountains would be represented by a grain of sand on a globe six feet in diameter, and the depth of the ocean by a scratch on its surface. Consequently the gradual elevation of a continent or chain of mountains above the surface of the ocean, or their depression below it, is no very great event compared with the magnitude of the earth, and

[1] Note 189

the energy of its subterranean fires, if the same periods of time be admitted in the progress of geological as in astronomical phenomena, which the successive and various races of extinct beings show to have been immense. Climate is always more intense in the interior of continents than in islands or sea-coasts. An increase of land within the tropics would therefore augment the general heat, and an increase in the temperate and frigid zones would render the cold more severe. Now, it appears that most of the European, North Asiatic, and North American continents and islands, were raised from the deep after the coal measures were formed in which the fossil tropical plants are found, and a variety of geological facts indicate the existence of an ancient and extensive archipelago throughout the greater part of the northern hemisphere. Mr. Lyell is therefore of opinion, that the climate of these islands must have been sufficiently mild, in consequence of the surrounding ocean, to clothe them with tropical plants, and render them a fit abode for the huge animals whose fossil remains are so often found. That the arborescent ferns and the palms of these regions, carried by streams to the bottom of the ocean, were imbedded in the strata which were by degrees heaved up by the subterranean fires during a long succession of ages, till the greater part of the northern hemisphere became dry land, as it now is, and that the consequence has been a continual decrease of temperature.

It is evident, from the marine shells found on the tops of the highest mountains, and in almost every part of the globe, that immense continents have been elevated above the ocean, which must have engulphed others. Such a catastrophe would be occasioned by a variation in the position of the axis of rotation on the surface of the earth;

for the seas, tending to a new equator, would leave some portions of the globe, and overwhelm others. Now, it is found by the laws of mechanics that, in every body, be its form or density what it may, there are at least three axes at right angles to each other, round any one of which, if the solid begins to rotate, it will continue to revolve for ever, provided it be not disturbed by a foreign cause, but that the rotation about any other axis will only be for an instant. Consequently the poles or extremities of the instantaneous axis of rotation, would perpetually change their position on the surface of the body. In an ellipsoid of revolution, the polar diameter, and every diameter in the plane of the equator, are the only permanent axes of rotation.[1] Hence, if the ellipsoid were to begin to revolve about any diameter between the pole and the equator, the motion would be so unstable, that the axis of rotation and the position of the poles would change every instant. Therefore, as the earth does not differ much from this figure, if it did not turn round one of its principal axes, the position of the poles would change daily; the equator, which is 90° distant, would undergo corresponding variations; and the geographical latitudes of all places, being estimated from the equator, assumed to be fixed, would be perpetually changing.

A displacement in the position of the poles of only two hundred miles would be sufficient to produce these effects, and would immediately be detected. But, as the latitudes are found to be invariable, it may be concluded that the terrestrial spheroid must have revolved about the same axis for ages. The earth and planets differ so little from ellipsoids of revolution, that, in all probability, any librations from one axis to another, produced by the

[1] Note 140.

Besides, it is clear, from the mensuration of the arcs of the meridian, and the length of the seconds pendulum, as well as from the lunar theory, that the internal strata, and also the external outline of the globe, are elliptical, their centres being coincident, and their axes identical, with that of the surface,—a state of things which, according to the distinguished author lately quoted, is incompatible with a subsequent accommodation of the surface to a new and different state of rotation, from that which determined the original distribution of the component matter. Thus, amidst the mighty revolutions which have swept innumerable races of organized beings from the earth, which have elevated plains, and buried mountains in the ocean, the rotation of the earth, and the position of the axes on its surface, have undergone but slight variations.

The strata of the terrestrial spheroid are not only concentric and elliptical, but the lunar inequalities show that they increase in density from the surface of the earth to its centre. This would certainly have happened if the earth had originally been fluid, for the denser parts must have subsided towards the centre as it approached a state of equilibrium. But the enormous pressure of the superincumbent mass is a sufficient cause for the phenomenon. Professor Leslie observes, that air, compressed into the fiftieth part of its volume, has its elasticity fifty times augmented. If it continues to contract at that rate, it would, from its own incumbent weight, acquire the density of water at the depth of thirty-four miles. But water itself would have its density doubled at the depth of ninety-three miles, and would even attain the density of quicksilver at a depth of 362 miles. Descending, therefore, towards the centre, through nearly 4000 miles, the condensation of

ordinary substances would surpass the utmost powers of conception. Dr Young says that steel would be compressed into one fourth and stone into one eighth of its bulk at the earth's centre However, we are yet ignorant of the laws of compression of solid bodies beyond a certain limit, though, from the experiments of Mr Perkins, they appear to be capable of a greater degree of compression than has generally been imagined

But a density so extreme is not borne out by astronomical observation It might seem to follow, therefore, that our planet must have a widely cavernous structure, and that we tread on a crust or shell whose thickness bears a very small proportion to the diameter of its sphere. Possibly, too, this great condensation at the central regions may be counterbalanced by the increased elasticity due to a very elevated temperature.

SECTION XI.

PRECESSION AND NUTATION.—THEIR EFFECTS ON THE APPARENT PLACES OF THE FIXED STARS.

It has been shown that the axis of rotation is invariable on the surface of the earth; and observation, as well as theory prove, that were it not for the action of the sun and moon on the matter at the equator, it would remain exactly parallel to itself in every point of its orbit.

The attraction of an external body not only draws a spheroid towards it, but, as the force varies inversely as the square of the distance, it gives it a motion about its centre of gravity, unless when the attracting body is situate in the prolongation of one of the axes of the spheroid. The plane of the equator is inclined to the plane of the ecliptic at an angle of $23° 27' 39''{\cdot}26$; and the inclination of the lunar orbit on the same is $5° 8' 47''{\cdot}9$. Consequently, from the oblate figure of the earth, the sun and moon, acting obliquely and unequally on the different parts of the terrestrial spheroid, urge the plane of the equator from its direction, and force it to move from east to west, so that the equinoctial points have a slow retrograde motion on the plane of the ecliptic of $50''{\cdot}41$ annually. The direct tendency of this action is to make the planes of the equator and ecliptic coincide, but it is balanced by the tendency of the earth to return to stable rotation about the polar diameter, which is one of its principal axes of rotation. Therefore the inclination of the two planes remains constant, as a top spinning preserves the same inclination to the plane of

the horizon Were the earth spherical, this effect would not be produced, and the equinoxes would always correspond with the same points of the ecliptic, at least as far as this kind of motion is concerned. But another and totally different cause which operates on this motion has already been mentioned The action of the planets on one another, and on the sun, occasions a very slow variation in the position of the plane of the ecliptic, which affects its inclination to the plane of the equator, and gives the equinoctial points a slow but direct motion on the ecliptic of 0″·31 annually, which is entirely independent of the figure of the earth, and would be the same if it were a sphere. Thus the sun and moon, by moving the plane of the equator, cause the equinoctial points to retrograde on the ecliptic; and the planets, by moving the plane of the ecliptic, give them a direct motion, though much less than the former. Consequently, the difference of the two is the mean precession, which is proved, both by theory and observation, to be about 50″·1 annually [1]

As the longitudes of all the fixed stars are increased by this quantity, the effects of precession are soon detected. It was accordingly discovered by Hipparchus, in the year 128 before Christ, from a comparison of his own observations with those of Timocharis, 155 years before In the time of Hipparchus, the entrance of the sun into the constellation Aries was the beginning of spring, but since that time the equinoctial points have receded 30°, so that the constellations called the signs of the zodiac are now at a considerable distance from those divisions of the ecliptic which bear their names. Moving at the rate of 50″·1 annually, the equinoctial points will accomplish a revolution in 25,868 years.

[1] Note 111

But as the precession varies in different centuries, the extent of this period will be slightly modified. Since the motion of the sun is direct, and that of the equinoctial points retrograde, he takes a shorter time to return to the equator than to arrive at the same stars, so that the tropical year of 365^d 5^h 48^m 49^s·2 must be increased by the time he takes to move through an arc of 50″·1, in order to have the length of the sidereal year. The time required is 20′ 20″·4, so that the sidereal year contains 365^d 6^h 9^m 9^s·6 mean solar days

The mean annual precession is subject to a secular variation; for, although the change in the plane of the ecliptic, in which the orbit of the sun lies, be independent of the form of the earth, yet, by bringing the sun, moon, and earth into different relative positions, from age to age, it alters the direct action of the two first on the prominent matter at the equator. on this account, the motion of the equinox is greater by 0″·455 now than it was in the time of Hipparchus Consequently, the actual length of the tropical year is about 4^s·21 shorter than it was at that time The utmost change that it can experience from this cause amounts to 43 seconds.

Such is the secular motion of the equinoxes. But it is sometimes increased and sometimes diminished by periodic variations, whose periods depend upon the relative positions of the sun and moon with regard to the earth, and which are occasioned by the direct action of these bodies on the equator. Dr. Bradley discovered that by this action the moon causes the pole of the equator to describe a small ellipse in the heavens, the diameters of which are 18″·5 and 13″·74, the longer being directed towards the pole of the ecliptic. The period of this inequality is about 19 years, the time

employed by the nodes of the lunar orbit to accomplish a revolution. The sun causes a small variation in the description of this ellipse; it runs through its period in half a year. Since the whole earth obeys these motions, they affect the position of its axis of rotation with regard to the starry heavens, though not with regard to the surface of the earth; for, in consequence of precession alone, the pole of the equator moves in a circle round the pole of the ecliptic in 25,868 years, and by nutation alone it describes a small ellipse in the heavens every 19 years, on each side of which it deviates every half year from the action of the sun. The real curve traced in the starry heavens by the imaginary prolongation of the earth's axis is compounded of these three motions.[1] This nutation in the earth's axis affects both the precession and obliquity, with small periodic variations. But, in consequence of the secular variation in the position of the terrestrial orbit, which is chiefly owing to the disturbing energy of Jupiter on the earth, the obliquity of the ecliptic is annually diminished according to M. Bessel, by 0″.457. This variation in the course of ages may amount to 10 or 11 degrees; but the obliquity of the ecliptic to the equator can never vary more than 2° 42′ or 3°, since the equator will follow in some measure the motion of the ecliptic.

It is evident that the places of all the celestial bodies are affected by precession and nutation. Their longitudes, estimated from the equinox, are augmented by precession; but as it affects all the bodies equally, it makes no change in their relative positions. Both the celestial latitudes and longitudes are altered to a small degree by nutation; hence all observations must be cor-

1 Note 112.

rected for these inequalities. In consequence of this real motion in the earth's axis, the pole star, forming part of the constellation of the Little Bear, which was formerly 12° from the celestial pole, is now within 1° 24′ of it, and will continue to approach it till it is within $\frac{1}{2}$°, after which it will retreat from the pole for ages, and 12,000 years hence, the star α Lyræ will come within 5° of the celestial pole, and become the polar star of the northern hemisphere

SECTION XII

MEAN AND APPARENT SIDEREAL TIME.—MEAN AND APPARENT SOLAR TIME.—EQUATION OF TIME.—ENGLISH AND FRENCH SUBDIVISIONS OF TIME.—LEAP-YEAR.—CHRISTIAN ERA.—EQUINOCTIAL TIME.—REMARKABLE ERAS DEPENDING UPON THE POSITION OF THE SOLAR PERIGEE.—INEQUALITY OF THE LENGTHS OF THE SEASONS IN THE TWO HEMISPHERES.—APPLICATION OF ASTRONOMY TO CHRONOLOGY.—ENGLISH AND FRENCH STANDARDS OF WEIGHTS AND MEASURES.

ASTRONOMY has been of immediate and essential use in affording invariable standards for measuring duration, distance, magnitude, and velocity. The mean sidereal day, measured by the time elapsed between two consecutive transits of any star at the same meridian, and the mean sidereal year, which is the time included between two consecutive returns of the sun to the same star, are immutable units with which all great periods of time are compared; the oscillations of the isochronous pendulum measure its smaller portions. By these invariable standards alone, we can judge of the slow changes that other elements of the system may have undergone. Apparent sidereal time, which is measured by the transit of the equinoctial point at the meridian of any place, is a variable quantity from the effects of precession and nutation. Clocks showing apparent sidereal time are employed for observation, and are so regulated that they indicate $0^h\ 0^m\ 0^s$ at the instant the equinoctial point passes the meridian of the observatory. And as time is a measure of angular motion, the clock gives the distances of the heavenly bodies from the equinox, by observing the instant at which each passes

the meridian, and converting the interval into arcs at the rate of 15° to an hour

The returns of the sun to the meridian, and to the same equinox or solstice, have been universally adopted as the measure of our civil days and years The solar or astronomical day is the time that elapses between two consecutive noons or midnights. It is consequently longer than the sidereal day, on account of the proper motion of the sun during a revolution of the celestial sphere But, as the sun moves with greater rapidity at the winter than at the summer solstice, the astronomical day is more nearly equal to the sidereal day in summer than in winter. The obliquity of the ecliptic also affects its duration, for in the equinoxes the arc of the equator is less than the corresponding arc of the ecliptic, and in the solstices it is greater.[1] The astronomical day is, therefore, diminished in the first case, and increased in the second If the sun moved uniformly in the equator at the rate of 59′ 8″·3 every day, the solar days would be all equal. The time, therefore, which is reckoned by the arrival of an imaginary sun at the meridian, or of one which is supposed to move uniformly in the equator, is denominated mean solar time, such as is given by clocks and watches in common life. When it is reckoned by the arrival of the real sun at the meridian, it is apparent time, such as is given by dials The difference between the time shown by a clock and a dial is the Equation of Time given in the Nautical Almanac, sometimes amounting to as much as sixteen minutes. The apparent and mean time coincide four times in the year.

The astronomical day begins at noon, but in common reckoning the day begins at midnight. In England it

[1] Note 143

is divided into twenty-four hours, which are counted by twelve and twelve; but in France, astronomers, adopting the decimal division, divide the day into ten hours, the hour into one hundred minutes, and the minute into a hundred seconds, because of the facility in computation, and in conformity with their system of weights and measures This subdivision is not used in common life, nor has it been adopted in any other country, and although some scientific writers in France still employ that division of time, the custom is beginning to wear out. The mean length of the day, though accurately determined, is not sufficient for the purposes either of astronomy or civil life. The tropical or civil year of $365^d\ 5^h\ 48^m\ 49^s.2$, which is the time elapsed between the consecutive returns of the sun to the mean equinoxes or solstices, including all the changes of the seasons, is a natural cycle peculiarly suited for a measure of duration. It is estimated from the winter solstice, the middle of the long annual night under the north pole. But although the length of the civil year is pointed out by nature as a measure of long periods, the incommensurability that exists between the length of the day and the revolution of the sun, renders it difficult to adjust the estimation of both in whole numbers. If the revolution of the sun were accomplished in 365 days, all the years would be of precisely the same number of days, and would begin and end with the sun at the same point of the ecliptic. But as the sun's revolution includes the fraction of a day, a civil year and a revolution of the sun have not the same duration. Since the fraction is nearly the fourth of a day, in four years it is nearly equal to a revolution of the sun, so that the addition of a supernumerary day every fourth year nearly compensates the difference. But, in pro-

cess of time, further correction will be necessary, because the fraction is less than the fourth of a day In fact, if a bissextile be suppressed at the end of three out of four centuries, the year so determined will only exceed the true year by an extremely small fraction of a day, and if, in addition to this, a bissextile be suppressed every 4000 years, the length of the year will be nearly equal to that given by observation. Were the fraction neglected, the beginning of the year would precede that of the tropical year, so that it would retrograde through the different seasons in a period of about 1507 years. The Egyptians estimated the year at $365^{d}\ 6^{h}$, by which they lost one year in every 14,601 — their Sothiac period. They determined the length of their year by the heliacal rising[1] of Sirius 2782 years before the Christian era, which is the earliest epoch of Egyptian chronology The division of the year into months is very old and almost universal. But the period of seven days, by far the most permanent division of time, and the most ancient monument of astronomical knowledge, was used by the Brahmins in India, with the same denominations employed by us, and was alike found in the calendars of the Jews, Egyptians, Arabs, and Assyrians It has survived the fall of empires, and has existed among all successive generations, a proof of their common origin.

The day of the new moon immediately following the winter solstice in the 707th year of Rome was made the 1st of January of the first year of Julius Cæsar. The 25th of December of his forty fifth year is considered as the date of Christ's nativity; and the forty-sixth year of the Julian Calendar is assumed to be the first of our era. The preceding year is called the first

[1] Note 114

year before Christ by chronologists, but by astronomers it is called the year 0. The astronomical year begins on the 31st of December, at noon; and the date of an observation expresses the days and hours which have actually elapsed since that time.

Since solar and sidereal time are estimated from the passage of the sun and the equinoctial point across the meridian of each place, an event which happened at one and the same instant of absolute time, is recorded at different places as having happened at different times; which is obvious, when it is considered that while it is noon at one part of the globe, it is midnight at another diametrically opposite to it. Therefore, when observations made at different places are to be compared, they must be reduced by computation to what they would have been had they been made under the same meridian. To obviate this, it was proposed by Sir John Herschel to employ mean equinoctial time, which is the same for all the world, and independent alike of local circumstances and inequalities in the sun's motion. It is the time elapsed from the instant the mean sun enters the mean vernal equinox, and is reckoned in mean solar days and parts of a day.

Some remarkable astronomical eras are determined by the position of the major axis of the solar ellipse, which depends upon the direct motion of the perigee[1] and the precession of the equinoxes conjointly, the annual motion of the one being 11″·8, and that of the other 50″·1. Hence the axis, moving at the rate of 61″·9 annually, accomplishes a tropical revolution in 20937 years. It coincided with the line of the equinoxes 4000 or 4089 years before the Christian era, much about the time chronologists assign for the cre-

[1] Note 100.

No circumstance in the whole science of astronomy excites a deeper interest than its application to chronology. "Whole nations," says La Place, "have been swept from the earth, with their languages, arts, and sciences, leaving but confused masses of ruins to mark the place where mighty cities stood; their history, with the exception of a few doubtful traditions, has perished, but the perfection of their astronomical observations marks their high antiquity, fixes the periods of their existence, and proves that, even at that early time, they must have made considerable progress in science" The ancient state of the heavens may now be computed with great accuracy, and by comparing the results of computation with ancient observations, the exact period at which they were made, may be verified if true, or, if false, their error may be detected. If the date be accurate, and the observation good, it will verify the accuracy of modern tables, and will show to how many centuries they may be extended, without the fear of error A few examples will show the importance of the subject.

At the solstices the sun is at his greatest distance from the equator, consequently his declination at these times is equal to the obliquity of the ecliptic [1], which, formerly, was determined from the meridian length of the shadow of the stile of a dial on the day of the solstice. The lengths of the meridian shadow at the summer and winter solstice are recorded to have been observed at the city of Layang, in China, 1100 years before the Christian era From these, the distances of the sun from the zenith [2] of the city of Layang are known. Half the sum of these zenith distances determines the latitude, and half their difference gives the obliquity of the ecliptic at the period of the observation;

[1] Note 146. [2] Note 147

and as the law of the variation of the obliquity is known, both the time and place of the observations have been verified by computations from modern tables. Thus the Chinese had made some advances in the science of astronomy at that early period. Their whole chronology is founded on the observation of eclipses, which prove the existence of that empire for more than 4700 years. The epoch of the lunar tables of the Indians, supposed by Bailly to be 3000 years before the Christian era, was proved by La Place, from the acceleration of the moon, not to be more ancient than the time of Ptolemy, who lived in the second century after it. The great inequality of Jupiter and Saturn, whose cycle embraces 918 years, is peculiarly fitted for marking the civilisation of a people. The Indians had determined the mean motions of these two planets in that part of their periods, when the apparent mean motion of Saturn was at the slowest, and that of Jupiter the most rapid. The periods in which that happened was 3102 years before the Christian era, and the year 1491 after it. The returns of comets to their perihelia may possibly mark the present state of astronomy to future ages.

The places of the fixed stars are affected by the precession of the equinoxes, and as the law of that variation is known, their positions at any time may be computed. Now Eudoxus, a contemporary of Plato, mentions a star situate in the pole of the equator, and it appears from computation, that κ Draconis was not very far from that place about 3000 years ago; but as it is only about 2150 years since Eudoxus lived, he must have described an anterior state of the heavens, supposed to be the same that was mentioned by Chiron, about the time of the siege of Troy. Every circumstance concurs

in showing that astronomy was cultivated in the highest ages of antiquity.

It is possible that a knowledge of astronomy may lead to the interpretation of hieroglyphical characters. Astronomical signs are often found on the ancient Egyptian monuments, probably employed by the priests to record dates. The author had occasion to witness an instance of this most interesting application of astronomy, in ascertaining the date of a papyrus, sent from Egypt by Mr. Salt, in the hieroglyphical researches of the late Dr. Thomas Young, whose profound and varied acquirements do honour to his country and to the age in which he lived. The manuscript was found in a mummy-case; it proved to be a horoscope of the age of Ptolemy, and its antiquity was determined from the configuration of the heavens at the time of its construction.

The form of the earth furnishes a standard of weights and measures for the ordinary purposes of life, as well as for the determination of the masses and distances of the heavenly bodies. The length of the pendulum vibrating seconds of mean solar time, in the latitude of London, forms the standard of the British measure of extension. Its length oscillating in vacuo at the temperature of 62° of Fahrenheit, and reduced to the level of the sea[1], was determined, by Captain Kater, to be 39·1393 inches. The weight of a cubic inch of water at the temperature of 62° of Fahrenheit, barometer 30 inches, was also determined in parts of the imperial troy pound, whence a standard both of weight and capacity is deduced. The French have adopted the mètre, equal to 3·2808992 English feet, for their unit of linear

[1] Note 148.

measure, which is the ten-millionth part of that quadrant of the meridian[1] passing through Formentera and Greenwich, the middle of which is nearly in the forty-fifth degree of latitude. Should the national standards of the two countries be lost in the vicissitude of human affairs, both may be recovered, since they are derived from natural standards presumed to be invariable. The length of the pendulum would be found again with more facility than the mètre But as no measure is mathematically exact, an error in the original standard may at length become sensible in measuring a great extent, whereas the error that must necessarily arise in measuring the quadrant of the meridian is rendered totally insensible by subdivisions, in taking its ten-millionth part. The French have adopted the decimal division, not only in time, but in their degrees, weights, and measures, on account of the very great facility it affords in computation. It has not been adopted by any other people, though nothing is more desirable than that all nations should concur in using the same division and standards, not only on account of convenience, but as affording a more definite idea of quantity. It is singular that the decimal division of the day, of degrees, weights, and measures, was employed in China 4000 years ago; and that at the time Ibn Junis made his observations at Cairo, about the year 1000 of the Christian era, the Arabs were in the habit of employing the vibrations of the pendulum in their astronomical observations as a measure of time.

1 Note 149

SECTION XIII.

TIDES.—FORCES THAT PRODUCE THEM.—THREE KINDS OF OSCILLATIONS IN THE OCEAN.—THE SEMIDIURNAL TIDES.—EQUINOCTIAL TIDES.—EFFECTS OF THE DECLINATION OF THE SUN AND MOON.—THEORY INSUFFICIENT WITHOUT OBSERVATION.—DIRECTION OF THE TIDAL WAVE.—HEIGHT OF TIDES.—MASS OF MOON OBTAINED FROM HER ACTION ON THE TIDES.—INTERFERENCE OF UNDULATIONS.—IMPOSSIBILITY OF A UNIVERSAL INUNDATION.—CURRENTS.

One of the most immediate and remarkable effects of a gravitating force external to the earth, is the alternate rise and fall of the surface of the sea twice in the course of a lunar day, or $24^h\ 50^m\ 48^s$ of mean solar time. As it depends upon the action of the sun and moon, it is classed among astronomical problems, of which it is by far the most difficult, and its explanation the least satisfactory. The form of the surface of the ocean in equilibrio, when revolving with the earth round its axis, is an ellipsoid flattened at the poles; but the action of the sun and moon, especially of the moon, disturbs the equilibrium of the ocean. If the moon attracted the centre of gravity of the earth and all its particles with equal and parallel forces, the whole system of the earth and the waters that cover it would yield to these forces with a common motion, and the equilibrium of the seas would remain undisturbed. The difference of the forces, and the inequality of their directions, alone disturb the equilibrium.

It is proved by daily experience, as well as by strict mathematical reasoning, that if a number of waves or oscillations be excited in a fluid by different forces, each

pursues its course, and has its effect independently of the rest. Now, in the tides there are three kinds of oscillations, depending on different causes, and producing their effects independently of each other, which may therefore be estimated separately.

The oscillations of the first kind, which are very small, are independent of the rotation of the earth; and as they depend upon the motion of the disturbing body in its orbit, they are of long periods. The second kind of oscillations depends upon the rotation of the earth, therefore their period is nearly a day. The oscillations of the third kind vary with an angle equal to twice the angular rotation of the earth, and consequently happen twice in twenty-four hours.[1] The first afford no particular interest, and are extremely small; but the difference of two consecutive tides depends upon the second. At the time of the solstices, this difference, which ought to be very great, according to Newton's theory, is hardly sensible on our shores. La Place has shown that this discrepancy arises from the depth of the sea, and that if the depth were uniform, there would be no difference in the consecutive tides but that which is occasioned by local circumstances. It follows, therefore, that as this difference is extremely small, the sea, considered in a large extent, must be nearly of uniform depth, that is to say, there is a certain mean depth from which the deviation is not great. The mean depth of the Pacific Ocean is supposed to be about four miles, that of the Atlantic only three. From the formulæ which determine the difference of the consecutive tides, it is also proved, that the precession of the equinoxes, and the nutation of the earth's axis, are the same as if the sea formed one solid mass with the earth.

[1] Note 150.

Oscillations of the third kind are the semidiurnal tides, so remarkable on our coasts. They are occasioned by the combined action of the sun and moon, but as the effect of each is independent of the other, they may be considered separately.

The particles of water under the moon are more attracted than the centre of gravity of the earth, in the inverse ratio of the square of the distances. Hence they have a tendency to leave the earth, but are retained by their gravitation, which is diminished by this tendency. On the contrary, the moon attracts the centre of the earth more powerfully than she attracts the particles of water in the hemisphere opposite to her, so that the earth has a tendency to leave the waters, but is retained by gravitation, which is again diminished by this tendency. Thus the waters immediately under the moon are drawn from the earth at the same time that the earth is drawn from those which are diametrically opposite to her, in both instances producing an elevation of the ocean of nearly the same height above the surface of equilibrium, for, the diminution of the gravitation of the particles in each position is almost the same, on account of the distance of the moon being great in comparison of the radius of the earth. Were the earth entirely covered by the sea, the water thus attracted by the moon would assume the form of an oblong spheroid, whose greater axis would point towards the moon, since the columns of water under the moon and in the direction diametrically opposite to her, are rendered lighter in consequence of the diminution of their gravitation; and in order to preserve the equilibrium, the axes 90° distant would be shortened. The elevation, on account of the smaller space to which it is confined, is twice as great as the depression, because the contents of the

spheroid always remain the same. If the waters were capable of assuming the form of equilibrium instantaneously, that is, the form of the spheroid, its summit would always point to the moon, notwithstanding the earth's rotation. But on account of their resistance, the rapid motion produced in them by rotation, prevents them from assuming at every instant, the form which the equilibrium of the forces acting upon them requires. Hence, on account of the inertia of the waters, if the tides be considered relatively to the whole earth, and open sea, there is a meridian about 30° eastward of the moon, where it is always high water both in the hemisphere where the moon is, and in that which is opposite On the west side of this circle the tide is flowing, on the east it is ebbing, and on every part of the meridian at 90° distant, it is low water This great wave, which follows all the motions of the moon as far as the rotation of the earth will permit, is modified by the action of the sun, the effects of whose attraction are in every respect like those produced by the moon, though greatly less in degree Consequently, a similar wave, but much smaller, raised by the sun, tends to follow his motions, which at times combines with the lunar wave, and at others opposes it, according to the relative positions of the two luminaries; but as the lunar wave is only modified a little by the solar, the tides must necessarily happen twice in a day, since the rotation of the earth brings the same point twice under the meridian of the moon in that time, once under the superior, and once under the inferior, meridian.

In the semidiurnal tides there are two phenomena particularly to be distinguished, one occurring twice in a month, and the other twice in a year

The first phenomenon is, that the tides are much

increased in the syzigies, or at the time of new and full moon.[1] In both cases the sun and moon are in the same meridian; for when the moon is new, they are in conjunction, and when she is full, they are in opposition. In each of these positions, their action is combined to produce the highest or spring tides under that meridian, and the lowest in those points that are 90° distant. It is observed that the higher the sea rises in full tide, the lower it is in the ebb. The neap tides take place when the moon is in quadrature; they neither rise so high nor sink so low as the spring tides. The spring tides are much increased when the moon is in perigee, because she is then nearest to the earth. It is evident that the spring tides must happen twice in a month, since in that time the moon is once new and once full.

The second phenomenon in the tides is the augmentation, which occurs at the time of the equinoxes, when the sun's declination[2] is zero, which happens twice every year. The greatest tides take place when a new or full moon happens near the equinoxes while the moon is in perigee. The inclination of the moon's orbit on the ecliptic is 5° 8′ 47″·9; hence, in the equinoxes, the action of the moon would be increased if her node were to coincide with her perigee. For it is clear, that the action of the sun and moon on the ocean is most direct and intense when they are in the plane of the equator, and in the same meridian, and when the moon in conjunction or opposition is at her least distance from the earth. The spring tides which happen under all these favourable circumstances must be the greatest possible. The equinoctial gales often raise these tides to a great height. Besides these remarkable variations, there are others arising from the declination

[1] Note 151. [2] Note 152.

or angular distance of the sun and moon from the plane of the equator, which have a great influence on the ebb and flow of the waters The sun and moon are continually making the circuit of the heavens at different distances from the plane of the equator, on account of the obliquity of the ecliptic, and the inclination of the lunar orbit The moon takes about twenty-nine days and a half to vary through all her declinations, which sometimes extend 28¾ degrees on each side of the equator, while the sun requires nearly 365¼ days to accomplish his motion from tropic to tropic through about 23½ degrees, so that their combined motion causes great irregularities, and, at times, their attractive forces counteract each other's effects to a certain extent, but, on an average, the mean monthly range of the moon's declination is nearly the same as the annual range of the declination of the sun: consequently, the highest tides take place within the tropics, and the lowest towards the poles

Both the height and time of high water are thus perpetually changing, therefore in solving the problem, it is required to determine the heights to which the tides rise, the times at which they happen, and the daily variations Theory and observation show, that each partial tide increases as the cube of the apparent diameter, or of the parallax of the body which produces it, and that it diminishes as the square of the cosine of the declination [1] of that body For the greater the apparent diameter, the nearer the body, and the more intense its action on the sea, but the greater the declination, the less the action, because it is less direct.

The periodic motions of the waters of the ocean, on the hypothesis of an ellipsoid of revolution entirely

[1] Note 162

covered by the sea, are very far from according with observation. This arises from the very great irregularities in the surface of the earth, which is but partially covered by the sea, from the variety in the depths of the ocean, the manner in which it is spread out on the earth, the position and inclination of the shores, the currents, and the resistance the waters meet with: causes it is impossible to estimate, but which modify the oscillations of the great mass of the ocean. However, amidst all these irregularities, the ebb and flow of the sea maintain a ratio to the forces producing them sufficient to indicate their nature, and to verify the law of the attraction of the sun and moon on the sea. La Place observes, that the investigation of such relations between cause and effect, is no less useful in natural philosophy than the direct solution of problems, either to prove the existence of the causes, or to trace the laws of their effects. Like the theory of probabilities, it is a happy supplement to the ignorance and weakness of the human mind. Thus the problem of the tides does not admit of a general solution. It is certainly necessary to analyse the general phenomena which ought to result from the attraction of the sun and moon, but these must be corrected in each particular case by local observations modified by the extent and depth of the sea, and the peculiar circumstances of the place.

Since the disturbing action of the sun and moon can only become sensible in a very great extent of water, it is evident that the Pacific Ocean is one of the principal sources of our tides. But, in consequence of the rotation of the earth, and the inertia of the ocean, high water does not happen till some time after the moon's

southing[1] The tide raised in that world of waters is transmitted to the Atlantic, from which sea it moves in a northerly direction along the coasts of Africa and Europe, arriving later and later at each place This great wave, however, is modified by the tide raised in the Atlantic, which sometimes combines with that from the Pacific in raising the sea, and sometimes is in opposition to it, so that the tides only rise in proportion to their difference This vast combined wave, reflected by the shores of the Atlantic, extending nearly from pole to pole, still coming northward, pours through the Irish and British Channels into the North Sea, so that the tides in our ports are modified by those of another hemisphere. Thus the theory of the tides in each port, both as to their height and the times at which they take place, is really a matter of experiment, and can only be perfectly determined by the mean of a very great number of observations, including several revolutions of the moon's nodes.

The height to which the tides rise is much greater in narrow channels than in the open sea, on account of the obstructions they meet with. The sea is so pent up in the British Channel, that the tides sometimes rise as much as fifty feet at St Malo, on the coast of France; whereas, on the shores of some of the South Sea islands, they do not exceed one or two feet The winds have a great influence on the height of the tides, according as they conspire with or oppose them. But the actual effect of the wind in exciting the waves of the ocean extends very little below the surface Even in the most violent storms, the water is probably calm at the depth of ninety or a hundred feet. The tidal wave of the ocean does not reach the Mediterranean

[1] Note 153

nor the Baltic, partly from their position and partly from the narrowness of the Straits of Gibraltar and of the Categat, but it is very perceptible in the Red Sea and in Hudson's Bay In high latitudes, where the ocean is less directly under the influence of the luminaries, the rise and fall of the sea is inconsiderable, so that, in all probability, there is no tide at the poles, or only a small annual and monthly tide The ebb and flow of the sea are perceptible in rivers to a very great distance from their estuaries. In the Straits of Pauxis, in the river of the Amazons, more than five hundred miles from the sea, the tides are evident It requires so many days for the tide to ascend this mighty stream, that the returning tides meet a succession of those which are coming up, so that every possible variety occurs in some part or other of its shores, both as to magnitude and time. It requires a very wide expanse of water to accumulate the impulse of the sun and moon, so as to render their influence sensible, on that account, the tides in the Mediterranean and Black Sea are scarcely perceptible

These perpetual commotions in the waters are occasioned by forces that bear a very small proportion to terrestrial gravitation the sun's action in raising the ocean is only $\frac{1}{38448000}$ of gravitation at the earth's surface, and the action of the moon is little more than twice as much; these forces being in the ratio of 1 to 2 35333, when the sun and moon are at their mean distances from the earth. From this ratio, the mass of the moon is found to be only $\frac{1}{75}$ of that of the earth. Had the action of the sun on the ocean been exactly equal to that of the moon, there would have been no neap tides, and the spring tides would have been of twice the height which the action of either the sun or

moon would have produced separately; a phenomenon depending upon the interference of the waves or undulations.

A stone plunged into a pool of still water occasions a series of waves to advance along the surface, though the water itself is not carried forward, but only rises into heights and sinks into hollows, each portion of the surface being elevated and depressed in its turn. Another stone of the same size, thrown into the water near the first, will occasion a similar set of undulations. Then, if an equal and similar wave from each stone arrive at the same spot at the same time, so that the elevation of the one exactly coincides with the elevation of the other, their united effect will produce a wave twice the size of either. But if one wave precede the other by exactly half an undulation, the elevation of the one will coincide with the hollow of the other, and the hollow of the one with the elevation of the other, and the waves will so entirely obliterate one another, that the surface of the water will remain smooth and level. Hence, if the length of each wave be represented by 1, they will destroy one another at intervals of $\frac{1}{2}$, $\frac{3}{2}$, $\frac{5}{2}$, &c., and will combine their effects at the intervals, 1, 2, 3, &c. It will be found, according to this principle, when still water is disturbed by the fall of two equal stones, that there are certain lines on its surface of a hyperbolic form, where the water is smooth in consequence of the waves obliterating each other; and that the elevation of the water in the adjacent parts corresponds to both the waves united.[1] Now, in the spring and neap tides, arising from the combination of the simple soli-lunar waves, the spring tide is the joint result of the combination when they coincide in time and place; and the neap

[1] Note 104.

tide happens when they succeed each other by half an interval, so as to leave only the effect of their difference sensible. It is therefore evident that, if the solar and lunar tides were of the same height, there would be no difference, consequently no neap tides, and the spring tides would be twice as high as either separately. In the port of Batsha, in Tonquin, where the tides arrive by two channels, of lengths corresponding to half an interval, there is neither high nor low water, on account of the interference of the waves.

The initial state of the ocean has no influence on the tides, for, whatever its primitive conditions may have been, they must soon have vanished by the friction and mobility of the fluid. One of the most remarkable circumstances in the theory of the tides is the assurance that, in consequence of the density of the sea being only one fifth of the mean density of the earth, and that the earth itself increases in density towards the centre, the stability of the equilibrium of the ocean never can be subverted by any physical cause whatever. A general inundation, arising from the mere instability of the ocean, is therefore impossible. A variety of circumstances, however, tend to produce partial variations in the equilibrium of the seas, which is restored by means of currents. Winds, and the periodical melting of the ice at the poles, occasion temporary water-courses, but by far the most important causes are the centrifugal force induced by the velocity of the earth's rotation, and variations in the density of the sea.

The centrifugal force may be resolved into two forces —one perpendicular, and another tangent to the earth's surface.[1] The tangential force, though small, is sufficient to make the fluid particles within the polar circles

[1] Note 155.

tend towards the equator, and the tendency is much increased by the immense evaporation in the equatorial regions, from the heat of the sun, which disturbs the equilibrium of the ocean. To this may also be added the superior density of the waters near the poles, partly from their low temperature, and partly from their gravitation being less diminished by the action of the sun and moon, than that of the seas of lower latitudes In consequence of the combination of all these circumstances, two great currents perpetually set from each pole towards the equator But, as they come from latitudes where the rotatory motion of the surface of the earth is very much less than it is between the tropics, on account of their inertia, they do not immediately acquire the velocity with which the solid part of the earth's surface is revolving at the equatorial regions, from whence it follows that, within twenty-five or thirty degrees on each side of the line, the ocean appears to have a general motion from east to west, which is much increased by the action of the trade-winds. This mighty mass of rushing waters, at about the tenth degree of south latitude, is turned towards the north-west by the coast of America, runs through the Gulf of Mexico, and, passing the Straits of Florida at the rate of five miles an hour, forms the well-known current of the Gulf-stream, which sweeps along the whole coast of America, and runs northward as far as the bank of Newfoundland, whence, bending to the east, it flows past the Azores and Canary Islands, till it joins the great westerly current of the tropics about latitude 21° north According to M. de Humboldt, this great circuit of 3800 leagues, which the waters of the Atlantic are perpetually describing between the parallels of eleven and forty-three degrees of latitude, may be accomplished by

any one particle in two years and ten months. Besides this, there are branches of the Gulf-stream, which convey the fruits, seeds, and a portion of the warmth of the tropical climates, to our northern shores

The general westward motion of the South Sea, together with the south polar current, produce various water-courses in the Pacific and Indian Oceans, according as the one or the other prevails. The western set of the Pacific causes currents to pass on each side of Australia, while the polar stream rushes along the Bay of Bengal, but the westerly current again becomes most powerful towards Ceylon and the Maldives, whence it stretches by the extremity of the Indian peninsula, past Madagascar, to the most northern point of the continent of Africa, where it mingles with the general motion of the seas. Icebergs are sometimes drifted as far as the Azores from the north pole, and from the south pole they have come even to the Cape of Good Hope. In consequence of the polar current, Sir Edward Parry was obliged to give up his attempt to reach the north pole in the year 1827, because he found that the fields of ice were drifting to the south faster than his party could travel over them to the north.

SECTION XIV.

COHESIVE AND REPULSIVE FORCES — CONSTITUTION OF AERIFORM FLUIDS, OF LIQUIDS AND SOLIDS — EFFECTS OF GRAVITATION — INTERSTICES OR PORES — ELASTICITY — GASES REDUCED TO LIQUIDS BY PRESSURE — INTENSITY OF THE COHESIVE AND REPULSIVE FORCES — EFFECTS OF COHESION — MINUTENESS OF THE ULTIMATE ATOMS OF MATTER — LIMITED HEIGHT OF THE ATMOSPHERE — THEORY OF DEFINITE PROPORTIONS AND RELATIVE WEIGHTS OF ATOMS — DR FARADAY'S DISCOVERIES WITH REGARD TO AFFINITY — COMPOSITION OF WATER BY A PLATE OF PLATINA — CRYSTALLISATION — CLEAVAGE — ISOMORPHISM — MATTER CONSISTS OF ATOMS OF DEFINITE FORM — CAPILLARY ATTRACTION.

The oscillations of the atmosphere, and its action upon rays of light coming from the heavenly bodies, connect the science of astronomy with the equilibrium and movements of fluids, and the laws of molecular attraction. Hitherto, those forces have been under consideration which act upon masses of matter at sensible distances, but now the effects of such forces must be considered as act at inappreciable distances upon the ultimate atoms of material bodies, which are far too small to be visible by any means human ingenuity has yet been able to devise. All bodies consist of an assemblage of material particles, held in equilibrio by a cohesive force, which tends to unite them, and also by a repulsive force, probably caloric, the principle of heat, which tends to separate them. The intensity of these forces decreases rapidly as the distance between the particles augments, and becomes altogether insensible as soon as that distance has acquired a sensible magni-

tude. It is evident, that the density of substances will depend upon the ratio which the opposing forces of cohesion and repulsion bear to one another.

When particles of the same kind of matter are at such distances from each other, that the cohesion which retains them is insensible, the repulsive principle remains unbalanced, and the particles have a tendency to fly from one another, as in aeriform fluids. If the particles approach sufficiently near to produce equilibrium between the attractive and repulsive forces, but not near enough to admit of any influence from their form, perfect mobility will exist among them, resulting from the similarity of their attractions, and they will offer great resistance when compressed, properties which characterise liquids, in which the repulsive principle is greater than in the gases. When the distance between the particles is still less, solids are formed, in consequence of the preponderating force of cohesion. But the nature of their structure will vary, because at such small distances the power of the mutual attraction of the particles will depend upon their form, and will be modified by the sides they present to one another during their aggregation. Besides these three conditions of matter, there are an infinite variety of others, corresponding to all the various relations that can exist between the two contending forces, which may be observed in the fusion of metals, and other substances, passing from hardness to toughness, viscidity, and through all the other stages to perfect fluidity, and even to vapour.

Every particle of matter, whether it forms a constituent part of a solid, liquid, or aeriform fluid, is subject to the law of gravitation. The weight of the atmosphere, of gases and vapour, shows that they consist of

gravitating particles In liquids, the cohesive force is not sufficiently powerful to resist the united action of repulsion and gravitation. Therefore, although their component particles still maintain their connexion, the liquid is scattered by their weight, unless when it is confined in a vessel, or has already descended to the lowest point possible, and assumed a level surface from the mobility of its particles and the influence of the gravitating force, as in the ocean, or a lake. Solids would also fall to pieces by the weight of their particles if the force of cohesion were not powerful enough to resist the united efforts of gravitation and repulsion. Since every known substance may be reduced in bulk by pressure, it follows that the particles of matter are not in actual contact, but are separated by interstices, owing to the repulsive principle that maintains them at extremely minute distances from one another. It is evident that the smaller the interstitial spaces, the greater the density These spaces appear in some cases to be void or filled with air, as may be inferred from certain semi-opaque minerals and other substances becoming transparent when plunged in water, possibly they may contain some unknown and highly elastic fluid, such as Sir David Brewster has discovered in the minute cavities of various minerals, which occasionally causes these substances to explode with violence when under the hands of the lapidary.

All substances may be compressed by a sufficient force, and are said to be more or less elastic, according to the facility with which they regain their bulk or volume when the pressure is removed, a property which depends upon the repulsive force of their particles. But the pressure may be so great as to bring the particles within the sphere of the cohesive force, and then

an aeriform fluid may become a liquid, and a liquid a solid. Dr. Faraday has reduced some of the gases to a liquid state by very great compression; but although atmospheric air is capable of a diminution of volume to which we do not know the limit, it has hitherto always retained its gaseous properties, and resumes its primitive volume the instant the pressure is removed.

The effort required to break a substance is a measure of the intensity of the cohesive force exerted by its particles, which is as variable as the intensity of the repulsive principle. In stone, iron, steel, and all brittle and hard bodies, the cohesion of the particles is powerful, but of small extent. In elastic substances, on the contrary, its action is weak, but more extensive. Since all bodies expand by heat, the cohesive force is weakened by an increase of temperature.

The phenomena arising from the force of cohesion are innumerable. The spherical form of rain-drops; the difficulty of detaching a plate of glass from the surface of water; the force with which two plane surfaces adhere when pressed together; the drops that cling to the window-glass in a shower of rain, are all effects of cohesion, entirely independent of atmospheric pressure, and are included in the same analytical formula[1], which expresses all the circumstances accurately, although the laws, according to which the forces of cohesion and repulsion vary, are unknown. It is more than probable that the spherical form of the sun and planets is due to the force of cohesion, as they have every appearance of having been at one period in a state of fusion.

A very remarkable instance of cohesion has occasionally

[1] Note 156

been observed in plate-glass manufactories. After the large plates of glass of which the mirrors are to be made have received their last polish, they are carefully wiped and laid on their edges with their surfaces resting on one another. In the course of time the cohesion has sometimes been so powerful, that they could not be separated without breaking. Instances have occurred where two or three have been so perfectly united, that they have been cut, and their edges polished, as if they had been fused together, and so great was the force required to make the surfaces slide, that one tore off a portion of the surface of the other.

The size of the ultimate particles of matter must be small in the extreme. Organised beings, possessing life and all its functions, have been discovered so small, that a million of them would occupy less space than a grain of sand. The malleability of gold, the perfume of musk, the odour of flowers, and many other instances might be given of the excessive minuteness of the atoms of matter, yet from a variety of circumstances it may be inferred, that matter is not infinitely divisible. Dr Wollaston has shown, that in all probability the atmospheres of the sun and planets, as well as of the earth, consist of ultimate atoms no longer divisible, and, if so, that our atmosphere only extends to that point where the terrestrial attraction is balanced by the elasticity of the air. The definite proportions of chemical compounds afford one of the best proofs that the divisibility of matter has a limit. The cohesive force, which has been the subject of the preceding considerations, only unites particles of the same kind of matter, whereas affinity is the mutual attraction between particles of different kinds of matter, and, when

modified by the electric state of the particles, has been assigned as the cause of chemical combinations.

It is a permanent and universal law in all unorganised bodies, hitherto analysed, that the composition of substances is definite and invariable, the same compound always consisting of the same elements united together in the same proportions Two substances may, indeed, be mixed, but they will not combine to form a third substance different from both, unless their component particles unite in definite proportions, that is to say, one part, by weight, of one of the substances, will unite with one part, by weight, of the other, or with two parts, or three, or four, &c., so as to form a new substance, but in any other proportions they will only be mechanically mixed For example, one part, by weight, of hydrogen gas, will combine with eight parts, by weight, of oxygen gas, and form water; or it will unite with sixteen parts, by weight, of oxygen, and form a substance called deutoxide of hydrogen; but, added to any other weight of oxygen, it will produce one or both of these compounds mingled with the portion of oxygen or hydrogen in excess The law of definite proportion, established by Dr. Dalton, on the principle that every compound body consists of a combination of the atoms of its constituent parts, is of universal application, and is, in fact, one of the most important discoveries in physical science, furnishing information previously unhoped for, with regard to the most secret and minute operations of nature, in disclosing the relative weights of the ultimate atoms of matter. Thus, an atom of oxygen, uniting with an atom of hydrogen, forms the compound water. But, as every drop of water, however small, consists of eight parts, by weight, of oxygen, and one part, by weight, of hydrogen, it follows that an atom of oxygen is eight

times heavier than an atom of hydrogen. In the same manner, sulphuretted hydrogen gas consists of sixteen parts, by weight, of sulphur, and one of hydrogen; therefore an atom of sulphur is sixteen times heavier than an atom of hydrogen. Also, carbonic oxide is constituted of six parts by weight of carbon, and eight of oxygen, and as an atom of oxygen has eight times the weight of an atom of hydrogen, it follows that an atom of carbon is six times heavier than one of hydrogen. Since the same definite proportion holds in the composition of all substances that have been examined, it may be concluded that there are great differences in the weights of the ultimate particles of matter. M. Gay Lussac discovered, that gases unite together by their bulk or volumes, in such simple and definite proportions as one to one, one to two, one to three, &c. For example, one volume or measure of oxygen unites with two volumes or measures of hydrogen in the formation of water.

Affinity, modified by the electrical condition of the particles of matter, has hitherto been believed to be the cause of chemical combinations. However, Dr. Faraday has proved, by recent experiments, on bodies both in solution and fusion, that chemical affinity is merely a result of the electrical state of the particles of matter. Now, it must be observed, that the composition of bodies, as well as their decomposition, may be accomplished by means of electricity, and Dr. Faraday has found, that this chemical composition and decomposition, by a given current of electricity, is always accomplished according to the laws of definite proportions; and that the quantity of electricity requisite for the decomposition of a substance is exactly the quantity necessary for its composition. Thus, the quantity of

electricity which can decompose a grain weight of water, is exactly equal to the quantity of electricity which unites the elements of that grain of water together, and is equivalent to the quantity of atmospheric electricity which is active in a very powerful thunder storm. These laws are universal, and are of that high and general order that characterise all great discoveries.

Dr. Faraday has given a singular instance of cohesive force inducing chemical combination, by the following experiment, which seems to be nearly allied to the discovery made by M. Dœbereiner, in 1823, of the spontaneous combustion of spongy platina[1] exposed to a stream of hydrogen gas mixed with common air. A plate of platina, with extremely clean surfaces, when plunged into oxygen and hydrogen gas, mixed in the proportions which are found in the constitution of water, causes the gases to combine, and water to be formed, the platina to become red-hot, and at last an explosion to take place; the only conditions necessary for this curious experiment being excessive purity in the gases and in the surface of the plate. A sufficiently pure metallic surface can only be obtained by immersing the platina in very strong hot sulphuric acid, and then washing it in distilled water, or by making it the positive pole of a pile in dilute sulphuric acid. It appears that the force of cohesion, as well as the force of affinity, exerted by particles of matter, extends to all the particles within a very minute distance. Hence the platina, while drawing the particles of the two gases towards its surface, by its great cohesive attraction, brings them so near to one another, that they come within the sphere of their mutual affinity, and a chemical combination takes place. Dr. Faraday attributes the effect,

[1] Note 157.

in part also, to a diminution in the elasticity of the gaseous particles, on their sides adjacent to the platina, and to their perfect mixture or association, as well as to the positive action of the metal in condensing them against its surface by its attractive force. The particles, when chemically united, run off the surface of the metal, in the form of water, by their gravitation, or pass away as aqueous vapour, and make way for others.

The particles of matter are so small, that nothing is known of their form, further than the dissimilarity of their different sides in certain cases, which appears from their reciprocal attractions during crystallization being more or less powerful, according to the sides they present to one another. Crystallization is an effect of molecular attraction, regulated by certain laws, according to which atoms of the same kind of matter unite in regular forms,— a fact easily proved by dissolving a piece of alum in pure water. The mutual attraction of the particles is destroyed by the water, but if it be evaporated, they unite, and form in uniting, eight-sided figures called octahedrons.[1] These, however, are not all the same. Some have their angles cut off, others their edges, and some both, while the remainder take the regular form. It is quite clear that the same circumstances which cause the aggregation of a few particles would, if continued, cause the addition of more, and the process would go on as long as any particles remain free round the primitive nucleus, which would increase in size, but would remain unchanged in form, the figure of the particles being such, as to maintain the regularity and smoothness of the surfaces of the solid and their mutual inclinations. A broken crystal will, by degrees, resume its regular figure, when put back again into the

[1] Note 174.

solution of alum, which shows, that the internal and external particles are similar, and have a similar attraction for the particles held in solution. The original conditions of aggregation, which make the molecules of the same substance unite in different forms, must be very numerous, since of carbonate of lime alone there are many hundreds of varieties, and certain it is, from the motion of polarised light through rock crystal, that a very different arrangement of particles is requisite to produce an extremely small change in external form. A variety of substances, in crystallising, combine chemically with a certain portion of water, which in a dry state forms an essential part of their crystals, and, according to the experiments of MM. Haidinger and Mitscherlich, seems in some cases to give the peculiar determination to their constituent molecules. These gentlemen have observed, that the same substance, crystallising at different temperatures, unites with different quantities of water, and assumes a corresponding variety of forms. Seleniate of zinc, for example, unites with three different portions of water, and assumes three different forms, according as its temperature in the act of crystallising is hot, lukewarm, or cold. Sulphate of soda, also, which crystallises at 90° of Fahrenheit, without water of crystallisation, combines with water at the ordinary temperature, and takes a different form. Heat appears to have a great influence on the phenomena of crystallisation; not only when the particles of matter are free, but even when firmly united, it dissolves their union and gives them another determination. Professor Mitscherlich found, that prismatic crystals of sulphate of nickel[1], exposed to a summer's sun in a close vessel, had their internal structure so completely altered,

[1] Note 159

without any exterior change, that when broken open they were composed of octahedrons with square bases. The original aggregation of the internal particles had been dissolved, and a disposition given to arrange themselves in a crystalline form. Crystals of sulphate of magnesia and of sulphate of zinc, gradually heated in alcohol, till it boils, lose their transparency by degrees, and when opened are found to consist of innumerable minute crystals, totally different in form from the whole crystals; and prismatic crystals of zinc[1] are changed in a few seconds into octahedrons, by the heat of the sun; other instances might be given of the influence of even moderate degrees of temperature on molecular attraction in the interior of substances. It must be observed in passing, that these experiments give entirely new views with regard to the constitution of solid bodies. We are led from the mobility of fluids to expect great changes in the relative position of their molecules, which must be in perpetual motion even in the stillest water or calmest air; but we were not prepared to find motion to such an extent in the interior of solids. That their particles were brought nearer by cold and pressure, or removed farther from one another by heat, was to be expected, but it could not have been anticipated that their relative positions could be so entirely changed as to alter their mode of aggregation. It follows, from the low temperature at which these changes are effected, that there is probably no portion of inorganic matter that is not in a state of relative motion.

Professor Mitscherlich's discoveries with regard to the forms of crystallised substances, as connected with their chemical character, have thrown additional light on the constitution of material bodies. There is a certain

[1] Note 160.

set of crystalline forms which are not susceptible of variation, as the die or cube[1], which may be small or large, but is invariably a solid bounded by six square surfaces or planes. Such, also, is the tetrahedron[2] or four-sided solid, contained by four equal-sided triangles. Several other solids belong to this class, which is called the Tessular system of crystallisation. There are other crystals which, though bounded by the same number of sides, and having the same form, are yet susceptible of variation; as for instance, the eight sided figure with a square base, called an octahedron[3], which is sometimes flat and low, and sometimes acute and high. Now, it was formerly believed, that identity of form in all crystals not belonging to the Tessular system, indicated identity of chemical composition. Professor Mitscherlich, however, has shown that not to be the case, but that substances, differing to a certain degree in chemical composition, have the property of assuming the same crystalline form. For example, the neutral phosphate of soda, and the arseniate of soda, crystallise in the very same form, contain the same quantities of acid, alkali, and water of crystallization, yet they differ so far, that the one contains arsenic, and the other an equivalent quantity of phosphorus. Substances having such properties are said to be isomorphous, that is, equal in form. Of these there are many groups, each group having the same form, and similarity though not identity of chemical composition. For instance, one of the isomorphous groups is that consisting of certain chemical substances called the protoxides of iron, copper, zinc, nickel, and manganese, all of which are identical in form, and contain the same quantity of oxygen, but differ in the respective metals they contain,

[1] Note 161. [2] Note 162. [3] Note 163.

which are, however, nearly in the same proportion in each. All these circumstances tend to prove, that substances having the same crystalline form must consist of ultimate atoms, having the same figure, and arranged in the very same order; so that the form of crystals is dependent on their atomic constitution.

All crystallised bodies have joints called cleavages, at which they split more easily than in other directions; on this property the whole art of cutting diamonds depends. Each substance splits in a manner and in forms peculiar to itself. For example, all the hundreds of forms of carbonate of lime split into six-sided figures, called rhombohedrons[1], whose alternate angles measure 105 55° and 75 05°, however far the division may be carried; and, therefore, the ultimate particle of carbonate of lime is presumed to have that form. However this may be, it is certain that all the various crystals of that mineral may be formed, by building up six-sided solids of the form described, in the same manner as children build houses with miniature bricks. It may be imagined that a wide difference may exist between the particles of an unformed mass, and a crystal of the same substance,—between the common shapeless limestone and the pure and limpid crystal of Iceland spar, yet chemical analysis detects none; their ultimate atoms are identical, and crystallisation shows that the difference arises only from the mode of aggregation. Besides, all substances either crystallise naturally, or may be made to do so by art. Liquids crystallise in freezing, vapours by sublimation[2], and hard bodies when fused, crystallise in cooling. Hence it may be inferred, that all substances are composed of atoms, on whose magnitude, density and form, their nature and qualities depend;

[1] Note 164. [2] Note 165.

and as these qualities are unchangeable, the ultimate particles of matter must be incapable of wear, and the same now as when created

The oscillations of the atmosphere, and the changes in its temperature, are measured by variations in the heights of the barometer and thermometer. But the actual length of the liquid columns depend not only upon the force of gravitation, but upon the cohesive force, or reciprocal attraction between the molecules of the liquid and those of the tube containing it This peculiar action of the cohesive force is called capillary attraction, or capillarity If a glass tube of extremely fine bore, such as a small thermometer tube, be plunged into a cup of water or spirit of wine, the liquid will immediately rise in the tube above the level of that in the cup, and the surface of the little column thus suspended will be a hollow hemisphere, whose diameter is the interior diameter of the tube If the same tube be plunged into a cupful of mercury, the liquid will also rise in the tube, but it will never attain the level of that in the cup, and its surface will be a hemisphere whose diameter is also the diameter of the tube.[1] The elevation or depression of the same liquid in different tubes of the same matter, is in the inverse ratio of their internal diameters[2], and altogether independent of their thickness Whence it follows, that the molecular action is insensible at sensible distances, and that it is only the thinnest possible film of the interior surface of the tubes that exerts a sensible action on the liquid So much indeed is this the case, that when tubes of the same bore are completely wetted with water throughout their whole extent, mercury will rise to the same height in all of them, whatever be their thickness or density, be-

[1] Note 166 [2] Note 167

cause the minute coating of moisture is sufficient to remove the internal column of mercury beyond the sphere of attraction of the tube, and to supply the place of a tube by its own capillary attraction. The forces which produce the capillary phenomena, are the reciprocal attraction of the tube and the liquid, and of the liquid particles on one another; and in order that the capillary column may be in equilibrio, the weight of that part of it which rises above or sinks below the level of the liquid in the cup, must balance these forces.

The estimation of the action of the liquid is a difficult part of this problem. La Place, Dr. Young, and other mathematicians, have considered the liquid within the tube to be of uniform density; but M. Poisson, in one of those masterly productions in which he elucidates the most abstruse subjects, has proved that the phenomena of capillary attraction, depend upon a rapid decrease in the density of the liquid column throughout an extremely small space at its surface. Every indefinitely thin layer of a liquid is compressed by the liquid above it, and supported by that below. Its degree of condensation depends upon the magnitude of the compressing force, and, as this force decreases rapidly towards the surface, where it vanishes, the density of the liquid decreases also. M. Poisson has shown, that when this force is omitted, the capillary surface becomes plane, and that the liquid in the tube will neither rise above nor sink below the level of that in the cup. But, in estimating the forces, it is also necessary to include the variation in the density of the capillary surface round the edges, from the attraction of the tube.

The direction of the resulting force, determines the curvature of the surface of the capillary column. In order that a liquid may be in equilibrio, the force re-

sulting from all the forces acting upon it must be perpendicular to the surface. Now, it appears that, as glass is more dense than water or alcohol, the resulting force will be inclined towards the interior side of the tube, therefore the surface of the liquid must be more elevated at the sides of the tube than in the centre, in order to be perpendicular to it, so that it will be concave, as in the thermometer. But, as glass is less dense than mercury, the resulting force will be inclined from the interior side of the tube[1], so that the surface of the capillary column must be more depressed at the sides of the tube than in the centre, in order to be perpendicular to the resulting force, and is consequently convex, as may be perceived in the mercury of the barometer when rising. The absorption of moisture by sponges, sugar, salt, &c. are familiar examples of capillary attraction. Indeed, the pores of sugar are so minute, that there seems to be no limit to the ascent of the liquid. Wine is drawn up in a curve on the interior surface of a glass, tea rises above its level on the side of a cup, but if the glass or cup be too full, their edges attract the liquid downwards and give it a rounded form. A column of liquid will rise above or sink below its level, between two plane parallel surfaces when near to one another, according to the relative densities of the plates and the liquid[2], and the phenomena will be exactly the same, as in a cylindrical tube whose diameter is double the distance of the plates from each other. If the two surfaces be very near to one another, and touch each other at one of their upright edges, the liquid will rise highest at the edges that are in contact, and will gradually diminish in height as the surfaces become more separated. The whole outline of the liquid column

[1] Note 168. [2] Note 169.

will have the form of a hyperbola. Indeed, so universal is the action of capillarity, that solids and liquids cannot touch one another without producing a change in the form of the surface of the liquid.

The attractions and repulsions arising from capillarity present many curious phenomena If two plates of glass or metal, both of which are either dry or wet, be partly immersed in a liquid parallel to one another, the liquid will be raised or depressed close to their surfaces, but will maintain its level through the rest of the space that separates them. At such a distance they neither attract nor repel one another. But the instant they are brought so near as to make the level part of the liquid disappear and the two curved parts of it meet, the two plates will rush towards each other and remain pressed together.[1] If one of the surfaces be wet and the other dry, they will repel one another when so near as to have a curved surface of liquid between them, but if forced to approach a little nearer the repulsion will be overcome, and they will attract each other as if they were both wet or both dry Two balls of pith or wood floating in water, or two balls of tin floating in mercury, attract one another as soon as they are so near that the surface of the liquid is curved between them. Two ships in the ocean may be brought into collision by this principle But two balls, one of which is wet and the other dry, repel one another as soon as the liquid which separates them is curved at its surface A bit of tea leaf is attracted by the edge of the cup if wet, and repelled when dry, provided it be not too far from the edge, and the cup moderately full, if too full, the contrary takes place. It is probable that the rise of the sap in vegetables is chiefly owing to capillarity.

[1] Note 170.

SECTION XV.

ANALYSIS OF THE ATMOSPHERE.—ITS PRESSURE.—LAW OF DECREASE IN DENSITY.—LAW OF DECREASE IN TEMPERATURE.—MEASUREMENT OF HEIGHTS BY THE BAROMETER.—GREAT HOLLOW IN CENTRAL ASIA.—EXTENT OF THE ATMOSPHERE.—OSCILLATIONS.—BAROMETRICAL VARIATIONS CORRESPONDING TO PHASES OF THE MOON NOT OWING TO GRAVITATION.—TRADE WINDS.—COUNTER CURRENTS.

The atmosphere is not homogeneous. It appears from analysis that, of 100 parts, 79 are azotic gas, and 21 oxygen, the great source of combustion and animal heat. Besides these, there are three or four parts of carbonic acid gas in 1000 parts of atmospheric air. These proportions are found to be the same at all heights hitherto attained by man. The air is an elastic fluid, resisting pressure in every direction, and is subject to the law of gravitation. As the space in the top of the tube of a barometer is a vacuum, the column of mercury suspended by the pressure of the atmosphere on the surface of the cistern is a measure of its weight. Consequently, every variation in the density occasions a corresponding rise or fall in the barometrical column. The pressure of the atmosphere is about fifteen pounds on every square inch, so that the surface of the whole globe sustains a weight of 11449000000 hundreds of millions of pounds. Shell-fish, which have the power of producing a vacuum, adhere to the rocks by a pressure of fifteen pounds upon every square inch of contact.

Since the atmosphere is both elastic and heavy, its density necessarily diminishes in ascending above the surface of the earth, for each stratum of air is compressed only by the weight above it. Therefore the

upper strata are less dense, because they are less compressed, than those below them. Whence it is easy to show, supposing the temperature to be constant, that, if the heights above the earth be taken in increasing arithmetical progression,—that is, if they increase by equal quantities, as by a foot or a mile, the densities of the strata of air, or the heights of the barometer, which are proportional to them, will decrease in geometrical progression. For example, at the level of the sea, if the mean height of the barometer be 29.922 inches, at the height of 18000 feet it will be 14.961 inches, or one half as great; at the height of 36000 feet it will be one fourth as great; at 54000 feet it will be one eighth, and so on, which affords a method of measuring the heights of mountains with considerable accuracy, and would be very simple, if the decrease in the density of the air were exactly according to the preceding law. But it is modified by several circumstances, and chiefly by changes of temperature, because heat dilates the air and cold contracts it, varying $\frac{1}{480}$ of the whole bulk, when at 32°, for every degree of Fahrenheit's thermometer. Experience shows that the heat of the air decreases as the height above the surface of the earth increases. And it appears, from recent investigations, that the mean temperature of space is 58° below the zero point of Fahrenheit, which would probably be the temperature of the surface of the earth also, were it not for the non-conducting power of the air, whence it is enabled to retain the heat of the sun's rays, which the earth imbibes and radiates in all directions. The decrease in heat is very irregular; each authority gives a different estimate; probably because the decrease varies with the latitude as well as the height, and something may be due also to

local circumstances. But, from the mean of five different statements, it seems to be about one degree for every 334 feet, which is the cause of the severe cold and eternal snows on the summits of the Alpine chains. Of the various methods of computing heights from barometrical measurements, that of Mr. Ivory has the advantage of combining accuracy with the greatest simplicity. The most remarkable result of barometrical measurement was recently obtained by Baron von Humboldt, showing that about 18,000 square leagues of the north-west of Asia, including the Caspian Sea and the Lake of Aral, are more than 320 feet below the level of the surface of the ocean in a state of mean equilibrium. This enormous basin is similar to some of those large cavities on the surface of the moon, and is attributed, by M. de Humboldt, to the upheaving of the surrounding mountain-chains of the Himalaya, of Kuen Lun, of Thian-Chan, to those of Armenia, of Erzerum, and of Caucasus, which, by undermining the country to so great an extent, caused it to settle below the usual level of the sea. The very contemplation of the destruction that would ensue from the bursting of any of those barriers which now shut out the sea, is fearful. In consequence of the diminished pressure of the atmosphere, water boils at a lower temperature on the mountain-tops than in the valleys, which induced Fahrenheit to propose this mode of observation as a method of ascertaining their heights. But although an instrument was constructed for that purpose by Archdeacon Wollaston, it does not appear to have been much employed.

The atmosphere, when in equilibrio, is an ellipsoid flattened at the poles from its rotation with the earth. In that state its strata are of uniform density at equal heights above the level of the sea, and it is sensibly of

finite extent, whether it consists of particles infinitely divisible or not. On the latter hypothesis, it must really be finite, and even if its particles be infinitely divisible, it is known, by experience, to be of extreme tenuity at very small heights. The barometer rises in proportion to the superincumbent pressure. At the level of the sea, in the latitude of 45°, and at the temperature of melting ice, the mean height of the barometer being 29.922 inches, the density of air is to the density of a similar volume of mercury, as 1 to 10477.9. Consequently, the height of the atmosphere, supposed to be of uniform density, would be about 4.95 miles. But as the density decreases upwards in geometrical progression, it is considerably higher, probably about fifty miles. The air, even on the mountain tops, is sufficiently rare to diminish the intensity of sound, to affect respiration, and to occasion a loss of muscular strength. The blood burst from the lips and ears of M. de Humboldt as he ascended the Andes, and he experienced the same difficulty in kindling and maintaining a fire at great heights which Marco Polo the Venetian felt on the mountains of Central Asia. At the height of thirty-seven miles, the atmosphere is still dense enough to reflect the rays of the sun when eighteen degrees below the horizon. And although at the height of fifty miles, the bursting of the meteor of 1783 was heard on earth like the report of a cannon, it only proves the immensity of the explosion of a mass, half a mile in diameter, which could produce a sound, capable of penetrating air three thousand times more rare than that we breathe. But even these heights are extremely small when compared with the radius of the earth.

The expansion of the atmosphere from the heat of

the sun occasions diurnal variations in the height of the barometer. There are nocturnal oscillations also as regular as those of the day, though not to the same extent.

The sun and moon disturb the equilibrium of the atmosphere by their attraction, producing oscillations similar to those in the ocean, which ought to occasion periodic variations in the heights of the barometer. These, however, are so extremely small, that their existence in latitudes far removed from the equator is doubtful. M. Arago has lately been even led to conclude, that the barometrical variations corresponding to the phases of the moon are the effects of some special cause, totally different from attraction, of which the nature and mode of action are unknown. La Place seems to think that the flux and reflux distinguishable at Paris, may be occasioned by the rise and fall of the ocean, which forms a variable base to so great a portion of the atmosphere.

The attraction of the sun and moon has no sensible effect on the trade winds. The heat of the sun occasions these aerial currents, by rarefying the air at the equator, which causes the cooler and more dense part of the atmosphere to rush along the surface of the earth to the equator, while that which is heated is carried along the higher strata to the poles, forming two counter currents in the direction of the meridian. But the rotatory velocity of the air, corresponding to its geographical position, decreases towards the poles. In approaching the equator, it must therefore revolve more slowly than the corresponding parts of the earth, and the bodies on the surface of the earth must strike against it with the excess of their velocity, and, by its re-action,

they will meet with a resistance contrary to their motion of rotation. So that the wind will appear to a person supposing himself to be at rest, to blow in a direction nearly though not altogether contrary to the earth's rotation; because these currents will still retain a part of their northerly and southerly impetus, which, combining with their deficiency of rotatory velocity, will make them appear to blow from the north-east on one side of the equator, and from the south-east on the other, which is the direction of the trade winds. These winds, however, are not felt at all under the line, because the easterly tendency of the two great polar currents is gradually diminished as they approach the equator, by the friction of the earth, which slowly imparts a portion of its rotatory velocity to them as they pass along, and when they meet in the equator they destroy one another's impetus. The equator does not exactly coincide with the line which separates the trade winds north and south of it. That line of separation depends upon the total difference of heat in the two hemispheres, arising from the distribution of land and water, and other causes.

The polar currents, from defect of rotatory velocity, tend by their friction near the equator, to diminish the velocity of the earth's rotation, while on the contrary, the equatorial or upper currents carry their excess of rotatory velocity north and south. And, as they occasionally come to the surface in their passage to the poles, they act on the earth by their friction, as a strong south-west wind in the northern hemisphere, and as a north-west wind in the southern. In this manner the equilibrium of rotation is maintained. Sir John Herschel ascribes to this cause the western and

south-western gales, so prevalent in our latitudes, and also the west winds, which are so constant in the North Atlantic.

There are many proofs of the existence of the counter currents above the trade winds. On the Peak of Teneriffe, the prevailing winds are from the west The ashes of the volcano of St Vincent's, in the year 1812, were carried to windward as far as the island of Barbadoes, by the upper current The captain of a Bristol ship declared that, on that occasion, dust from St Vincent's fell to the depth of five inches on the deck at the distance of 500 miles to the eastward Light clouds have frequently been seen moving rapidly from west to east at a very great height above the trade winds, which were sweeping along the surface of the ocean in a contrary direction.

SECTION XVI.

SOUND — PROPAGATION OF SOUND ILLUSTRATED BY A FIELD OF STANDING CORN. — NATURE OF WAVES — PROPAGATION OF SOUND THROUGH THE ATMOSPHERE — INTENSITY. — NOISE — A MUSICAL SOUND — QUALITY — PITCH — EXTENT OF HUMAN HEARING — VELOCITY OF SOUND IN AIR, WATER, AND SOLIDS — CAUSES OF THE OBSTRUCTION OF SOUND — LAW OF ITS INTENSITY — REFLECTION OF SOUND. — ECHOS — THUNDER — REFRACTION OF SOUND — INTERFERENCE OF SOUNDS

ONE of the most important uses of the atmosphere is the conveyance of sound. Without the air, death-like silence would prevail through nature, for, in common with all substances, it has a tendency to impart vibrations to bodies in contact with it. Therefore undulations received by the air, whether it be from a sudden impulse, such as an explosion, or the vibrations of a musical chord, are propagated in every direction, and produce the sensation of sound upon the auditory nerves. A bell rung, under the exhausted receiver of an air-pump, is inaudible, which shows that the atmosphere is really the medium of sound. In the small undulations of deep water in a calm, the vibrations of the liquid particles are made in the vertical plane, that is, up and down, or at right angles to the direction of the transmission of the waves. But the vibrations of the particles of air which produce sound differ from these, being performed in the same direction in which the waves of sound travel. The propagation of sound may be illustrated by a field of corn agitated by a gust of wind. However irregular the motion of the corn may

seem on a superficial view, it will be found, if the intensity of the wind be constant, that the waves are all precisely similar and equal, and that all are separated by equal intervals, and move in equal times.

A sudden blast depresses each ear equally and successively in the direction of the wind, but in consequence of the elasticity of the stalks and the force of the impulse, each ear not only rises again as soon as the pressure is removed, but bends back nearly as much in the contrary direction, and then continues to oscillate backwards and forwards, in equal times, like a pendulum, to a less and less extent, till the resistance of the air puts a stop to the motion. These vibrations are the same for every individual ear of corn. Yet as their oscillations do not all commence at the same time, but successively, the ears will have a variety of positions at any one instant. Some of the advancing ears will meet others in their returning vibrations, and as the times of oscillation are equal for all, they will be crowded together at regular intervals. Between these, there will occur equal spaces where the ears will be few, in consequence of being bent in opposite directions; and at other equal intervals they will be in their natural upright positions. So that over the whole field there will be a regular series of condensations and rarefactions among the ears of corn, separated by equal intervals, where they will be in their natural state of density. In consequence of these changes, the field will be marked by an alternation of bright and dark bands. Thus the successive waves which fly over the corn with the speed of the wind are totally distinct from, and entirely independent of, the extent of the oscillations of each individual ear, though both take place in the same direction. The length of a wave is equal to the space between two ears

precisely in the same state of motion, or which are moving similarly, and the time of the vibration of each ear is equal to that which elapses between the arrival of two successive waves at the same point. The only difference between the undulations of a corn-field and those of the air which produce sound is, that each ear of corn is set in motion by an external cause, and is uninfluenced by the motion of the rest; whereas in air, which is a compressible and elastic fluid, when one particle begins to oscillate, it communicates its vibrations to the surrounding particles, which transmit them to those adjacent, and so on continually. Hence, from the successive vibrations of the particles of air, the same regular condensations and rarefactions take place as in the field of corn, producing waves throughout the whole mass of air, though each molecule, like each individual ear of corn, never moves far from its state of rest. The small waves of a liquid, and the undulations of the air, like waves in the corn, are evidently not real masses moving in the direction in which they are advancing, but merely outlines, motions, or forms rushing along, and comprehending all the particles of an undulating fluid, which are at once in a vibratory state. It is thus that an impulse given to any one point of the atmosphere is successively propagated in all directions, in waves diverging as from the centre of a sphere to greater and greater distances, but with decreasing intensity, in consequence of the increasing number of particles of inert matter which the force has to move; like the waves formed in still water by a fallen stone, which are propagated circularly all around the centre of disturbance.[1] These successive spherical waves are only the repercussions of the condensations and mo-

[1] Note 164.

tions of the first particles to which the impulse was given.

The intensity of sound depends upon the violence and extent of the initial vibrations of air, but whatever they may be, each undulation, when once formed, can only be transmitted straight forwards, and never returns back again, unless when reflected by an opposing obstacle The vibrations of the aerial molecules are always extremely small, whereas the waves of sound vary from a few inches to several feet. The various kinds of musical instruments, the human voice, and that of animals, the singing of birds, the hum of insects, the roar of the cataract, the whistling of the wind, and the other nameless peculiarities of sound, at once show an infinite variety in the modes of aerial vibrations, and the astonishing acuteness and delicacy of the ear, thus capable of appreciating the minutest differences in the laws of molecular oscillation

All mere noises are occasioned by irregular impulses communicated to the ear, and if they be short, sudden, and repeated beyond a certain degree of quickness, the ear loses the intervals of silence, and the sound appears continuous. Still such sounds will be mere noise in order to produce a musical sound, the impulses, and, consequently, the undulations of the air, must be all exactly similar in duration and intensity, and must recur after exactly equal intervals of time. If a blow be given to the nearest of a series of broad, flat, and equidistant palisades, set edgewise in a line direct from the ear, each palisade will repeat or echo the sound, and these echos returning to the ear, at successive equal intervals of time, will produce a musical note The quality of a musical note depends upon the abruptness, and its intensity upon the violence and extent of the original

impulse In the theory of harmony the only property of sound taken into consideration is the pitch, which varies with the rapidity of the vibrations. The grave, or low tones, are produced by very slow vibrations, which increase in frequency, as the note becomes more acute Very deep tones are not heard by all alike, and Dr Wollaston, who made a variety of experiments on the sense of hearing, found that many people, though not at all deaf, are quite insensible to the cry of the bat or the cricket, while to others it is painfully shrill From this he concluded, that human hearing is limited to about nine octaves, extending from the lowest note of the organ to the highest known cry of insects, and he observes, with his usual originality, that, "as there is nothing in the nature of the atmosphere to prevent the existence of vibrations incomparably more frequent than any of which we are conscious, we may imagine that animals, like the Grylli, whose powers appear to commence nearly where ours terminate, may have the faculty of hearing still sharper sounds which we do not know to exist, and that there may be other insects hearing nothing in common with us, but endowed with a power of exciting, and a sense which perceives vibrations of the same nature, indeed, as those which constitute our ordinary sounds, but so remote, that the animals who perceive them may be said to possess another sense, agreeing with our own, solely in the medium by which it is excited"

M Savart, so well known for the number and beauty of his researches in acoustics, has proved that a high note of a given intensity being heard by some ears and not by others, must not be attributed to its pitch, but to its feebleness. The experiments of that gentleman, as well as those more recently made by Professor Wheat-

stone, show, that if the pulses could be rendered sufficiently powerful, it would be difficult to fix a limit to human hearing at either end of the scale M Savart had a wheel made about nine inches in diameter with 360 teeth set at equal distances round its rim, so that while in motion each tooth successively hit on a piece of card. The tone increased in pitch with the rapidity of the rotation, and was very pure when the number of strokes did not exceed three or four thousand in a second, but beyond that it became feeble and indistinct. With a wheel of a larger size, a much higher tone could be obtained, because, the teeth being wider apart, the blows were more intense and more separated from one another With 720 teeth on a wheel thirty-two inches in diameter, the sound produced by 12,000 strokes in a second was audible, which corresponds to 24,000 vibrations of a musical chord. So that the human ear can appreciate a sound which only lasts the 24,000th part of a second This note was distinctly heard by M Savart and by several people who were present, which convinced him, that with another apparatus, still more acute sounds might be rendered audible.

For the deep tones M Savart employed a bar of iron, two feet eight inches long, about two inches broad, and half an inch in thickness, which revolved about its centre, as if its arms were the spokes of wheel. When such a machine rotates, it impresses a motion on the air similar to its own, and when a thin board or card is brought close to its extremities the current of air is momentarily interrupted at the instant each arm of the bar passes before the card, it is compressed above the card and dilated below, but the instant the spoke has passed, a rush of air to restore equilibrium makes a kind of explosion, and when these

succeed each other rapidly, a musical note is produced, of a pitch proportional to the velocity of the revolution When M Savart turned this bar slowly, a succession of single beats was heard, as the velocity became greater the sound was only a rattle, but as soon as it was sufficient to give eight beats in a second, a very deep musical note was distinctly audible, corresponding to sixteen single vibrations in a second, which is the lowest that has been hitherto produced When the velocity of the bar was much increased, the intensity of the sound was hardly bearable The spokes of a revolving wheel produce the sensation of sound, on the very same principle that a burning stick whirled round gives the impression of a luminous circle The vibrations excited in the organ of hearing by one beat have not ceased before another impulse is given Indeed, it is indispensable that the impressions made upon the auditory nerves should encroach upon each other, in order to produce a full and continued note. On the whole, M Savart has come to the conclusion, that the most acute sounds would be heard with as much ease as those of a lower pitch, if the duration of the sensation produced by each pulse could be diminished proportionally to the augmentation of the number of pulses in a given time, and, on the contrary, if the duration of the sensation produced by each pulse could be increased in proportion to their number in a given time, that the deepest tones would be as audible as any of the others

The velocity of sound is uniform, and is independent of the nature, extent, and intensity of the primitive disturbance. Consequently sounds of every quality and pitch travel with equal speed The smallest difference in their velocity is incompatible either with harmony or melody, for notes of different pitches and

intensities, sounded together at a little distance, would arrive at the ear in different times. A rapid succession of notes would in this case produce confusion and discord. But as the rapidity with which sound is transmitted depends upon the elasticity of the medium through which it has to pass, whatever tends to increase the elasticity of the air must also accelerate the motion of sound. On that account its velocity is greater in warm than in cold weather, supposing the pressure of the atmosphere constant. In dry air, at the freezing temperature, sound travels at the rate of 1089 feet in a second, and at 62° of Fahrenheit, its speed is 1123 feet in the same time, or 765 miles an hour, which is about three fourths of the diurnal velocity of the earth's equator. Since all the phenomena of the transmission of sound are simple consequences of the physical properties of the air, they have been predicted and computed rigorously by the laws of mechanics. It was found, however, that the velocity of sound, determined by observation, exceeded what it ought to have been theoretically by 173 feet, or about one sixth of the whole amount. La Place suggested that this discrepancy might arise from the increased elasticity of the air, in consequence of a developement of latent heat[1] during the undulations of sound, and the result of calculation fully confirmed the accuracy of his views. The aërial molecules, being suddenly compressed, give out their latent heat; and, as air is too bad a conductor to carry it rapidly off, it occasions a momentary and local rise of temperature, which, increasing the consecutive expansion of the air, causes a still greater developement of heat, and as it exceeds that which is absorbed in the next rarefaction, the air becomes yet warmer, which favours the transmission of sound. Ana-

[1] Note 171.

lysis gives the true velocity of sound, in terms of the elevation of temperature that a mass of air is capable of communicating to itself, by the disengagement of its own latent heat, when it is suddenly compressed in a given ratio. This change of temperature, however, cannot be obtained directly by experiment; but by inverting the problem, and assuming the velocity of sound as given by experiment, it was computed that the temperature of a mass of air is raised nine tenths of a degree, when the compression is equal to $\frac{1}{116}$ of its volume

Probably all liquids are elastic, though considerable force is required to compress them. Water suffers a condensation of nearly 0 0000496 for every atmosphere of pressure, and is consequently capable of conveying sound even more rapidly than air, the velocity in the former being 4708 feet in a second A person under water hears sounds made in air feebly, but those produced in water very distinctly. According to the experiments of M. Colladon, the sound of a bell was conveyed under water through the Lake of Geneva to the distance of about nine miles He also perceived that the progress of sound through water is greatly impeded by the interposition of any object, such as a projecting wall, consequently sound under water resembles light, in having a distinct shadow It has much less in air, being transmitted all round buildings, or other obstacles, so as to be heard in every direction, though often with a considerable diminution of intensity, as when a carriage turns the corner of a street

The velocity of sound, in passing through solids, is in proportion to their hardness, and is much greater than in air or water. A sound which takes some time in travelling through the air, passes almost instantaneously

along a wire six hundred feet long, consequently it is heard twice,—first as communicated by the wire, and afterwards through the medium of the air. The facility with which the vibrations of sound are transmitted along the grain of a log of wood is well known. Indeed, they pass through iron, glass, and some kinds of wood, at the rate of 18,530 feet in a second. The velocity of sound is obstructed by a variety of circumstances, such as falling snow, fog, rain, or any other cause which disturbs the homogeneity of the medium through which it has to pass. M. de Humboldt says, that it is on account of the greater homogeneity of the atmosphere during the night that sounds are then better heard than during the day, when its density is perpetually changing from partial variations of temperature. His attention was called to this subject by the rushing noise of the great cataracts of the Orinoco, which seemed to be three times as loud during the night as in the day, from the plain surrounding the Mission of the Apures. This he illustrated by a celebrated experiment. A tall glass, half full of champagne, cannot be made to ring as long as the effervescence lasts. In order to produce a musical note, the glass, together with the liquid it contains, must vibrate in unison as a system, which it cannot do, in consequence of the fixed air rising through the wine and disturbing its homogeneity, because, the vibrations of the gas being much slower than those of the liquid, the velocity of the sound is perpetually interrupted. For the same reason, the transmission of sound as well as light is impeded in passing through an atmosphere of variable density. Sir John Herschel, in his admirable Treatise on Sound, thus explains the phenomenon.— "It is obvious," he says, "that sound as well as light must be obstructed, stifled, and dissipated from its ori-

ginal direction by the mixture of air of different temperatures, and consequently elasticities, and thus the same cause which produces that extreme transparency of the air at night, which astronomers alone fully appreciate, renders it also more favourable to sound. There is no doubt, however, that the universal and dead silence, generally prevalent at night, renders our auditory nerves sensible to impressions which would otherwise escape notice. The analogy between sound and light is perfect in this as in so many other respects. In the general light of day the stars disappear. In the continual hum of voices, which is always going on by day, and which reach us from all quarters, and never leave the ear time to attain complete tranquillity, those feeble sounds which catch our attention at night make no impression The ear, like the eye, requires long and perfect repose to attain its utmost sensibility"

Many instances may be brought in proof of the strength and clearness with which sound passes over the surface of water or ice Lieutenant Foster was able to carry on a conversation across Port Bowen harbour, when frozen, a distance of a mile and a half.

The intensity of sound depends upon the extent of the excursions of the fluid molecules, on the energy of the transient condensations and dilatations, and on the greater or less number of particles which experience these effects We estimate that intensity by the impetus of these fluid molecules on our organs, which is consequently as the square of the velocity, and not by their inertia, which is as the simple velocity. Were the latter the case, there would be no sound, because the inertia of the receding waves of air would destroy the equal and opposite inertia of those advancing; whence it may be concluded, that the intensity of sound di-

minishes inversely as the square of the distance from its origin. In a tube, however, the force of sound does not decay as in open air, unless, perhaps, by friction against the sides. M Biot found, from a number of highly interesting experiments which he made on the pipes of the aqueducts in Paris, that a continued conversation could be carried on, in the lowest possible whisper, through a cylindrical tube about 3120 feet long, the time of transmission through that space being 2·79 seconds. In most cases sound diverges in all directions, so as to occupy at any one time a spherical surface, but Dr Young has shown that there are exceptions, as, for example, when a flat surface vibrates only in one direction. The sound is then most intense when the ear is at right angles to the surface, whereas it is scarcely audible in a direction precisely perpendicular to its edge In this case it is impossible that the whole of the surrounding air can be affected in the same manner, since the particles behind the sounding surface must be moving towards it, whenever the particles before it are retreating. Hence in one half of the surrounding sphere of air its motions are retrograde, while in the other half they are direct, consequently at the edges, where these two portions meet, the motions of the air will neither be retrograde nor direct, and therefore it must be at rest

It appears from theory as well as daily experience, that sound is capable of reflection from surfaces[1], according to the same laws as light. Indeed, any one who has observed the reflection of the waves from a wall on the side of a river, or very wide canal, after the passage of a steam-boat, will have a perfect idea of the reflection of sound and of light. As every substance in nature is

[1] Note 172

more or less elastic, it may be agitated according to its own law, by the impulse of a mass of undulating air; but reciprocally, the surface by its re-action will communicate its undulations back again into the air. Such reflections produce echos, and as a series of them may take place between two or more obstacles, each will cause an echo of the original sound, growing fainter and fainter till it dies away, because sound, like light, is weakened by reflection. Should the reflecting surface be concave towards a person, the sound will converge towards him with increased intensity, which will be greater still if the surface be spherical and concentric with him. Undulations of sound diverging from one focus of an elliptical shell[1] converge in the other after reflection. Consequently a sound from the one will be heard in the other as if it were close to the ear. The rolling noise of thunder has been attributed to reverberation between different clouds, which may possibly be the case to a certain extent. But Sir John Herschel is of opinion, that an intensely prolonged peal is probably owing to a combination of sounds, because the velocity of electricity being incomparably greater than that of sound, the thunder may be regarded as originating in every point of a flash of lightning at the same instant. The sound from the nearest point will arrive first, and if the flash run in a direct line from a person, the noise will come later and later from the remote points of its path in a continued roar. Should the direction of the flash be inclined, the succession of sounds will be more rapid and intense, and if the lightning describe a circular curve round a person, the sound will arrive from every point at the same instant with a stunning crash. In like manner, the subterranean noises heard during

[1] Note 172.

earthquakes, like distant thunder, may arise from the consecutive arrival at the ear, of undulations propagated at the same instant from nearer and more remote points; or, if they originate in the same point, the sound may come by different routes through strata of different densities.

Sounds under water are heard very distinctly in the air immediately above, but the intensity decays with great rapidity as the observer goes farther off, and is altogether inaudible at the distance of two or three hundred yards. So that waves of sound, like those of light, in passing from a dense to a rare medium, are not only refracted, but suffer total reflection at very oblique incidences.[1]

The laws of interference extend also to sound. It is clear that two equal and similar musical strings will be in unison, if they communicate the same number of vibrations to the air in the same time. But if two such strings be so nearly in unison, that one performs a hundred vibrations in a second, and the other a hundred and one in the same period,—during the first few vibrations, the two resulting sounds will combine to form one of double the intensity of either, because the aërial waves will sensibly coincide in time and place; but the one will gradually gain on the other, till, at the fiftieth vibration, it will be half an oscillation in advance. Then the waves of air which produce the sound being sensibly equal, but the receding part of the one coinciding with the advancing part of the other, they will destroy one another, and occasion an instant of silence. The sound will be renewed immediately after, and will gradually increase till the hundredth vibration, when the two waves will combine to produce a sound double the in-

[1] Note 182.

tensity of either. These intervals of silence and greatest intensity, called beats, will recur every second; but if the notes differ much from one another, the alternations will resemble a rattle; and if the strings be in perfect unison, there will be no beats, since there will be no interference. Thus, by interference is meant the co-existence of two undulations, in which the lengths of the waves are the same. And as the magnitude of an undulation may be diminished by the addition of another transmitted in the same direction, it follows, that one undulation may be absolutely destroyed by another, when waves of the same length are transmitted in the same direction, provided that the maxima of the undulations are equal, and that one follows the other by half the length of a wave. A tuning-fork affords a good example of interference. When that instrument vibrates, its two branches alternately recede from and approach one another; each communicates its vibrations to the air, and a musical note is the consequence. If the fork be held upright, about a foot from the ear, and turned round its axis while vibrating, at every quarter revolution the sound will scarcely be heard, while at the intermediate points it will be strong and clear. This phenomenon arises from the interference of the undulations of air coming from the two branches of the fork. When the two branches coincide, or when they are at equal distances from the ear, the waves of air combine to reinforce each other; but at the quadrants where the two branches are at unequal distances from the ear, the lengths of the waves differ by half an undulation, and consequently destroy one another.

SECTION XVII

VIBRATION OF MUSICAL STRINGS — HARMONIC SOUNDS — NODES — VIBRATION OF AIR IN WIND-INSTRUMENTS — VIBRATION OF SOLIDS — VIBRATING PLATES — BELLS — HARMONY. — SOUNDING BOARDS — FORCED VIBRATIONS — RESONANCE. — SPEAKING MACHINES.

WHEN the particles of elastic bodies are suddenly disturbed by an impulse, they return to their natural position by a series of isochronous vibrations, whose rapidity, force, and permanency depend upon the elasticity, the form, and the mode of aggregation which unites the particles of the body. These oscillations are communicated to the air, and on account of its elasticity they excite alternate condensations and dilatations in the strata of the fluid nearest to the vibrating body from thence they are propagated to a distance A string or wire stretched between two pins, when drawn aside and suddenly let go, will vibrate till its own rigidity and the resistance of the air reduce it to rest These oscillations may be rotatory, in every plane, or confined to one plane, according as the motion is communicated In the piano-forte, where the strings are struck by a hammer at one extremity, the vibrations probably consist of a bulge running to and fro, from end to end Different modes of vibration may be obtained from the same sonorous body. Suppose a vibrating string to give the lowest C of the piano-forte, which is the fundamental note of the string, if it be lightly touched exactly in the middle, so as to retain that point at rest, each half will then vibrate twice as fast as the whole, but in opposite direc-

tions, the ventral or bulging segments will be alternately above and below the natural position of the string, and the resulting note will be the octave above C. When a point at a third of the length of the string is kept at rest, the vibration will be three times as fast as those of the whole string, and will give the twelfth above C. When the point of rest is one fourth of the whole, the oscillations will be four times as fast as those of the fundamental note, and will give the double octave, and so on. These acute sounds are called the harmonics of the fundamental note. It is clear from what has been stated, that the string thus vibrating could not give these harmonics, unless it divided itself spontaneously at its aliquot parts into two, three, four, or more segments in opposite states of vibration, separated by points actually at rest. In proof of this, pieces of paper placed on the string at the half, third, fourth, or other aliquot points, according to the corresponding harmonic sound, will remain on it during its vibration, but will instantly fly off from any of the intermediate points. The points of rest, called the nodal points of the string, are a mere consequence of the law of interferences. For if a rope fastened at one end be moved to and fro at the other extremity, so as to transmit a succession of equal waves along it, they will be successively reflected when they arrive at the other end of the rope by the fixed point, and in returning they will occasionally interfere with the advancing waves, and as these opposite undulations will at certain points destroy one another, the point of the rope in which this happens will remain at rest. Thus a series of nodes and ventral segments will be produced, whose number will depend upon the tension and the frequency of the alternate motions communicated to the movable end. So, when a string fixed at both ends is put in

motion by a sudden blow at any point of it, the primitive impulse divides itself into two pulses running opposite ways, which are each totally reflected at the extremities, and, running back again along the whole length, are again reflected at the other ends. And thus they will continue to run backwards and forwards, crossing one another at each traverse, and occasionally interfering, so as to produce nodes; so that the motion of a string fastened at both ends consists of a wave or pulse, continually doubled back on itself by reflection at the fixed extremities.

Harmonics frequently co-exist with the fundamental sound in the same vibrating body. If one of the lowest strings of the piano-forte be struck, an attentive ear will not only hear the fundamental note, but will detect all the others sounding along with it, though with less and less intensity as the pitch becomes higher. According to the law of co-existing undulations, the whole string and each of its aliquot parts are in different and independent states of vibration at the same time; and as all the resulting notes are heard simultaneously, not only the air, but the ear also, vibrates in unison with each at the same instant.[1]

Harmony consists in an agreeable combination of sounds. When two cords perform their vibrations in the same time, they are in unison. But when their vibrations are so related as to have a common period after a few oscillations, they produce concord. Thus, where the vibrations of two strings bear a very simple relation to each other, as where one of them makes two, three, four, &c. vibrations in the time the other makes one, or if it accomplishes three, four, &c. vibrations while the

[1] Note 174.

other makes two, the result is a concord, which is the more perfect the shorter the common period. In discords, on the contrary, the beats are distinctly audible, which produces a disagreeable and harsh effect, because the vibrations do not bear a simple relation to one another, as where one of two strings makes eight vibrations while the other accomplishes fifteen The pleasure afforded by harmony is attributed by Dr Young to the love of order, and to a predilection for a regular recurrence of sensations, natural to the human mind, which is gratified by the perfect regularity and rapid recurrence of the vibrations The love of poetry and dancing he conceives to arise in some degree from the rhythm of the one and the regularity of the motions in the other

A blast of air passing over the open end of a tube, as over the reeds in Pan's pipes, over a hole in one side, as in the flute, or through the aperture called a reed, with a flexible tongue, as in the clarinet, puts the internal column of air into longitudinal vibrations by the alternate condensations and rarefactions of its particles. At the same time the column spontaneously divides itself into nodes, between which the air also vibrates longitudinally, but with a rapidity inversely proportional to the length of the divisions, giving the fundamental note or one of its harmonics. The nodes are produced on the principle of interferences, by the reflection of the longitudinal undulations of the air at the ends of the pipe, as in the musical string, only that in one case the undulations are longitudinal, and in the other transverse.

"A pipe, either open or shut at both ends, when sounded, vibrates entire, or divides itself spontaneously into two, three, four, &c. segments separated by nodes. The whole column gives the fundamental

note by waves or vibrations of the same length with the pipe. The first harmonic is produced by waves half as long as the tube, the second harmonic by waves a third as long, and so on. The harmonic segments in an open and shut pipe are the same in number, but differently placed In a shut pipe the two ends are nodes, but in an open pipe there is half a segment at each extremity, because the air at these points is neither rarefied nor condensed, being in contact with that which is external If one of the ends of the open pipe be closed, its fundamental note will be an octave lower, the air will now divide itself into three, five, seven, &c. segments, and the wave producing its fundamental note will be twice as long as the pipe, so that it will be doubled back [1] All these notes may be produced separately, by varying the intensity of the blast Blowing steadily and gently, the fundamental note will sound, when the force of the blast is increased, the note will all at once start up an octave, when the intensity of the wind is augmented, the twelfth will be heard, and by continuing to increase the force of the blast the other harmonics may be obtained, but no force of wind will produce a note intermediate between these. The harmonics of a flute may be obtained in this manner, from the lowest C or D upwards, without altering the fingering, merely by increasing the intensity of the blast, and altering the form of the lips. Pipes of the same dimensions, whether they be made of lead, glass, or wood, give the same tone as to pitch under the same circumstances, which shows that the air alone produces the sound

Metal springs fastened at one end, when forcibly bent, endeavour to return to rest by a series of vibrations, which give very pleasing tones, as in musical boxes. Various

[1] Note 175

musical instruments have recently been constructed consisting of metallic springs thrown into vibration by a current of air. Among the most perfect of these are Mr. Wheatstone's Symphonion, Concertina, and Æolian Organ, instruments of different effects and capabilities, but all possessing considerable execution and expression.

The Syren is an ingenious instrument, devised by M. Cagniard de la Tour, for ascertaining the number of pulsations in a second corresponding to each pitch: the notes are produced by jets of air passing through small apertures arranged at regular distances in a circle on the side of a box, before which a disc revolves pierced with the same number of holes. During a revolution of the disc the currents are alternately intercepted and allowed to pass as many times as there are apertures in it, and a sound is produced whose pitch depends on the velocity of rotation.

A glass or metallic rod, when struck at one end, or rubbed in the direction of its length with a wet finger, vibrates longitudinally, like a column of air, by the alternate condensation and expansion of its constituent particles, which produces a clear and beautiful musical note of a high pitch, on account of the rapidity with which these substances transmit sound. Rods, surfaces, and in general all undulating bodies, resolve themselves into nodes. But, in surfaces, the parts which remain at rest during their vibrations are lines, which are curved or plane according to the substance, its form, and the mode of vibration. If a little fine dry sand be strowed over the surface of a plate of glass or metal, and if undulations be excited by drawing the bow of a violin across its edge, it will emit a musical sound, and the sand will immediately arrange itself in the nodal lines, where alone it will accumulate and remain at rest, because the segments of the surface on each side will be

in different states of vibration, the one being elevated while the other is depressed, and as these two motions meet in the nodal lines, they neutralise one another These lines vary in form and position with the part where the bow is drawn across, and the point by which the plate is held. The motion of the sand shows in what direction the vibrations take place If they be perpendicular to the surface, the sand will be violently tossed up and down, till it finds the points of rest If they be tangential, the sand will only creep along the surface to the nodal lines Sometimes the undulations are oblique, or compounded of both the preceding If a bow be drawn across one of the angles of a square plate of glass or metal held firmly by the centre, the sand will arrange itself in two straight lines parallel to the sides of the plate, and crossing in the centre, so as to divide it into four equal squares, whose motions will be contrary to each other Two of the diagonal squares will make their excursions on one side of the plate, while the other two make their vibrations on the other side of it. This mode of vibration produces the lowest tone of the plates.[1] If the plate be still held by the centre, and the bow applied to the middle of one of the sides, the vibrations will be more rapid, and the tone will be a fifth higher than in the preceding case; now the sand will arrange itself from corner to corner, and will divide the plate into four equal triangles, each pair of which will make their excursions on opposite sides of the plate The nodal lines and pitch vary not only with the point where the bow is applied, but with the point by which the plate is held, which being at rest, necessarily determines the direction of one of the quiescent lines. The forms assumed by the sand in square plates are very

[1] Note 176

numerous, corresponding to all the various modes of vibration. The lines in circular plates are even more remarkable for their symmetry, and upon them the forms assumed by the sand may be classed in three systems The first is the diametrical system, in which the figures consist of diameters dividing the circumference of the plate into equal parts, each of which is in a different state of vibration from those adjacent. Two diameters, for example, crossing at right angles, divide the circumference into four equal parts, three diameters divide it into six equal parts, four divide it into eight; and so on In a metallic plate, these divisions may amount to thirty-six or forty The next is the concentric system, where the sand arranges itself in circles, having the same centre with the plate, and the third is the compound system, where the figures assumed by the sand are compounded of the other two, producing very complicated and beautiful forms Galileo seems to have been the first to notice the points of rest and motion in the sounding board of a musical instrument, but to Chladni is due the whole discovery of the symmetrical forms of the nodal lines in vibrating plates[1] Mr Wheatstone has shown, in a paper read before the Royal Society in 1833, that all Chladni's figures, and indeed all the nodal figures of vibrating surfaces, result from very simple modes of vibration, oscillating isochronously, and superposed upon each other, the resulting figure varying with the component modes of vibration, the number of the superpositions, and the angles at which they are superposed. For example, if a square plate be vibrating so as to make the sand arrange itself in straight lines parallel to one side of the plate,

[1] Note 177

and if, in addition to this, such vibrations be excited as would have caused the sand to form in lines perpendicular to the first had the plate been at rest, the combined vibrations will make the sand form in lines from corner to corner.[1]

M. Savart's experiments on the vibrations of flat glass rulers are highly interesting Let a lamina of glass, $27^{\text{in}}{\cdot}56$ long, 0·59 of an inch broad, and 0·06 of an inch in thickness, be held by the edges in the middle, with its flat surface horizontal If this surface be strewed with sand, and set in longitudinal vibration by rubbing its under surface with a wet cloth, the sand on the upper surface will arrange itself in lines parallel to the ends of the ruler, always in one or other of two systems[2] Although the same one of the two systems will always be produced by the same plate of glass, yet among different plates of the preceding dimensions, even though cut from the same sheet side by side, one will invariably exhibit one system, and the other the other, without any visible reason for the difference Now if the positions of these quiescent lines be marked on the upper surface, and if the plate be turned so that the lower surface becomes the upper one, the sand being strewed and vibrations excited as before, the nodal lines will still be parallel to the ends of the lamina, but their positions will be intermediate between those of the upper surface[3] Thus it appears that all the motions of one half of the thickness of the lamina, or ruler, are exactly contrary to those of the corresponding points of the other half If the thickness of the lamina be increased, the other dimensions remaining the same, the sound will not vary, but the number of nodal lines will be less. When the breadth of the lamina

[1] Note 178 [2] Note 179 [3] Note 180

exceeds the 0.6 of an inch, the nodal lines become curved, and are different on the two surfaces. A great variety of forms are produced by increasing the breadth and changing the form of the surface, but in all it appears that the motions in one half of the thickness are opposed to those in the other half.

M. Savart also found, by placing small paper rings round a cylindrical tube or rod, so as to rest upon it at one point only, that when the tube or rod is continually turned on its axis in the same direction, the rings slide along during the vibrations, till they come to a quiescent point, where they rest. By thus tracing these nodal lines he discovered that they twist in a spiral or cork-screw round rods and cylinders, making one or more turns according to the length; but at certain points, varying in number according to the mode of vibration of the rod, the screw stops, and recommences on the other side, though it is turned in a contrary direction; that is, on one side it is a right-handed screw, on the other a left.[1] The nodal lines in the interior surface of the tube are perfectly similar to those in the exterior, but they occupy intermediate positions. If a small ivory ball be put within the tube, it will follow these nodal lines when the tube is made to revolve on its axis.

All solids which ring when struck, such as bells, drinking-glasses, gongs, &c., have their shape momentarily and forcibly changed by the blow, and from their elasticity, or tendency to resume their natural form, a series of undulations take place, owing to the alternate condensations and rarefactions of the particles of solid matter. These have also their harmonic tones, and, consequently, nodes. Indeed, generally, when a rigid system of any form whatever vibrates either trans-

[1] Note 181.

versely or longitudinally, it divides itself into a certain number of parts, which perform their vibrations without disturbing one another These parts are at every instant in alternate states of undulation, and as the points or lines where they join partake of both, they remain at rest, because the opposing motions destroy one another.

The air, notwithstanding its rarity, is capable of transmitting its undulations when in contact with a body susceptible of admitting and exciting them It is thus that sympathetic undulations are excited by a body vibrating near insulated tended strings, capable of following its undulations, either by vibrating entire, or by separating themselves into their harmonic divisions If two cords equally stretched, of which one is twice or three times longer than the other, be placed side by side, and if the shorter be sounded, its vibrations will be communicated by the air to the other, which will be thrown into such a state of vibration that it will be spontaneously divided into segments equal in length to the shorter string When a tuning-fork receives a blow, and is made to rest upon a piano-forte during its vibration, every string which either by its natural length or by its spontaneous subdivisions, is capable of executing corresponding vibrations, responds in a sympathetic note Some one or other of the notes of an organ are generally in unison with one of the panes, or with the whole sash of a window, which consequently resound when these notes are sounded A peal of thunder has frequently the same effect The sound of very large organ-pipes is generally inaudible till the air be set in motion by the undulations of some of the superior accords, and then its sound becomes extremely energetic. Recurring vibrations occasionally influence each other's periods. For example, two adjacent organ-pipes, nearly

in unison, may force themselves into concord, and two clocks, whose rates differed considerably when separate, have been known to beat together when fixed to the same wall. Nay, one clock has been known to force the pendulum of another into motion, when merely standing on the same stone pavement. These forced oscillations, which correspond in their periods with those of the exciting cause, are to be traced in every department of physical science. Several instances of them have already occurred in this work. Such are the tides, which follow the sun and moon in all their motions and periods. The nutation of the earth's axis also corresponds with the period, and represents the motion of the nodes of the moon, and is again reflected back to the moon, and may be traced in the nutation of the lunar orbit. And, lastly, the acceleration of the moon's mean motion represents the action of the planets on the earth reflected by the sun to the moon.

In consequence of the facility with which the air communicates undulations, all the phenomena of vibrating plates may be exhibited by sand strewed on paper or parchment, stretched over a harmonica glass, or large bell-shaped tumbler. In order to give due tension to the paper or vellum, it must be wetted, stretched over the glass, gummed round the edges, allowed to dry, and varnished over to prevent changes in its tension from the humidity of the atmosphere. If a circular disc of glass be held concentrically over this apparatus, with its plane parallel to the surface of the paper, and set in vibration by drawing a bow across its edge, so as to make sand on its surface take any of Chladni's figures, the sand on the paper will assume the very same form, in consequence of the vibrations of the disc being communicated to the paper by the air.

When the disc is removed slowly in a horizontal direction, the forms on the paper will correspond with those on the disc, till the distance is too great for the air to convey the vibrations. If the disc while vibrating be gradually more and more inclined to the horizon, the figures on the paper will vary by degrees, and when the vibrating disc is perpendicular to the horizon, the sand on the paper will form into straight lines parallel to the surface of the disc, by creeping along it instead of dancing up and down. If the disc be made to turn round its vertical diameter while vibrating, the nodal lines on the paper will revolve, and exactly follow the motion of the disc. It appears from this experiment, that the motions of the aerial molecules in every part of a spherical wave, propagated from a vibrating body as a centre, are parallel to each other, and not divergent like the radii of a circle. When a slow air is played on a flute near this apparatus, each note calls up a particular form in the sand, which the next note effaces to establish its own. The motion of the sand will even detect sounds that are inaudible. By the vibrations of sand on a drum-head the besieged have discovered the direction in which a counter-mine was working. M. Savart, who made these beautiful experiments, employed this apparatus to discover nodal lines in masses of air. He found that the air of a room, when thrown into undulations by the continued sound of an organ-pipe, or by any other means, divides itself into masses separated by nodal curves of double curvature, such as spirals, on each side of which the air is in opposite states of vibration. He even traced these quiescent lines going out at an open window, and for a considerable distance in the open air. The sand is violently agitated where the undulations of the air are greatest, and remains at rest

in the nodal lines M Savart observed, that when he moved his head away from a quiescent line towards the right the sound appeared to come from the right, and when he moved it towards the left the sound seemed to come from the left, because the molecules of air are in different states of motion on each side of the quiescent line.

A musical string gives a very feeble sound when vibrating alone, on account of the small quantity of air set in motion But, when attached to a sounding board, as in the harp and piano-forte, it communicates its undulations to that surface, and from thence to every part of the instrument, so that the whole system vibrates isochronously, and by exposing an extensive undulating surface, which transmits its undulations to a great mass of air, the sound is much reinforced. The intensity is greatest when the vibrations of the string or sounding body are perpendicular to the sounding board, and least when they are in the same plane with it. The sounding board of the piano-forte is better disposed than that of any other stringed instrument, because the hammers strike the strings so as to make them vibrate at right angles to it In the guitar, on the contrary, they are struck obliquely, which renders the tone feeble, unless when the sides, which also act as a sounding board, are deep. It is evident that the sounding board and the whole instrument are agitated at once by all the superposed vibrations excited by the simultaneous or consecutive notes that are sounded, each having its perfect effect independently of the rest A sounding board not only reciprocates the different degrees of pitch, but all the nameless qualities of tone. This has been beautifully illustrated by Professor Wheatstone in a series of experiments on the transmission, through solid conductors, of musical performances, from the harp, piano, violin,

clarinet, &c. He found that all the varieties of pitch, quality, and intensity are perfectly transmitted with their relative gradations, and may be communicated, through conducting wires or rods of very considerable length, to a properly disposed sounding-board in a distant apartment The sounds of an entire orchestra may be transmitted and reciprocated by connecting one end of a metallic rod with a sounding-board near the orchestra, so placed as to resound to all the instruments, and the other end with the sounding-board of a harp, piano, or guitar, in a remote apartment Mr. Wheatstone observes, "the effect of this experiment is very pleasing, the sounds, indeed, have so little intensity as scarcely to be heard at a distance from the reciprocating instrument, but on placing the ear close to it, a diminutive band is heard in which all the instruments preserve their distinctive qualities, and the pianos and fortes, the crescendos and diminuendos their relative contrasts Compared with an ordinary band heard at a distance through the air, the effect is as a landscape seen in miniature beauty through a concave lens compared with the same scene viewed by ordinary vision through a murky atmosphere"

Every one is aware of the reinforcement of sound by the resonance of cavities. When singing or speaking near the aperture of a wide-mouthed vessel, the intensity of some one note in unison with the air in the cavity is often augmented to a great degree. Any vessel will resound if a body vibrating the natural note of the cavity be placed opposite to its orifice, and be large enough to cover it, or, at least, to set a large portion of the adjacent air in motion. For the sound will be alternately reflected by the bottom of the cavity and the undulating body at its mouth. The first impulse of

the undulating substance will be reflected by the bottom of the cavity, and then by the undulating body, in time to combine with the second new impulse. This reinforced sound will also be twice reflected in time to conspire with the third new impulse, and as the same process will be repeated on every new impulse, each will combine with all its echos to reinforce the sound prodigiously. Mr. Wheatstone, to whose ingenuity we are indebted for so much new and valuable information on the theory of sound, has given some very striking instances of resonance. If one of the branches of a vibrating tuning-fork be brought near the embouchure of a flute, the lateral apertures of which are stopped so as to render it capable of producing the same sound as the fork, the feeble and scarcely audible sound of the fork will be augmented by the rich resonance of the column of air within the flute, and the tone will be full and clear The sound will be found greatly to decrease by closing or opening another aperture, for the alteration in the length of the column of air renders it no longer fit perfectly to reciprocate the sound of the flute. This experiment may be made on a concert flute with a C tuning-fork. But Mr. Wheatstone observes, that in this case it is generally necessary to finger the flute for B, because, when a flute is blown into with the mouth, the under-lip partly covers the embouchure, which renders the sound about a semitone flatter than it would be were the embouchure entirely uncovered. He has also shown, by the following experiment, that any one among several simultaneous sounds may be rendered separately audible. If two bottles be selected, and tuned by filling them with such a quantity of water as will render them unisonant with two tuning-forks which differ in pitch, on bringing both of the vibrating tuning-forks to

the mouth of each bottle alternately, in each case that sound only will be heard which is reciprocated by the unisonant bottle.

Several attempts have been made to imitate the articulation of the letters of the alphabet. About the year 1779, MM. Kratzenstein, of St. Petersburgh, and Kempelen, of Vienna, constructed instruments which articulated many letters, words, and even sentences. Mr. Willis, of Cambridge, has recently adapted cylindrical tubes to a reed, whose length can be varied at pleasure by sliding joints. Upon drawing out the tube, while a column of air from the bellows of an organ is passing through it, the vowels are pronounced in the order, *i*, *e*, *a*, *o*, *u*. On extending the tube, they are repeated, after a certain interval, in the inverted order *u*, *o*, *a*, *e*, *i*. After another interval, they are again obtained in the direct order, and so on. When the pitch of the reed is very high, it is impossible to sound some of the vowels, which is in perfect correspondence with the human voice, female singers being unable to pronounce *u* and *o* in their high notes. From the singular discoveries of M. Savart on the nature of the human voice, and the investigations of Mr. Willis on the mechanism of the larynx, it may be presumed that ultimately the utterance or pronunciation of modern languages will be conveyed, not only to the eye, but also to the ear, of posterity. Had the ancients possessed the means of transmitting such definite sounds, the civilised world would still have responded in sympathetic notes at the distance of hundreds of ages.

SECTION XVIII.

REFRACTION.—ASTRONOMICAL REFRACTION AND ITS LAWS.—FORMATION OF TABLES OF REFRACTION.—TERRESTRIAL REFRACTION.—ITS QUANTITY.—INSTANCES OF EXTRAORDINARY REFRACTION.—REFLECTION.—INSTANCES OF EXTRAORDINARY REFLECTION.—LOSS OF LIGHT BY THE ABSORBING POWER OF THE ATMOSPHERE.—APPARENT MAGNITUDE OF SUN AND MOON IN THE HORIZON.

NOT only every thing we hear, but all we see, is through the medium of the atmosphere. Without some knowledge of its action upon light, it would be impossible to ascertain the position of the heavenly bodies, or even to determine the exact place of very distant objects upon the surface of the earth; for in consequence of the refractive power of the air, no distant object is seen in its true position.

All the celestial bodies appear to be more elevated than they really are, because the rays of light, instead of moving through the atmosphere in straight lines, are continually inflected towards the earth. Light passing obliquely out of a rare into a denser medium, as from vacuum into air, or from air into water, is bent or refracted from its course towards a perpendicular to that point of the denser surface where the light enters it.[1] In the same medium, the sine of the angle contained between the incident ray and the perpendicular is in a constant ratio to the sine of the angle contained by the refracted ray and the same perpendicular; but this ratio varies with the refracting medium. The denser

[1] Note 182.

the medium, the more the ray is bent. The barometer shows, that the density of the atmosphere decreases as the height above the earth increases. Direct experiments prove, that the refractive power of the air increases with its density. It follows, therefore, that if the temperature be uniform, the refractive power of the air is greatest at the earth's surface and diminishes upwards.

A ray of light from a celestial object falling obliquely on this variable atmosphere, instead of being refracted at once from its course, is gradually more and more bent during its passage through it, so as move in a vertical curved line, in the same manner as if the atmosphere consisted of an infinite number of strata of different densities. The object is seen in the direction of a tangent to that part of the curve which meets the eye, consequently the apparent altitude[1] of the heavenly bodies is always greater than their true altitude. Owing to this circumstance, the stars are seen above the horizon after they are set, and the day is lengthened from a part of the sun being visible, though he really is behind the rotundity of the earth. It would be easy to determine the direction of a ray of light through the atmosphere, if the law of the density were known; but as this law is perpetually varying with the temperature, the case is very complicated. When rays pass perpendicularly from one medium into another, they are not bent; and experience shows, that in the same surface, though the sines of the angles of incidence and refraction retain the same ratio, the refraction increases with the obliquity of incidence.[2] Hence it appears, that the refraction is greatest at the horizon, and at the zenith there is none. But it is proved that at all heights above ten degrees, refraction varies nearly as the tangent of the

[1] Note 188. [2] Note 189.

angular distance of the object from the zenith, and wholly depends upon the heights of the barometer and thermometer For the quantity of refraction at the same distance from the zenith, varies nearly as the height of the barometer, the temperature being constant, and the effect of the variation of temperature is to diminish the quantity of refraction by about its 480th part for every degree in the rise of Fahrenheit's thermometer Not much reliance can be placed on celestial observations within less than ten or twelve degrees of the horizon, on account of irregular variations in the density of the air near the surface of the earth, which are sometimes the cause of very singular phenomena. The humidity of the air produces no sensible effect on its refractive power

Bodies, whether luminous or not, are only visible by the rays which proceed from them. As the rays must pass through strata of different densities in coming to us, it follows that, with the exception of stars in the zenith, no object either in or beyond our atmosphere is seen in its true place. But the deviation is so small in ordinary cases, that it causes no inconvenience, though in astronomical and trigonometrical observations a due allowance must be made for the effects of refraction. Dr Bradley's tables of refraction were formed by observing the zenith distances of the sun at his greatest declinations, and the zenith distances of the pole-star above and below the pole The sum of these four quantities is equal to 180°, diminished by the sum of the four refractions, whence the sum of the four refactions was obtained, and from the law of the variation of refraction determined by theory, he assigned the quantity due to each altitude.[1] The mean horizontal

[1] Note 184

refraction is about 35′ 6″, and at the height of forty-five degrees it is 58″ 36. The effect of refraction upon the same star above and below the pole was noticed by Alhazen, a Saracen astronomer of Spain, in the ninth century, but its existence was known to Ptolemy in the second, though he was ignorant of its quantity

The refraction of a terrestrial object is estimated differently from that of a celestial body It is measured by the angle contained between the tangent to the curvilineal path of the ray, where it meets the eye, and the straight line joining the eye and the object [1] Near the earth's surface, the path of the ray may be supposed to be circular, and the angle of this path between tangents at the two extremities of this arc, is called the horizontal angle. The quantity of terrestrial refraction is obtained, by measuring contemporaneously the elevation of the top of a mountain above a point in the plain at its base, and the depression of that point below the top of the mountain. The distance between these two stations is the chord of the horizontal angle, and it is easy to prove that double the refraction is equal to the horizontal angle, diminished by the difference between the apparent elevation and the apparent depression Whence it appears that, in the mean state of the atmosphere, the refraction is about the fourteenth part of the horizontal angle

Some very singular appearances occur from the accidental expansion or condensation of the strata of the atmosphere contiguous to the surface of the earth, by which distant objects, instead of being elevated, are depressed. Sometimes, being at once both elevated and depressed, they appear double, one of the images being direct, and the other inverted. In consequence of the

[1] Note 185.

upper edges of the sun and moon being less refracted than the lower, they often appear to be oval when near the horizon. The looming also, or elevation of coasts, mountains, and ships, when viewed across the sea, arises from unusual refraction. A friend of the author's, while standing on the plains of Hindostan, saw the whole upper chain of the Himalaya mountains start into view, from a sudden change in the density of the air, occasioned by a heavy shower after a very long course of dry and hot weather. Single and double images of objects at sea, arising from sudden changes of temperature, which are not so soon communicated to the water on account of its density as to the air, occur more rarely, and are of shorter duration than similar appearances on land. In 1818, Captain Scoresby, whose observations on the phenomena of the polar seas are so valuable, recognised his father's ship by its inverted image in the air, although the vessel itself was below the horizon. He afterwards found that she was seventeen miles beyond the horizon, and thirty miles distant. Two images are sometimes seen suspended in the air over a ship, one direct and the other inverted, with their topmasts or their hulls meeting, according as the inverted image is above or below the direct image.[1] Dr. Wollaston has proved that these appearances are owing to the refraction of the rays through media of different densities, by the very simple experiment of looking along a red hot poker at a distant object. Two images are seen, one direct and another inverted, in consequence of the change induced by the heat in the density of the adjacent air. He produced the same effect by a saline or saccharine solution with water and spirit of wine floating upon it.[2]

[1] Note 186. [2] Note 187.

Many of the phenomena that have been ascribed to extraordinary refraction seem to be occasioned by a partial or total reflection of the rays of light at the surfaces of strata of different densities.[1] It is well known, that when light falls obliquely upon the external surface of a transparent medium, as on a plate of glass, or stratum of air, one portion is reflected and the other transmitted. But when light falls very obliquely upon the internal surface, the whole is reflected and not a ray is transmitted. In all cases the angles made by the incident and reflected rays with a perpendicular to the surface being equal. As the brightness of the reflected image depends on the quantity of light, those arising from total reflection must be by far the most vivid. The delusive appearance of water, so well known to African travellers, and to the Arab of the desert, as the Lake of the Gazelles, is ascribed to the reflection which takes place between strata of air of different densities, owing to radiation of heat from the arid sandy plains. The mirage described by Captain Mundy, in his Journal of a Tour in India, probably arises from this cause. "A deep precipitous valley below us, at the bottom of which I had seen one or two miserable villages in the morning, bore in the evening a complete resemblance to a beautiful lake; the vapour, which played the part of water, ascending nearly half way up the sides of the vale, and on its bright surface trees and rocks being distinctly reflected. I had not been long contemplating the phenomenon, before a sudden storm came on and dropped a curtain of clouds over the scene."

An occurrence which happened on the 18th of November, 1804, was probably produced by reflection. Dr. Buchan, while watching the rising sun from the

[1] Note 182

cliff about a mile to the east of Brighton, at the instant the solar disc emerged from the surface of the ocean, saw the cliff on which he was standing, a windmill, his own figure, and that of a friend, depicted immediately opposite to him on the sea. This appearance lasted about ten minutes, till the sun had risen nearly his own diameter above the surface of the waves. The whole then seemed to be elevated into the air and successively vanished. The rays of the sun fell upon the cliff at an incidence of 73° from the perpendicular, and the sea was covered with a dense fog many yards in height, which gradually receded before the rising sun. When extraordinary refraction takes place laterally, the strata of variable density are perpendicular to the horizon, and when it is combined with vertical refraction, the objects are magnified as if seen through a telescope. From this cause, on the 26th of July, 1798, the cliffs of France, fifty miles off, were seen as distinctly from Hastings as if they had been close at hand, and even Dieppe was said to have been visible in the afternoon.

The stratum of air in the horizon is so much thicker and more dense than the stratum in the vertical, that the sun's light is diminished 1300 times in passing through it, which enables us to look at him when setting without being dazzled. The loss of light, and consequently of heat, by the absorbing power of the atmosphere, increases with the obliquity of incidence. Of ten thousand rays falling on its surface, 8123 arrive at a given point of the earth if they fall perpendicularly; 7024 arrive, if the angle of direction be fifty degrees; 2831, if it be seven degrees; and only five rays will arrive through a horizontal stratum. Since so great a quantity of light is lost in passing through the atmosphere, many celestial objects may be altogether invisible from the plain,

which may be seen from elevated situations. Diminished splendour and the false estimate we make of distance from the number of intervening objects, lead us to suppose the sun and moon to be much larger when in the horizon than at any other altitude, though their apparent diameters are then somewhat less. Instead of the sudden transitions of light and darkness, the reflective power of the air adorns nature with the rosy and golden hues of the Aurora and twilight. Even when the sun is eighteen degrees below the horizon, a sufficient portion of light remains to show that, at the height of thirty miles it is still dense enough to reflect light. The atmosphere scatters the sun's rays, and gives all the beautiful tints and cheerfulness of day. It transmits the blue light in greatest abundance; the higher we ascend, the sky assumes a deeper hue; but in the expanse of space, the sun and stars must appear like brilliant specks in profound blackness.

SECTION XIX

CONSTITUTION OF LIGHT ACCORDING TO SIR ISAAC NEWTON — ABSORPTION OF LIGHT — COLOURS OF BODIES — CONSTITUTION OF LIGHT ACCORDING TO SIR DAVID BREWSTER — FRAUNHOFER'S DARK LINES — DISPERSION OF LIGHT. — THE ACHROMATIC TELESCOPE — HOMOGENEOUS LIGHT — ACCIDENTAL AND COMPLEMENTARY COLOURS — M. PLATEAU'S EXPERIMENTS — SIR DAVID BREWSTER'S THEORY OF ACCIDENTAL COLOURS

It is impossible thus to trace the path of a sunbeam through our atmosphere without feeling a desire to know its nature, by what power it traverses the immensity of space, and the various modifications it undergoes at the surfaces and in the interior of terrestrial substances

Sir Isaac Newton proved the compound nature of white light, as emitted from the sun, by passing a sunbeam through a glass prism [1], which, separating the rays by refraction, formed a spectrum or oblong image of the sun, consisting of seven colours, red, orange, yellow, green, blue, indigo, and violet, of which the red is the least refrangible, and the violet the most But when he re-united these seven rays by means of a lens, the compound beam became pure white as before He insulated each coloured ray, and finding that it was no longer capable of decomposition by refraction, concluded that white light consists of seven kinds of homogeneous light, and that to the same colour the same refrangibility ever belongs, and to the same refrangibility the same colour. Since the discovery of absorbent media, however, it

[1] Note 169

appears that this is not the constitution of the solar spectrum.

We know of no substance that is either perfectly opaque or perfectly transparent. Even gold may be beaten so thin as to be pervious to light On the contrary, the clearest crystal, the purest air or water, stops or absorbs its rays when transmitted, and gradually extinguishes them as they penetrate to greater depths. On this account, objects cannot be seen at the bottom of very deep water, and many more stars are visible to the naked eye from the tops of mountains than from the valleys. The quantity of light that is incident on any transparent substance is always greater than the sum of the reflected and refracted rays A small quantity is irregularly reflected in all directions by the imperfections of the polish by which we are enabled to see the surface, but a much greater portion is absorbed by the body Bodies that reflect all the rays appear white, those that absorb them all seem black, but most substances, after decomposing the white light which falls upon them, reflect some colours and absorb the rest. A violet reflects the violet rays alone, and absorbs the others Scarlet cloth absorbs almost all the colours except red. Yellow cloth reflects the yellow rays most abundantly, and blue cloth those that are blue. Consequently colour is not a property of matter, but arises from the action of matter upon light. Thus a white ribbon reflects all the rays, but when dyed red the particles of the silk acquire the property of reflecting the red rays most abundantly and of absorbing the others. Upon this property of unequal absorption, the colours of transparent media depend For they also receive their colour from their power of stopping or absorbing some of the colours of white

light and transmitting others. As, for example, black and red inks, though equally homogeneous, absorb different kinds of rays, and when exposed to the sun, they become heated in different degrees, while pure water seems to transmit all rays equally, and is not sensibly heated by the passing light of the sun. The rich dark light transmitted by a smalt-blue finger-glass is not a homogeneous colour, like the blue or indigo of the spectrum, but is a mixture of all the colours of white light, which the glass has not absorbed. The colours absorbed are such as, mixed with the blue tint, would form white light When the spectrum of seven colours is viewed through a thin plate of this glass, they are all visible; and when the plate is very thick, every colour is absorbed between the extreme red and the extreme violet, the interval being perfectly black: but if the spectrum be viewed through a certain thickness of the glass intermediate between the two, it will be found that the middle of the red space, the whole of the orange, a great part of the green, a considerable part of the blue, a little of the indigo, and a very little of the violet, vanish, being absorbed by the blue glass; and that the yellow rays occupy a larger space, covering part of that formerly occupied by the orange on one side, and by the green on the other So that the blue glass absorbs the red light, which, when mixed with the yellow, constitutes orange, and also absorbs the blue light, which, when mixed with the yellow, forms the part of the green space next to the yellow. Hence, by absorption, green light is decomposed into yellow and blue, and orange light into yellow and red. Consequently, the orange and green rays, though incapable of decomposition by refraction, can be resolved by absorption,

and actually consist of two different colours possessing the same degree of refrangibility. Difference of colour, therefore, is not a test of difference of refrangibility, and the conclusion deduced by Newton is no longer admissible as a general truth. By this analysis of the spectrum, not only with blue glass but with a variety of coloured media, Sir David Brewster, so justly celebrated for his optical discoveries, has proved, that the solar spectrum consists of three primary colours, red, yellow, and blue, each of which exists throughout its whole extent, but with different degrees of intensity in different parts, and that the superposition of these three produces all the seven hues according as each primary colour is in excess or defect. Since a certain portion of red, yellow, and blue rays constitute white light, the colour of any point of the spectrum may be considered as consisting of the predominating colour at that point mixed with white light Consequently, by absorbing the excess of any colour at any point of the spectrum above what is necessary to form white light, such white light will appear at that point as never mortal eye looked upon before this experiment, since it possesses the remarkable property of remaining the same after any number of refractions, and of being capable of decomposition by absorption alone

When the prism is very perfect and the sunbeam small, so that the spectrum may be received on a sheet of white paper in its utmost state of purity, it presents the appearance of a ribbon shaded with all the prismatic colours, having its breadth irregularly striped or subdivided by an indefinite number of dark, and sometimes black, lines. The greater number of these rayless lines are so extremely narrow that it is impossible to

see them in ordinary circumstances. The best method is to receive the spectrum on the object glass of a telescope, so as to magnify them sufficiently to render them visible. This experiment may also be made, but in an imperfect manner, by viewing a narrow slit between two nearly closed window shutters through a very excellent glass prism held close to the eye, with its refracting angle parallel to the line of light. When the spectrum is formed by the sun's rays, either direct or indirect — as from the sky, clouds, rainbow, moon, or planets — the black bands are always found to be in the same parts of the spectrum, and under all circumstances to maintain the same relative positions, breadths, and intensities. Similar dark lines are also seen in the light of the stars, in the electric light, and in the flame of combustible substances, though differently arranged, each star and each flame having a system of dark lines peculiar to itself, which remains the same under every circumstance. Dr Wollaston and M Fraunhofer of Munich discovered these lines deficient of rays independently of each other. M Fraunhofer found that their number extends to nearly six hundred. From these he selected seven of the most remarkable, and determined their distances so accurately, that they now form standard and invariable points of reference for measuring the refractive powers of different media on the rays of light, which renders this department of optics as exact as any of the physical sciences. The rays that are wanting in the solar spectrum, which occasion the dark lines, are possibly absorbed by the atmosphere of the sun. If they were absorbed by the earth's atmosphere, the very same rays would be wanting in the spectra from the light of the fixed stars, which is not

the case; for it has already been stated that the position of the dark lines is not the same in spectra from star-light and from the light of the sun. The solar rays reflected from the moon and planets would, most likely, be modified also by their atmospheres, but they are not, for the dark lines have precisely the same positions in the spectra, from the direct and reflected light of the sun.

A sunbeam received on a screen, after passing through a small round hole in a window-shutter, appears like a round white spot; but when a prism is interposed, the beam no longer occupies the same space. It is separated into the prismatic colours, and spread over a line of considerable length, while its breadth remains the same with that of the white spot. The act of spreading or separation is called the dispersion of the coloured rays. Dispersion always takes place in the plane of refraction, and is greater as the angle of incidence is greater. Substances have very different dispersive powers. That is to say, the spectra formed by two equal prisms of different substances, under precisely the same circumstances, are of different lengths. Thus if a prism of flint glass, and one of crown glass, of equal-refracting angles, be presented to two rays of white light, it will be found, that the space over which the coloured rays are dispersed by the flint glass is much greater than that produced by the crown glass, and as the quantity of dispersion depends upon the refracting angle of the prism, the angles of the two prisms may be made such, that when the prisms are placed close together with their edges turned opposite ways, they will exactly oppose each other's action, and will refract the coloured rays equally but in contrary direc-

tions, so that an exact compensation will be effected, and the light will be refracted without colour.[1] The achromatic telescope is constructed on this principle. That instrument consists of a tube with an object-glass or lens at one end, to bring the rays to a focus, and form an image of the distant object, and a magnifying glass at the other end, with which to view the image thus formed. Now it was found that the object-glass, instead of making the rays converge to one point, dispersed them and gave a confused and coloured image; but by constructing it of two lenses in contact, one of flint and the other of crown glass of certain forms and proportions, the dispersion is counteracted, and a perfectly well-defined and colourless image of the object is formed.[2] It was thought to be impossible to produce refraction without colour, till Mr. Hall, a gentleman of Worcestershire, constructed a telescope on this principle in the year 1733, and twenty-five years afterwards the achromatic telescope was brought to perfection by Mr. Dollond, a celebrated optician in London.

A perfectly homogeneous colour is very rarely to be found, but the tints of all substances are most brilliant when viewed in light of their own colour. The red of a wafer is much more vivid in red than in white light; whereas, if placed in homogeneous yellow light, it can no longer appear red, because there is not a ray of red in the yellow light. Were it not that the wafer, like all other bodies whether coloured or not, reflects white light at its outer surface, it would appear absolutely black when placed in yellow light.

After looking steadily for a short time at a coloured

[1] Note 189. [2] Note 190.

object, such as a red wafer, on turning the eyes to a white substance, a green image of the wafer will appear, which is called the accidental colour of red. All tints have their accidental colours:—thus the accidental colour of orange is blue; that of yellow is indigo; of green, reddish-white; of blue, orange-red; of violet, yellow; and of white, black; and *vice versâ*. When the direct and accidental colours are of the same intensity, the accidental is then called the complementary colour, because any two colours are said to be complementary to one another which produce white when combined.

From recent experiments by M. Plateau of Brussels, it appears that two complementary colours from direct impression, which would produce white when combined, produce black, or extinguish one another by their union, when accidental; and also that the combination of all the tints of the solar spectrum produces white light if they be from a direct impression on the eye, whereas blackness results from a union of the same tints if they be accidental. According to Sir David Brewster this phenomenon has been long known, but attributed to the effect of accidental colours on the eye, and not to their actual combination, because an accidental colour cannot be combined with another like the rays of ordinary colours. When the eye sees an accidental colour, such as an accidental red, it is at the time insensible to every other colour. If then the retina be instantly excited by another accidental colour, as an accidental green, for example, the eye will see blackness, not because the accidental red and the accidental green compose black, but because the eye has been successively rendered insensible to the two colours which compose white light. When the image of an object is impressed

on the retina only for a few moments, the picture left is exactly of the same colour with the object, but in an extremely short time the picture is succeeded by the accidental image. If the prevailing impression be a very strong white light, its accidental image is not black, but a variety of colours in succession. With a little attention, it will generally be found that, whenever the eye is affected by one prevailing colour, it sees at the same time the accidental colour, in the same manner as in music the ear is sensible at once to the fundamental note and its harmonic sounds. The imagination has a powerful influence on our optical impressions, and has been known to revive the images of highly luminous objects months and even years afterwards.

SECTION XX.

INTERFERENCE OF LIGHT — UNDULATORY THEORY OF LIGHT — PROPAGATION OF LIGHT — NEWTON'S RINGS — MEASUREMENT OF THE LENGTH OF THE WAVES OF LIGHT, AND OF THE FREQUENCY OF THE VIBRATIONS OF ETHER FOR EACH COLOUR — NEWTON'S SCALE OF COLOURS — DIFFRACTION OF LIGHT — SIR JOHN HERSCHEL'S THEORY OF THE ABSORPTION OF LIGHT — REFRACTION AND REFLEXION OF LIGHT.

NEWTON and most of his immediate successors imagined light to be a material substance, emitted by all self-luminous bodies in extremely minute particles, moving in straight lines with prodigious velocity, which, by impinging upon the optic nerves, produce the sensation of light. Many of the observed phenomena have been successfully explained by this theory; it seems, however, totally inadequate to account for the following circumstances.

When two equal rays of red light, proceeding from two luminous points, fall upon a sheet of white paper in a dark room, they will produce a red spot on it, which will be twice as bright as either ray would produce singly, provided the difference in the lengths of the two beams, from the luminous points to the red spot on the paper, be exactly the 0.0000258th part of an inch. The same effect will take place if the difference in their lengths be twice, three times, four times, &c., that quantity. But if the difference in the lengths of the two rays be equal to one half of the 0.0000258th part of an inch, or to its 1½, 2½, 3½, &c. part, the one light will entirely extinguish the other, and will produce absolute darkness on the paper where the united beams

fall If the difference in the lengths of their paths be equal to the 1½, 2½, 3½, &c. of the 0·0000258th part of an inch, the red spot arising from the combined beams will be of the same intensity which one alone would produce If violet light be employed, the difference in the lengths of the two beams must be equal to the 0·0000157th part of an inch, in order to produce the same phenomena, and for the other colours, the difference must be intermediate between the 0·0000258th and the 0·0000157th part of an inch Similar phenomena may be seen by viewing the flame of a candle through two very fine slits in a card extremely near to one another[1], or by admitting the sun's light into a dark room through a pin-hole about the fortieth of an inch in diameter, and receiving the image on a sheet of white paper. When a slender wire is held in the light, its shadow consists of a bright white bar or stripe in the middle, with a series of alternate black and brightly coloured stripes on each side The rays which bend round the wire in two streams are of equal lengths in the middle stripe, it is consequently doubly bright from their combined effect; but the rays which fall on the paper on each side of the bright stripe, being of such unequal lengths as to destroy one another, form black lines. On each side of these black lines the rays are again of such lengths as to combine to form bright stripes, and so on alternately, till the light is too faint to be visible. When any homogeneous light is used, such as red, the alternations are only black and red, but on account of the heterogeneous nature of white light, the black lines alternate with vivid stripes or fringes of prismatic colours, arising from the superposition of systems of alternate

[1] Note 101

black lines and lines of each homogeneous colour. That the alternation of black lines and coloured fringes actually does arise from the mixture of the two streams of light which flow round the wire, is proved by their vanishing the instant one of the streams is interrupted. It may therefore be concluded, as often as these stripes of light and darkness occur, that they are owing to the rays combining at certain intervals to produce a joint effect, and at others to extinguish one another. Now it is contrary to all our ideas of matter to suppose that two particles of it should annihilate one another under any circumstances whatever; while, on the contrary, two opposing motions may; and it is impossible not to be struck with the perfect similarity between the interferences of small undulations of air and water and the preceding phenomena. The analogy is indeed so perfect that philosophers of the highest authority concur in the supposition that the celestial regions are filled with an extremely rare, imponderable, and highly elastic medium or ether, whose particles are capable of receiving the vibrations communicated to them by self-luminous bodies, and of transmitting them to the optic nerves, so as to produce the sensation of light. The acceleration in the mean motion of Encke's comet, as well as in the mean motion of the comet discovered by M. Biela, renders the existence of such a medium almost certain. It is clear that, in this hypothesis, the alternate stripes of light and darkness are entirely the effect of the interference of the undulations; for, by actual measurement, the length of a wave of the mean red rays of the solar spectrum is equal to the 0·0000258th part of an inch; consequently, when the elevation of the waves combine, they produce double the intensity of light that each would do singly; and when half a

wave combines with a whole, — that is, when the hollow of one wave is filled up by the elevation of another, darkness is the result. At intermediate points between these extremes, the intensity of the light corresponds to intermediate differences in the lengths of the rays.

The theory of interferences is a particular case of the general mechanical law of the superposition of small motions; whence it appears that the disturbance of a particle of an elastic medium, produced by two coexistent undulations, is the sum of the disturbances which each undulation would produce separately; consequently, the particle will move in the diagonal of a parallelogram, whose sides are the two undulations. If, therefore, the two undulations agree in direction, or nearly so, the resulting motion will be very nearly equal to their sum, and in the same direction; if they nearly oppose one another, the resulting motion will be nearly equal to their difference; and if the undulations be equal and opposite, the resultant will be zero, and the particle will remain at rest.

The preceding experiments, and the inferences deduced from them, which have led to the establishment of the doctrine of the undulations of light, are the most splendid memorials of our illustrious countryman Dr. Thomas Young, though Huygens was the first to originate the idea.

It is supposed that the particles of luminous bodies are in a state of perpetual agitation, and that they possess the property of exciting regular vibrations in the ethereal medium, corresponding to the vibrations of their own molecules; and that, on account of its elastic nature, one particle of the ether, when set in motion, communicates its vibrations to those adjacent, which in suc-

cession transmit them to those farther off, so that the primitive impulse is transferred from particle to particle, and the undulating motion darts through ether like a wave in water Although the progressive motion of light is known by experience to be uniform, and in a straight line, the vibrations of the particles are always at right angles to the direction of the ray. The propagation of light is like the spreading of waves in water, but if one ray alone be considered, its motion may be conceived by supposing a rope of indefinite length stretched horizontally, one end of which is held in the hand If it be agitated to and fro at regular intervals, with a motion perpendicular to its length, a series of similar and equal tremors or waves will be propagated along it, and if the regular impulses be given in a variety of planes, as up and down, from right to left, and also in oblique directions, the successive undulations will take place in every possible plane An analogous motion in the ether, when communicated to the optic nerves, would produce the sensation of common light It is evident that the waves which flow from end to end of the cord in a serpentine form are altogether different from the perpendicular vibratory motion of each particle of the rope, which never deviates far from a state of rest So in ether, each particle vibrates perpendicularly to the direction of the ray, but these vibrations are totally different from, and independent of, the undulations which are transmitted through it, in the same manner as the vibrations of each particular ear of corn are independent of the waves that rush from end to end of a harvest-field when agitated by the wind

The intensity of light depends upon the amplitude or extent of the vibrations of the particles of ether, while its colour depends upon their frequency. The time of

the vibration of a particle of ether is, by theory, as the length of a wave directly, and inversely as its velocity Now, as the velocity of light is known to be 192,000 miles in a second, if the lengths of the waves of the different coloured rays could be measured, the number of vibrations in a second corresponding to each could be computed, that has been accomplished as follows — All transparent substances of a certain thickness, with parallel surfaces, reflect and transmit white light; but if they be extremely thin, both the reflected and transmitted light is coloured. The vivid hues on soap-bubbles, the iridescent colours produced by heat on polished steel and copper, the fringes of colour between the laminæ of Iceland spar and sulphate of lime, all consist of a succession of hues disposed in the same order, totally independent of the colour of the substance, and determined solely by its greater or less thickness,—a circumstance which affords the means of ascertaining the length of the waves of each coloured ray, and the frequency of the vibrations of the particles producing them If a plate of glass be laid upon a lens of almost imperceptible curvature, before an open window, when they are pressed together a black spot will be seen in the point of contact, surrounded by seven rings of vivid colours, all differing from one another [1] In the first ring, estimated from the black spot, the colours succeed each other in the following order:— black, very faint blue, brilliant white, yellow, orange, and red They are quite different in the other rings, and in the seventh the only colours are pale bluish-green and very pale pink That these rings are formed between the two surfaces in apparent contact may be

[1] Note 102

proved by laying a prism on the lens, instead of the plate of glass, and viewing the rings through the inclined side of it that is next to the eye, which arrangement prevents the light reflected from the upper surface mixing with that from the surfaces in contact, so that the intervals between the rings appear perfectly black,—one of the strongest circumstances in favour of the undulatory theory; for, although the phenomena of the rings can be explained by either hypothesis, there is this material difference, that, according to the undulatory theory, the intervals between the rings ought to be absolutely black, which is confirmed by experiment; whereas, by the emanating doctrine, they ought to be half illuminated, which is not found to be the case. M. Fresnel, whose opinion is of the first authority, thought this test conclusive. It may therefore be concluded that the rings arise entirely from the interference of the rays: the light reflected from each of the surfaces in apparent contact reaches the eye by paths of different lengths, and produces coloured and dark rings alternately, according as the reflected waves coincide or destroy one another. The breadths of the rings are unequal; they decrease in width, and the colours become more crowded, as they recede from the centre. Coloured rings are also produced by transmitting light through the same apparatus; but the colours are less vivid, and are complementary to those reflected, consequently the central spot is white.

The size of the rings increases with the obliquity of the incident light, the same colour requiring a greater thickness or space between the glasses to produce it than when the light falls perpendicularly upon them. Now if the apparatus be placed in homogeneous instead of white light, the rings will all be of the same colour with

that of the light employed. That is to say, if the light be red, the rings will be red divided by black intervals. The size of the rings varies with the colour of the light. They are largest in red, and decrease in magnitude with the succeeding prismatic colours, being smallest in violet light.

Since one of the glasses is plane and the other spherical, it is evident that, from the point of contact, the space between them gradually increases in thickness all round, so that a certain thickness of air corresponds to each colour, which, in the undulatory system, measures the length of the wave producing it.[1] By actual measurement, Sir Isaac Newton found that the squares of the diameters of the brightest parts of each ring are as the odd numbers, 1, 3, 5, 7, &c., and that the squares of the diameters of the darkest parts are as the even numbers 0, 2, 4, 6, &c. Consequently the intervals between the glasses at these points are in the same proportion. If, then, the thickness of the air corresponding to any one colour could be found, its thickness for all the others would be known. Now, as Sir Isaac Newton knew the radius of curvature of the lens, and the actual breadth of the rings in parts of an inch, it was easy to compute that the thickness of air at the darkest part of the first ring is the $\frac{1}{89000}$th part of an inch, whence all the others have been deduced. As these intervals determine the lengths of the waves on the undulatory hypothesis, it appears that the length of a wave of the extreme red of the solar spectrum is equal to the 0·0000266th part of an inch; that the length of a wave of the extreme violet is equal to the 0·0000167th part of an inch; and as the time of a vibration of a particle

[1] Note 193.

of ether producing any particular colour is directly as the length of a wave of that colour, and inversely as the velocity of light, it follows that the molecules of ether producing the extreme red of the solar spectrum perform 458 millions of millions of vibrations in a second; and that those producing the extreme violet accomplish 727 millions of millions of vibrations in the same time. The lengths of the waves of the intermediate colours and the number of their vibrations being intermediate between these two, white light, which consists of all the colours, is consequently a mixture of waves of all lengths between the limits of the extreme red and violet. The determination of these minute portions of time and space, both of which have a real existence, being the actual results of measurement, do as much honour to the genius of Newton as that of the law of gravitation.

The phenomenon of the coloured rings takes place *in vacuo* as well as in air; which proves that it is the distance between the lenses alone, and not the air, which produces the colours. However, if water or oil be put between them, the rings contract, but no other change ensues; and Newton found that the thickness of different media at which a given tint is seen is in the inverse ratio of their refractive indices, so that the thickness of laminæ may be known by their colour, which could not otherwise be measured; and as the position of the colours in the rings is invariable, they form a fixed standard of comparison, well known as Newton's scale of colours; each tint being estimated according to the ring to which it belongs from the central spot inclusively. Not only the periodical colours which have been described, but the colours seen in thick plates of transparent substances, the variable hues of feathers, of in-

sects' wings, and of striated substances, all depend upon the same principle. To these may be added the coloured fringes, surrounding the shadows of all bodies, held in an extremely small beam of light, and the coloured rings surrounding the small beam itself when received on a screen.

When a very slender sunbeam passing through a small pin-hole into a dark room, is received on a white screen, or plate of ground glass, at the distance of a little more than six feet, the spot of light on the screen is larger than the pin-hole; and instead of being bounded by shadow, it is surrounded by a series of coloured rings separated by obscure intervals. The rings are more distinct in proportion to the smallness of the beam.[1] When the light is white, there are only three rings, which dilate or contract with the distance of the screen from the hole. As the distance of the screen diminishes, the white central spot contracts to a point and vanishes; and on approaching still nearer, the rings gradually close in upon it, so that the centre assumes successively the most intense and vivid hues. When the light is homogeneous, as red, for example, the rings are alternately red and black, and more numerous; and their breadth varies with the colour, being broadest in red light and narrowest in violet. The tints of the coloured fringes from white light, and their obliteration after the third ring arise from the superposition of the different sets of fringes of all the coloured rays. The shadows of objects are also bordered by coloured fringes when held in this slender beam of light. If the edge of a knife or a hair, for example, be held in it, the rays, instead of proceeding in straight lines past

[1] Note 194.

its edge, are bent when quite close to it, and proceed from thence to the screen in curved lines, called hyperbolas, so that the shadow of the object is enlarged, and instead of being at once bounded by light, is surrounded or edged with coloured fringes, alternating with black bands, which are more distinct the smaller the pin-hole.[1] The fringes are altogether independent of the form or density of the object, being the same when it is round or pointed, when of glass or platina. When the rays which form the fringes arrive at the screen, they are of different lengths, in consequence of the curved path they follow after passing the edge of the object. The waves are therefore in different phases or states of vibration, and either conspire to form coloured fringes or destroy one another in the obscure intervals. The coloured fringes bordering the shadows of objects were first described by Grimaldi in 1665, but besides these he noticed that there are others within the shadows of slender bodies exposed to a small sunbeam—a phenomenon which has already been mentioned to have afforded Dr Young the means of proving, beyond all controversy, that coloured rings are produced by the interference of light.

It may be concluded, that material substances derive their colours from two different causes: some from the law of interference, such as iridescent metals, peacock's feathers, &c., and others from the unequal absorption of the rays of white light, such as vermilion, ultramarine, blue or green cloth, flowers, and the greater number of coloured bodies. The latter phenomena have been considered extremely difficult to reconcile with the undulatory theory of light, and much discussion has arisen as

[1] Note 199.

to what becomes of the absorbed rays. But that embarrassing question has been ably answered by Sir John Herschel in a most profound paper, On the Absorption of Light by coloured Media, and cannot be better given than in his own words. It must, however, be premised, that as all transparent bodies are traversed by light, they are presumed to be permeable to the ether. He says, "Now, as regards only the general fact of the obstruction and ultimate extinction of light in its passage through gross media, if we compare the corpuscular and undulatory theories, we shall find that the former appeals to our ignorance, the latter to our knowledge, for its explanation of the absorptive phenomena. In attempting to explain the extinction of light, on the corpuscular doctrine, we have to account for the light so extinguished as a material body, which we must not suppose annihilated. It may, however, be transformed; and among the imponderable agents, heat, electricity, &c., it may be that we are to search for the light which has become thus comparatively stagnant. The heating power of the solar rays gives a *primâ facie* plausibility to the idea of a transformation of light into heat by absorption. But when we come to examine the matter more nearly, we find it encumbered on all sides with difficulties. How is it, for instance, that the most luminous rays are not the most calorific, but that, on the contrary, the calorific energy accompanies, in its greatest intensity, rays which possess comparatively feeble illuminating powers? These and other questions of similar nature may perhaps admit of answer in a more advanced state of our knowledge, but at present there is none obvious. It is not without reason, therefore, that the question, 'What becomes of light?' which appears to have been agitated among the photologists of

the last century, has been regarded as one of considerable importance as well as obscurity, by the corpuscular philosophers. On the other hand, the answer to this question, afforded by the undulatory theory of light, is simple and distinct. The question, 'What becomes of light?' merges in the more general one, 'What becomes of motion?' And the answer, on dynamical principles, is, that it continues for ever. No motion is, strictly speaking, annihilated; but it may be divided, and the divided parts made to oppose and, *in effect*, destroy one another. A body struck, however perfectly elastic, vibrates for a time, and then appears to sink into its original repose. But this apparent rest (even abstracting from the enquiry that part of the motion which may be conveyed away by the ambient air,) is nothing else than a state of subdivided and mutually destroying motion, in which every molecule continues to be agitated by an indefinite multitude of internally reflected waves, propagated through it in every possible direction, from every point in its surface on which they successively impinge. The superposition of such waves will, it is easily seen, at length operate their mutual destruction, which will be the more complete the more irregular the figure of the body and the greater the number of internal reflections." Thus Sir John Herschel, by referring the absorption of light to the subdivision and mutual destruction of the vibrations of ether in the interior of bodies, brings another class of phenomena under the laws of the undulatory theory.

The ethereal medium pervading space is supposed to penetrate all material substances, occupying the interstices between their molecules; but in the interior of refracting media it exists in a state of less elasticity compared with its density *in vacuo*; and the more re-

fractive the medium, the less the elasticity of the ether within it Hence the waves of light are transmitted with less velocity in such media as glass and water than in the external ether As soon as a ray of light reaches the surface of a diaphanous reflecting substance, for example, a plate of glass, it communicates its undulations to the ether next in contact with the surface, which thus becomes a new centre of motion, and two hemispherical waves are propagated from each point of this surface, one of which proceeds forward into the interior of the glass, with a less velocity than the incident wave, and the other is transmitted back into the air, with a velocity equal to that with which it came [1] Thus when refracted, the light moves with a different velocity without and within the glass, when reflected, the ray comes and goes with the same velocity. The particles of ether without the glass, which communicate their motions to the particles of the dense and less elastic ether within it, are analogous to small elastic balls striking large ones, for some of the motion will be communicated to the large balls, and the small ones will be reflected The first would cause the refracted wave, and the last, the reflected. Conversely, when the light passes from glass to air, the action is similar to large balls striking small ones The small balls receive a motion which would cause the refracted ray, and the part of the motion retained by the large ones would occasion the reflected wave, so that when light passes through a plate of glass or of any other medium differing in density from the air, there is a reflection at both surfaces, but this difference exists between the two reflections, that one is caused by a vibration in the same

[1] Note 196.

direction with that of the incident ray, and the other by a vibration in the opposite direction

A single wave of air or ether would not produce the sensation of sound or light In order to excite vision, the vibrations of the molecules of ether must be regular, periodical, and very often repeated, and as the ear continues to be agitated for a short time after the impulse, by which alone a sound becomes continuous, so also the fibres of the retina, according to M. d'Arcet, continue to vibrate for about the eighth part of a second, after the exciting cause has ceased Every one must have observed, when a strong impression is made by a bright light, that the object remains visible for a short time after shutting the eyes, which is supposed to be in consequence of the continued vibrations of the fibres of the retina. Occasionally the retina becomes insensible to feebly illuminated objects when continuously presented If the eye be turned aside for a moment the object becomes again visible It is probably on this account that the owl makes so peculiar a motion with its head when looking at objects in the twilight It is quite possible that many vibrations may be excited in the ethereal medium incapable of producing undulations in the fibres of the human retina, which yet have a powerful effect on those of other animals or of insects. Such may receive luminous impressions of which we are totally unconscious, and at the same time they may be insensible to the light and colours which affect our eyes, their perceptions beginning where ours end.

SECTION XXI.

POLARIZATION OF LIGHT — DEFINED — POLARIZATION BY REFRACTION — PROPERTIES OF THE TOURMALINE — DOUBLE REFRACTION — ALL DOUBLY REFRACTED LIGHT IS POLARIZED. — PROPERTIES OF ICELAND SPAR — TOURMALINE ABSORBS ONE OF THE TWO REFRACTED RAYS. — UNDULATIONS OF NATURAL LIGHT — UNDULATIONS OF POLARIZED LIGHT. — THE OPTIC AXES OF CRYSTALS — M. FRESNEL'S DISCOVERIES ON THE RAYS PASSING ALONG THE OPTIC AXIS — POLARIZATION BY REFLECTION.

In giving a sketch of the constitution of light, it is impossible to omit the extraordinary property of its polarization, "the phenomena of which," Sir John Herschel says, "are so singular and various, that to one who has only studied the common branches of physical optics, it is like entering into a new world, so splendid as to render it one of the most delightful branches of experimental enquiry, and so fertile in the views it lays open of the constitution of natural bodies, and the minuter mechanism of the universe, as to place it in the very first rank of the physico-mathematical sciences, which it maintains by the rigorous application of geometrical reasoning its nature admits and requires."

Light is said to be polarized, which, by being once reflected or refracted, is rendered incapable of being again reflected or refracted at certain angles. In general, when a ray of light is reflected from a pane of plate-glass, or any other substance, it may be reflected a second time from another surface, and it will also pass freely through transparent bodies. But if a ray of light be reflected from a pane of plate-glass at an angle of

57°, it is rendered totally incapable of reflection at the surface of another pane of glass in certain definite positions, but it will be completely reflected by the second pane in other positions. It likewise loses the property of penetrating transparent bodies in particular positions, whilst it is freely transmitted by them in others. Light so modified as to be incapable of reflection and transmission in certain directions, is said to be polarized This name was originally adopted from an imaginary analogy in the arrangement of the particles of light on the corpuscular doctrine to the poles of a magnet, and is still retained in the undulatory theory

Light may be polarized by reflection from any polished surface, and the same property is also imparted by refraction. It is proposed to explain these methods of polarizing light, to give a short account of its most remarkable properties, and to endeavour to describe a few of the splendid phenomena it exhibits

If a brown tourmaline, which is a mineral generally crystallized in the form of a long prism, be cut longitudinally, that is, parallel to the axis of the prism, into plates about the thirtieth of an inch in thickness, and the surfaces polished, luminous objects may be seen through them, as through plates of coloured glass The axis of each plate is, in its longitudinal section, parallel to the axes of the prism whence it was cut [1] If one of these plates be held perpendicularly between the eye and a candle, and turned slowly round in its own plane, no change will take place in the image of the candle. But if the plate be held in a fixed position, with its axis or longitudinal section vertical, when a

[1] Note 187.

second plate of tourmaline is interposed between it and the eye, parallel to the first, and turned slowly round in its own plane, a remarkable change will be found to have taken place in the nature of the light. For the image of the candle will vanish and appear alternately at every quarter revolution of the plate, varying through all degrees of brightness down to total, or almost total evanescence, and then increasing again by the same degrees as it had before decreased. These changes depend upon the relative positions of the plates. When the longitudinal sections of the two plates are parallel, the brightness of the image is at its maximum; and when the axes of the sections cross at right angles, the image of the candle vanishes. Thus the light, in passing through the first plate of tourmaline, has acquired a property totally different from the direct light of the candle. The direct light would have penetrated the second plate equally well in all directions, whereas the refracted ray will only pass through it in particular positions, and is altogether incapable of penetrating it in others. The refracted ray is polarized in its passage through the first tourmaline, and experience shows that it never loses that property, unless when acted upon by a new substance. Thus, one of the properties of polarized light is proved to be the incapability of passing through a plate of tourmaline perpendicular to it, in certain positions, and its ready transmission in other positions at right angles to the former.

Many other substances have the property of polarizing light. If a ray of light falls upon a transparent medium, which has the same temperature, density, and structure throughout every part, as fluids, gases, glass, &c., and a few regularly crystallized minerals, it is refracted into a single pencil of light by the laws of ordi-

nary refraction, according to which the ray, passing through the refracting surface from the object to the eye, never quits a plane perpendicular to that surface. Almost all other bodies, such as the greater number of crystallized minerals, animal and vegetable substances, gums, resins, jellies, and all solid bodies having unequal tensions, whether from unequal temperature or pressure, possess the property of doubling the image or appearance of an object seen through them in certain directions. Because a ray of natural light falling upon them is refracted into two pencils, which move with different velocities, and are more or less separated, according to the nature of the body and the direction of the incident ray. Whenever a ray of natural light is thus divided into two pencils, in its passage through a substance, both of the transmitted rays are polarized. Iceland spar, a carbonate of lime, which, by its natural cleavage, may be split into the form of a rhombohedron, possesses the property of double refraction in an eminent degree, as may be seen by pasting a piece of paper, with a large pin hole in it, on the side of the spar farthest from the eye. The hole will appear double when held to the light.[1] One of these pencils is refracted according to the same law, as in glass or water, never quitting the plane perpendicular to the refracting surface, and is therefore called the ordinary ray. But the other does quit that plane, being refracted according to a different and much more complicated law, and on that account is called the extraordinary ray. For the same reason one image is called the ordinary, and the other the extraordinary image. When the spar is turned round in the same plane, the extraordinary image of the hole

[1] Note 198.

revolves about the ordinary image, which remains fixed, both being equally bright. But if the spar be kept in one position, and viewed through a plate of tourmaline, it will be found that, as the tourmaline revolves, the images vary in their relative brightness—one increases in intensity till it arrives at a maximum, at the same time that the other diminishes till it vanishes, and so on alternately at each quarter revolution, proving both rays to be polarized. For in one position the tourmaline transmits the ordinary ray, and reflects the extraordinary, and after revolving 90°, the extraordinary ray is transmitted, and the ordinary ray is reflected. Thus, another property of polarized light is, that it cannot be divided into two equal pencils by double refraction, in positions of the doubly refracting bodies in which a ray of common light would be so divided.

Were tourmaline like other doubly refracting bodies, each of the transmitted rays would be double, but that mineral, when of a certain thickness, after separating the light into two polarized pencils, absorbs one of them, and consequently shows only one image of an object. On this account, tourmaline is peculiarly fitted for analyzing polarized light, which shows nothing remarkable till viewed through it or something equivalent.

The pencils of light, on leaving a double refracting substance, are parallel, and it is clear, from the preceding experiments, that they are polarized in planes at right angles to each other.[1] But that will be better understood by considering the change produced in common light by the action of the polarizing body. It has been shown that the undulations of ether, which produce the sensation of common light, are performed in

[1] Note 199

every possible plane, at right angles to the direction in which the ray is moving But the case is very different after the ray has passed through a doubly refracting substance, like Iceland spar. The light then proceeds in two parallel pencils, whose undulations are still indeed, transverse to the direction of the rays, but they are accomplished in planes at right angles to one another, analogous to two parallel stretched cords, one of which performs its undulations only in a horizontal plane, and the other in a vertical or upright plane. Thus the polarizing action of Iceland spar, and of all doubly refracting substances, is, to separate a ray of common light, whose waves or undulations are in every plane, into two parallel rays, whose waves or undulations lie in planes at right angles to each other The ray of common light may be assimilated to a round rod, whereas the two polarized rays are like two parallel long flat rulers, one of which is laid horizontally on its broad surface, and the other horizontally on its edge. The alternate transmission and obstruction of one of these flattened beams by the tourmaline is similar to the facility with which a thin sheet of paper, or a card, may be passed between the bars of a grating, or wires of a cage, if presented edgeways, and the impossibility of its passing in a direction transverse to the openings of the bars or wires

Although it generally happens that a ray of light, in passing through Iceland spar, is separated into two polarized rays, yet there is one direction along which it is refracted in one ray only, and that according to the ordinary law. This direction is called the optic axis [1] Many crystals and other substances have two optic axes,

[1] Note 200

inclined to each other, along which a ray of light is transmitted in one pencil by the law of ordinary refraction. The extraordinary ray is sometimes refracted towards the optic axis, as in quartz, zircon, ice, &c., which are, therefore, said to be positive crystals; but when it is bent from the optic axis, as in Iceland spar, tourmaline, emerald, beryl, &c., the crystals are negative, which is the most numerous class. The ordinary ray moves with uniform velocity within a doubly refracting substance, but the velocity of the extraordinary ray varies with the position of the ray relatively to the optic axis, being a maximum when its motion within the crystal is at right angles to the optic axis, and a minimum when parallel to it. Between these extremes its velocity varies according to a determinate law.

It had been inferred from the action of Iceland spar on light, that, in all doubly refracting substances, one only of the two rays is turned aside from the plane of ordinary refraction, while the other follows the ordinary law; and the great difficulty of observing the phenomena tended to confirm that opinion. M. Fresnel, however, proved, by a most profound mathematical enquiry, *à priori*, that the extraordinary ray must be wanting in glass and other uncrystallized substances, and that it must necessarily exist in carbonate of lime, quartz, and other bodies having one optic axis, but that, in the numerous class of substances which possess two optic axes, both rays must undergo extraordinary refraction, and consequently that both must deviate from their original plane; and these results have been perfectly confirmed by subsequent experiments. This theory of refraction, which, for generalisation, is perhaps only inferior to the law of gravitation, has enrolled the name of Fresnel among those which pass not away,

and make his early loss a subject of deep regret to all who take an interest in the higher paths of scientific research.

Panes of glass, if sufficiently numerous, will give a polarized beam by refraction. It appears that, when a beam of common light is partly reflected at, and partly transmitted through, a transparent surface, the reflected and refracted pencils contain equal quantities of polarized light, and that their planes of polarization are at right angles to one another; hence, a pile of panes of glass will give a polarized beam by refraction. For if a ray of common light pass through them, part of it will be polarized by the first plate, the second plate will polarize a part of what passes through it, and the rest will do the same in succession, till the whole beam is polarized, except what is lost by reflection at the different surfaces, or by absorption. This beam is polarized in a plane at right angles to the plane of reflection, that is, at right angles to the plane passing through the incident and reflected ray.[1]

By far the most convenient way of polarizing light is by reflection. A pane of plate-glass laid upon a piece of black cloth, on a table at an open window, will appear of a uniform brightness from the reflection of the sky or clouds. But if it be viewed through a plate of tourmaline, having its axis vertical, instead of being illuminated as before, it will be obscured by a large cloudy spot, having its centre quite dark, which will readily be found by elevating or depressing the eye, and will only be visible when the angle of incidence is 57°, that is, when a line from the eye to the centre of the black spot makes an angle of 33° with the surface of the reflector.[2]

[1] Note 201. [2] Note 202.

When the tourmaline is turned round in its own plane, the dark cloud will diminish, and entirely vanish when the axis of the tourmaline is horizontal, and then every part of the surface of the glass will be equally illuminated. As the tourmaline revolves, the cloudy spot will appear and vanish alternately at every quarter revolution. Thus, when a ray of light is incident on a pane of plate-glass at an angle of 57°, the reflected ray is rendered incapable of penetrating a plate of tourmaline whose axis is in the plane of incidence. Consequently it has acquired the same character as if it had been polarized by transmission through a plate of tourmaline with its axis at right angles to the plane of reflection. It is found by experience that this polarized ray is incapable of a second reflection at certain angles and in certain positions of the incident plane. For if another pane of plate glass, having one surface blackened, be so placed as to make an angle of 33° with the reflected ray, the image of the first pane will be reflected in its surface, and will be alternately illuminated and obscured at every quarter revolution of the blackened pane, according as the plane of reflection is parallel or perpendicular to the plane of polarization. Since this happens, by whatever means the light has been polarized, it evinces another general property of polarized light, which is, that it is incapable of reflection in a plane at right angles to the plane of polarization.

All reflecting surfaces are capable of polarizing light, but the angle of incidence at which it is completely polarized, is different in each substance.[1] It appears that the angle for plate-glass is 57°; in crown-glass it is 56° 55′, and no ray will be completely polarized by

[1] Note 203.

water, unless the angle of incidence be 53° 11′ The angles at which different substances polarize light are determined by a very simple and elegant law, discovered by Sir David Brewster, "That the tangent of the polarizing angle for any medium is equal to the sine of the angle of incidence divided by the sine of the angle of refraction of that medium." Whence also the refractive power even of an opaque body is known when its polarizing angle has been determined.

Metallic substances, and such as are of high refractive powers, like the diamond, polarize imperfectly.

If a ray polarized by refraction or by reflection from any substance not metallic, be viewed through a piece of Iceland spar, each image will alternately vanish and reappear at every quarter revolution of the spar, whether it revolves from right to left, or from left to right, which shows that the properties of the polarized ray are symmetrical on each side of the plane of polarization

Although there be only one angle in each substance at which light is completely polarized by one reflection, yet it may be polarized at any angle of incidence by a sufficient number of reflections For if a ray falls upon the upper surface of a pile of glass at an angle greater or less than the polarizing angle, a part only of the reflected ray will be polarized, but a part of what is transmitted will be polarized by reflection at the surface of the second plate, part at the third, and so on till the whole is polarized. This is the best apparatus, but a plate of glass having its inferior surface blackened, or even a polished table, will answer the purpose.

SECTION XXII.

PHENOMENA EXHIBITED BY THE PASSAGE OF POLARIZED LIGHT THROUGH MICA AND SULPHATE OF LIME.—THE COLOURED IMAGES PRODUCED BY POLARIZED LIGHT PASSING THROUGH CRYSTALS HAVING ONE AND TWO OPTIC AXES.—CIRCULAR POLARIZATION.—ELLIPTICAL POLARIZATION.—DISCOVERIES OF M. BIOT, FRESNEL, AND PROFESSOR AIRY.—COLOURED IMAGES PRODUCED BY THE INTERFERENCE OF POLARIZED RAYS.

SUCH is the nature of polarized light and the laws it follows. But it is hardly possible to convey an idea of the splendour of the phenomena it exhibits under circumstances which an attempt will now be made to describe.

If light polarized by reflection from a pane of glass be viewed through a plate of tourmaline, with its longitudinal section vertical, an obscure cloud, with its centre totally dark, will be seen on the glass. Now, let a plate of mica, uniformly about the thirtieth of an inch in thickness, be interposed between the tourmaline and the glass; the dark spot will instantly vanish, and instead of it a succession of the most gorgeous colours will appear, varying with every inclination of the mica, from the richest reds, to the most vivid greens, blues, and purples.[1] That they may be seen in perfection, the mica must revolve at right angles to its own plane. When the mica is turned round in a plane perpendicular to the polarized ray, it will be found that there are two lines in it where the colours entirely vanish. These are the optic axes of the mica, which is a doubly refracting

[1] Note 204.

substance, with two optic axes along which light is refracted in one pencil

No colours are visible in the mica, whatever its position may be with regard to the polarized light, without the aid of the tourmaline, which separates the transmitted ray into two pencils of coloured light complementary to one another, that is, which taken together would make white light One of these it absorbs and transmits the other, it is therefore called the analyzing plate The truth of this will appear more readily if a film of sulphate of lime between the twentieth and sixtieth of an inch thick be used instead of the mica. When the film is of uniform thickness, only one colour will be seen when it is placed between the analyzing plate and the reflecting glass, as, for example, red But when the tourmaline revolves, the red will vanish by degrees, till the film is colourless, then it will assume a green hue, which will increase and arrive at its maximum when the tourmaline has turned through ninety degrees, after that the green will vanish and the red will reappear, alternating at each quadrant Whence it appears, that the tourmaline separates the light which has passed through the film into a red and a green pencil, and that in one position it absorbs the green and lets the red pass, and in another it absorbs the red and transmits the green. This is proved by analyzing the ray with Iceland spar instead of tourmaline, for since the spar does not absorb the light, two images of the sulphate of lime will be seen, one red and the other green, and these exchange colours every quarter revolution of the spar, the red becoming green and the green red, and where the images overlap, the colour is white, proving the red and green to be complementary to each other. The tint depends on the thickness of

the film. Films of sulphate of lime, the 0·00124 and 0·01818 of an inch respectively, give white light in whatever position they may be held, provided they be perpendicular to the polarized ray; but films of intermediate thickness will give all colours. Consequently, a wedge of sulphate of lime, varying in thickness between the 0·00124 and the 0·01818 of an inch will appear to be striped with all colours when polarized light is transmitted through it. A change in the inclination of the film, whether of mica or sulphate of lime, is evidently equivalent to a variation in thickness.

When a plate of mica held as close to the eye as possible, at such an inclination as to transmit the polarized ray along one of its optic axes, is viewed through the tourmaline with its axis vertical, a most splendid appearance is presented. The cloudy spot, which is in the direction of the optic axis, is seen surrounded by a set of vividly coloured rings of an oval form, divided into two unequal parts by a black curved band passing through the cloudy spot about which the rings are formed. The other optic axis of the mica exhibits a similar image.[1]

When the two optic axes of a crystal make a small angle with one another, as in nitre, the two sets of rings touch externally; and if the plate of nitre be turned round in its own plane, the black transverse bands undergo a variety of changes, till at last the whole richly coloured image assumes the form of the figure 8 traversed by a black cross.[2] Substances having one optic axis have but one set of coloured circular rings, with a broad black cross passing through its centre and dividing the rings into four equal parts. When the analyzing plate revolves, this figure recurs at every

[1] Note 205. [2] Note 206.

quarter revolution, but in the intermediate positions, it assumes the complementary colours, the black cross becoming white.

It is in vain to attempt to describe the beautiful phenomena exhibited by innumerable bodies, all of which undergo periodic changes in form and colour when the analyzing plate revolves, but not one of them shows a trace of colour without the aid of tourmaline or something equivalent to analyze the light, and as it were to call these beautiful phantoms into existence. Tourmaline has the disadvantage of being itself a coloured substance, but that inconvenience may be avoided by employing a reflecting surface as an analyzing plate. When polarized light is reflected by a plate of glass at the polarizing angle, it will be separated into two coloured pencils, and when the analyzing plate is turned round in its own plane, it will alternately reflect each ray at every quarter revolution, so that all the phenomena that have been described will be seen by reflection on its surface.

Coloured rings are produced by analyzing polarized light transmitted through glass melted and suddenly or unequally cooled, also in thin plates of glass bent with the hand, in jelly indurated or compressed, &c. &c. In short, all the phenomena of coloured rings may be produced, either permanently or transiently, in a variety of substances, by heat and cold, rapid cooling, compression, dilatation, and induration; and so little apparatus is necessary for performing the experiments, that, as Sir John Herschel observes, a piece of window-glass or a polished table to polarize the light, a sheet of clear ice to produce the rings, and a broken fragment of plate-glass placed near the eye to analyze the light, are alone requisite to produce one of the most splendid of optical exhibitions.

It has been observed that, when a ray of light, polarized by reflection from any surface not metallic, is analyzed by a doubly refracting substance, it exhibits properties which are symmetrical both to the right and left of the plane of reflection, and the ray is then said to be polarized according to that plane. This symmetry is not destroyed when the ray, before being analyzed, traverses the optic axis of a crystal having but one optic axis, as evidently appears from the circular form of the coloured rings already described. Regularly crystallized quartz, or rock crystal, however, forms an exception. In it, even though the rays should pass through the optic axis itself, where there is no double refraction, the primitive symmetry of the ray is destroyed, and the plane of primitive polarization deviates either to the right or left of the observer, by an angle proportional to the thickness of the plate of quartz. This angular motion, or true rotation of the plane of polarization, which is called circular polarization, is clearly proved by the phenomena. The coloured rings produced by all crystals having but one optic axis are circular, and traversed by a black cross concentric with the rings, so that the light entirely vanishes throughout the space enclosed by the interior ring, because there is neither double refraction nor polarization along the optic axis. But in the system of rings produced by a plate of quartz, whose surfaces are perpendicular to the axis of the crystal, the part within the interior ring, instead of being void of light, is occupied by a uniform tint of red, green, or blue, according to the thickness of the plate.[1] Suppose the plate of quartz to be $\frac{1}{25}$ of an inch thick, which will give the red tint to the space within the interior ring, when the analyzing plate is turned in

[1] Note 207.

its own plane through an angle of $17\frac{1}{2}°$, the red hue vanishes If a plate of rock crystal, $\frac{2}{25}$ of an inch thick, be used, the analyzing plate must revolve through 35° before the red tint vanishes, and so on, every additional 25th of an inch in thickness requiring an additional rotation of $17\frac{1}{2}°$, whence it is manifest that the plane of polarization revolves in the direction of a spiral within the rock crystal It is remarkable that, in some crystals of quartz, the plane of polarization revolves from right to left, and in others from left to right, although the crystals themselves differ apparently only by a very slight, almost imperceptible, variety in form In these phenomena, the rotation to the right is accomplished according to the same laws, and with the same energy, as that to the left. But if two plates of quartz be interposed which possess different affections, the second plate undoes, either wholly or partly, the rotatory motion which the first had produced, according as the plates are of equal or unequal thickness When the plates are of unequal thickness, the deviation is in the direction of the strongest, and exactly the same with that which a third plate would produce equal in thickness to the difference of the two.

M Biot has discovered the same properties in a variety of liquids. Oil of turpentine and an essential oil of laurel cause the plane of polarization to turn to the left, whereas the syrup of the sugar-cane and a solution of natural camphor by alcohol turn it to the right A compensation is effected by the superposition or mixture of two liquids which possess these opposite properties, provided no chemical action takes place. A remarkable difference was also observed by M. Biot between the action of the particles of the same substances when in a liquid or solid state. The syrup of

grapes, for example, turns the plane of polarization to the left as long as it remains liquid, but as soon as it acquires the solid form of sugar, it causes the plane of polarization to revolve towards the right, a property which it retains even when again dissolved. Instances occur also in which these circumstances are reversed.

A ray of light passing through a liquid possessing the power of circular polarization is not affected by mixing other fluids with the liquid—such as water, ether, alcohol, &c.—which do not possess circular polarization themselves, the angle of deviation remaining exactly the same as before the mixture. Whence M. Biot infers that the action exercised by the liquids in question does not depend upon their mass, but that it is a molecular action exercised by the ultimate particles of matter, which only depends upon their individual constitution, and is entirely independent of the positions and mutual distances of the particles with regard to each other. This peculiar action of matter on light affords the means of detecting varieties in the nature of substances which have eluded chemical research. For example, no chemical difference has been discovered between syrup from the sugar-cane and syrup from grapes. Yet the first causes the plane of polarization to revolve to the right, and the other to the left; therefore some essential difference must exist in the nature of their ultimate molecules. The same difference is to be traced between the juices of such plants as give sugar similar to that from the cane and those which give sugar like that obtained from grapes. M. Biot has shown, by these important discoveries, that circular polarization surpasses the power of chemical analysis in giving certain and direct evidence of the similarity or difference existing in the molecular constitution of bodies, as well as of the permanency of

that constitution, or of the fluctuations to which it may be liable This eminent philosopher is now engaged in a series of experiments on the progressive changes in the sap of vegetables at different distances from their roots, and on the products that are formed at the various epochs of vegetation, from their action on polarized light

One of the many brilliant discoveries of M Fresnel is the production of circular and elliptical polarization by the internal reflection of light from plate-glass He has shown that, if light, polarized by any of the usual methods, be twice reflected within a glass rhomb[1] of a given form, the vibrations of the ether that are perpendicular to the plane of incidence will be retarded a quarter of a vibration, which causes the vibrating particles to describe a circular helix, or curve, like a cork-screw. However, that only happens when the plane of polarization is inclined at an angle of 45° to the plane of incidence. When these two planes form an angle, either greater or less, the vibrating particles move in an elliptical helix, which curve may be represented by twisting a thread in a spiral about an oval rod. These curves will turn to the right or left, according to the position of the incident plane

The motion of the ethereal medium in elliptical and circular polarization may be represented by the analogy of a stretched cord, for if the extremity of such a cord be agitated at equal and regular intervals by a vibratory motion entirely confined to one plane, the cord will be thrown into an undulating curve lying wholly in that plane. If to this motion there be superadded another, similar and equal, but perpendicular to the first, the cord will assume the form of an elliptical helix, its

[1] Note 164

extremity will describe an ellipse, and every molecule throughout its length will successively do the same. But if the second system of vibrations commence exactly a quarter of an undulation later than the first, the cord will take the form of a circular helix, or corkscrew; the extremity of it will move uniformly in a circle, and every molecule throughout the cord will do the same in succession It appears, therefore, that both circular and elliptical polarization may be produced by the composition of the motions of two rays in which the particles of ether vibrate in planes at right angles to one another

Professor Airy, in a very profound and able paper published in the Cambridge Transactions, has proved that all the different kinds of polarized light are obtained from rock crystal When polarized light is transmitted through the axis of a crystal of quartz, in the emergent ray, the particles of ether move in a circular helix, and when it is transmitted obliquely, so as to form an angle with the axis of the prism, the particles of ether move in an elliptical helix, the ellipticity increasing with the obliquity of the incident ray, so that, when the incident ray falls perpendicularly to the axis, the particles of ether move in a straight line. Thus quartz exhibits every variety of elliptical polarization, even including the extreme cases where the excentricity is zero, or equal to the greater axis of the ellipse.[1] In many crystals the two rays are so little separated, that it is only from the nature of the transmitted light that they are known to have the property of double refraction. M Fresnel discovered, by experiments on the properties of light passing through the axis of quartz, that it consists of two superposed rays moving with dif-

[1] Note 206.

ferent velocities, and Professor Airy has proved that, in these two rays, the molecules of ether vibrate in similar ellipses at right angles to each other, but in different directions; that their ellipticity varies with the angle which the incident ray makes with the axis; and that, by the composition of their motions, they produce all the phenomena of polarized light observed in quartz.

It appears from what has been said, that the molecules of ether always perform their vibrations at right angles to the direction of the ray, but very differently in the various kinds of light. In natural light the vibrations are rectilinear, and in every plane. In ordinary polarized light they are rectilinear, but confined to one plane; in circular polarization the vibrations are circular; and in elliptical polarization the molecules vibrate in ellipses. These vibrations are communicated from molecule to molecule, in straight lines when they are rectilinear, in a circular helix when they are circular, and in an oval or elliptical helix when elliptical.

Some fluids possess the property of circular polarization, as oil of turpentine, and elliptical polarization, or something similar, seems to be produced by reflection from metallic surfaces.

The coloured images from polarized light arise from the interference of the rays.[1] MM. Fresnel and Arago proved, by experiment, that two rays of polarized light interfere and produce coloured fringes if they be polarized in the same plane, but that they do not interfere when polarized in different planes. In all intermediate positions, fringes of intermediate brightness are produced. The analogy of a stretched cord will show how this happens. Suppose the cord to be moved backwards and forwards horizontally at equal intervals, it will be

[1] Note 209.

thrown into an undulating curve lying all in one plane If to this motion there be superadded another, similar and equal, commencing exactly half an undulation later than the first, it is evident that the direct motion every molecule will assume, in consequence of the first system of waves, will, at every instant, be exactly neutralized by the retrograde motion it would take in virtue of the second, and the cord itself will be quiescent in consequence of the interference But if the second system of waves be in a plane perpendicular to the first, the effect would only be to twist the rope, so that no interference would take place Rays polarized at right angles to each other may subsequently be brought into the same plane without acquiring the property of producing coloured fringes, but if they belong to a pencil the whole of which was originally polarized in the same plane, they will interfere

The manner in which the coloured images are formed, may be conceived by considering that, when polarized light passes through the optic axis of a doubly refracting substance,—as mica for example,—it is divided into two pencils by the analyzing tourmaline; and as one ray is absorbed, there can be no interference But when the polarized light passes through the mica in any other direction, it is separated into two white rays, and these are again divided into four pencils by the tourmaline, which absorbs two of them; and the other two, being transmitted in the same plane, with different velocities, interfere and produce the coloured phenomena. If the analysis be made with Iceland spar, the single ray passing through the optic axis of the mica will be refracted into two rays polarized in different planes, and no interference will happen. But when two rays are transmitted by the mica, they will be separated

into four by the spar, two of which will interfere to form one image, and the other two, by their interference, will produce the complementary colours of the other image, when the spar has revolved through 90°; because, in such positions of the spar as produce the coloured images, only two rays are visible at a time, the other two being reflected. When the analysis is accomplished by reflection, if two rays are transmitted by the mica, they are polarized in planes at right angles to each other. And if the plane of reflection of either of these rays be at right angles to the plane of polarization, only one of them will be reflected, and therefore no interference can take place; but in all other positions of the analyzing plate both rays will be reflected in the same plane, and, consequently, will produce coloured rings by their interference.

It is evident that a great deal of the light we see must be polarized, since most bodies which have the power of reflecting or refracting light also have the power of polarizing it. The blue light of the sky is completely polarized at an angle of 74° from the sun in a plane passing through his centre.

A constellation of talent, almost unrivalled at any period in the history of science, has contributed to the theory of polarization, though the original discovery of that property of light was accidental, and arose from an occurrence which, like thousands of others, would have passed unnoticed, had it not happened to one of those rare minds capable of drawing the most important inferences from circumstances apparently trifling. In 1808, while M. Malus was accidentally viewing, with a doubly-refracting prism, a brilliant sunset reflected from the windows of the Luxembourg palace in Paris, on turning the prism slowly round, he was surprised to

see a very great difference in the intensity of the two images, the most refracted alternately changing from brightness to obscurity at each quadrant of revolution. A phenomenon so unlooked for induced him to investigate its cause, whence sprung one of the most elegant and refined branches of physical optics.

SECTION XXIII

OBJECTIONS TO THE UNDULATORY THEORY, FROM A DIFFERENCE IN THE ACTION OF SOUND AND LIGHT UNDER THE SAME CIRCUMSTANCES, REMOVED.—A DIFFICULTY IN THE DISPERSION OF LIGHT REMOVED BY PROFESSOR AIRY

THE numerous phenomena of periodical colours arising from the interference of light, which do not admit of satisfactory explanation on any other principle than the undulatory theory, are the strongest arguments in favour of that hypothesis, and even cases which at one time, seemed unfavourable to that doctrine, have proved upon investigation, to proceed from it alone. Such is the erroneous objection which has been made, in consequence of a difference in the mode of action of light and sound, under the same circumstances, in one particular instance. When a ray of light from a luminous point, and a diverging sound, are both transmitted through a very small hole into a dark room, the light goes straight forward, and illuminates a small spot on the opposite wall, leaving the rest in darkness; whereas the sound, on entering, diverges in all directions, and is heard in every part of the room. These phenomena, however, instead of being at variance with the undulatory theory, are direct consequences of it, arising from the very great difference between the magnitude of the undulations of sound and those of light. The undulations of light are incomparably less than the minute aperture, while those of sound are much greater. Therefore, when light diverging from a luminous point

enters the hole, the rays round its edges are oblique, and consequently of different lengths, while those in the centre are direct, and nearly or altogether of the same lengths. So that the small undulations between the centre and the edges are in different phases, that is, in different states of undulation. Therefore the greater number of them interfere, and, by destroying one another, produce darkness all around the edges of the aperture, whereas the central rays, having the same phases, combine and produce a spot of bright light on a wall or screen directly opposite the hole. The waves of air producing sound, on the contrary, being very large compared with the hole, do not sensibly diverge in passing through it, and are therefore all so nearly of the same length, and consequently in the same phase, or state of undulation, that none of them interfere sufficiently to destroy one another. Hence all the particles of air in the room are set into a state of vibration, so that the intensity of the sound is very nearly every where the same. It is probable, however, that if the aperture were large enough, sound diverging from a point without would scarcely be audible, except immediately opposite the opening. Strong as the preceding cases may be, the following experiment, recently published by Professor Airy, seems to be decisive in favour of the undulatory doctrine. Suppose a plano convex lens of very great radius to be placed upon a plate of very highly polished metal. When a ray of polarized light falls upon this apparatus at a very great angle of incidence, Newton's rings are seen at the point of contact. But, as the polarizing angle of glass differs from that of metal, when the light falls on the lens at the polarizing angle of glass, the black spot and the system of rings vanish. For although light in abundance continues to

be reflected from the surface of the metal, not a ray is reflected from the surface of the glass that is in contact with it, consequently no interference can take place; which proves, beyond a doubt, that Newton's rings result from the interference of the light reflected from the surfaces apparently in contact.[1]

Notwithstanding the successful adaptation of the undulatory system to phenomena, it cannot be denied that an objection still exists in the dispersion of light, unless the explanation given by Professor Airy be deemed sufficient. A sunbeam falling on a prism, instead of being refracted to a single point, is dispersed, or scattered over a considerable space, so that the rays of the coloured spectrum, whose waves are of different lengths, have different degrees of refrangibility, and consequently move with different velocities, either in the medium which conveys the light from the sun, or in the refracting medium, or in both; whereas it has been shown that rays of all colours move with the same velocity. If, indeed, the velocities of the various rays were different in space, the aberration of the fixed stars, which is inversely as the velocity, would be different for different colours, and every star would appear as a spectrum whose length would be parallel to the direction of the earth's motion, which is not found to agree with observation. Besides, there is no such difference in the velocities of the long and short waves of air in the analogous case of sound, since notes of the lowest and highest pitch are heard in the order in which they are struck. The solution of this anomalous case suggested by Professor Airy, from a similar instance in the theory of sound, already mentioned, will be best understood in his own words. "We have every reason," he observes, "to think that a part of the

[1] Note 102.

velocity of sound depends upon the circumstance that the law of elasticity of the air is altered by the instantaneous developement of latent heat on compression, or the contrary effect on expansion. Now, if this heat required time for its developement, the quantity of heat developed would depend upon the time during which the particles remained in nearly the same relative state, that is, on the time of vibration. Consequently, the law of elasticity would be different for different times of vibration, or for different lengths of waves; and therefore the velocity of transmission would be different for waves of different lengths. If we suppose some cause which is put in action by the vibration of the particles to affect, in a similar manner, the elasticity of the medium of light, and if we conceive the degree of developement of that cause to depend upon time, we shall have a sufficient explanation of the unequal refrangibility of different coloured rays." Even should this view be objectionable, instead of being surprised that one discrepant case should occur, it is astonishing to find the theory so nearly complete, if it be considered that no subject in the whole course of physico-mathematical enquiry is more abstruse than the doctrine of the propagation of motion through elastic media, perpetually requiring the aid of analogy, from the unconquerable difficulties of the subject.

SECTION XXIV

HEAT.—CALORIFIC RAYS OF THE SOLAR SPECTRUM.—CHEMICAL RAYS OF THE SOLAR SPECTRUM.—EXPERIMENTS OF MM. DE LAROCHE AND MELLONI ON THE TRANSMISSION OF HEAT.—THE POINT OF GREATEST HEAT IN THE SOLAR SPECTRUM VARIES WITH THE SUBSTANCE OF THE PRISM.—ABSORPTION OF HEAT.—RADIATION OF HEAT.—DEW.—HOAR FROST.—RAIN.—HAIL.—COMBUSTION.—DILATATION OF BODIES BY HEAT.—PROPAGATION OF HEAT.—LATENT HEAT.—HEAT PRESUMED TO CONSIST OF THE UNDULATIONS OF AN ELASTIC MEDIUM.

It is not by vision alone that a knowledge of the sun's rays is acquired,—touch proves that they have the power of raising the temperature of substances exposed to their action, and experience likewise teaches that remarkable changes are effected by their chemical agency. Sir William Herschel discovered that rays of caloric, which produce the sensation of heat, exist independently of those of light, when he used a prism of flint glass, he found the warm rays most abundant in the dark space a little beyond the red extremity of the solar spectrum, from whence they decrease towards the violet, beyond which they are insensible. It may, therefore, be concluded, that the calorific rays vary in refrangibility, and that those beyond the extreme red are less refrangible than any rays of light. Dr Wollaston, and MM. Ritter and Beckman, discovered simultaneously that invisible rays, known only by their chemical action, exist in the dark space beyond the extreme violet, where there is no sensible heat. These are more refrangible than any of the rays of light or heat, and gradually decrease in refrangibility towards the other end

of the spectrum, where they cease. Thus, the solar spectrum is proved to consist of five superposed spectra, only three of which are visible—the red, yellow, and blue; each of the five varies in refrangibility and intensity throughout the whole extent, the visible part being overlapped at one extremity by the chemical, and at the other by the calorific rays. The action of the chemical rays blackens the salts of silver, and their influence is daily seen in the fading of vegetable colours. What object they are destined to accomplish in the economy of nature remains unknown; but certain it is, that the very existence of the animal and vegetable creation depends upon the calorific rays. That the heat-producing rays exist independently of light is a matter of constant experience in the abundant emission of them from boiling water. Yet there is every reason to believe that both the calorific and chemical rays are modifications of the same agent which produces the sensation of light. The rays of heat are subject to the same laws of reflection and refraction with those of light. They pass through the gases with the same facility, but a remarkable difference obtains in the transmission of light and heat through most solid and liquid substances, the same body being often perfectly transparent to the luminous, and altogether impermeable to the calorific rays. The experiments of M. de Laroche show that glass, however thin, totally intercepts the obscure rays of caloric when they flow from a body whose temperature is lower than that of boiling water; that, as the temperature increases, the calorific rays are transmitted more and more abundantly; and when the body becomes highly luminous, that they penetrate the glass with perfect ease. The very feeble heat of moonlight must be incapable of penetrating glass, consequently it

does not sensibly affect the thermometer, even when concentrated On the contrary, the extreme brilliancy of the sun is probably the reason why his heat, when brought to a focus by a lens, is more intense than any that can be produced artificially. It is owing to the same cause that glass screens, which entirely exclude the heat of a common fire, are permeable by the solar caloric.

The results of M De Laroche have been confirmed by the recent experiments of M Melloni, whence it appears that the calorific rays pass less abundantly, not only through glass, but through rock-crystal, Iceland spar, and other diaphanous bodies, both solid and liquid, according as the temperature of their origin is diminished, and that they are altogether intercepted when the temperature is about that of boiling water It is singular that transparency with regard to light is totally different from the power of transmitting heat In bodies possessing the same degree of transparency for light, the quantities of heat which they transmit differ immensely, though proceeding from the same source The transmissive power of certain substances having a dark colour, exceeds by four or five times that of others perfectly diaphanous, and the calorific rays pass instantaneously through black glass perfectly opaque to light.

The property of transmitting the calorific rays diminishes, to a certain degree, with the thickness of the body they have to traverse, but not so much as might be expected. A piece of very transparent alum transmitted three or four times less radiant heat from the flame of a lamp than a piece of nearly opaque quartz about a hundred times as thick. However, the influence of thickness upon the phenomena of transmission increases with the decrease of temperature in the

origin of the rays, and becomes very great when that temperature is low. This is a circumstance intimately connected with the law established by M. De Laroche, for M. Melloni observed that the differences between the quantities of caloric transmitted by the same plate of glass, exposed successively to several sources of heat, diminished with the thinness of the plate, and vanished altogether at a certain limit, and that a film of mica transmitted the same quantity of caloric whether it was exposed to incandescent platina or to a mass of iron heated to 360°. Every time that heat is transmitted through a substance, less of it is absorbed. For example, a certain quantity of heat is absorbed in passing through a thin film of glass; less of the same is absorbed in traversing a second; and still less, the third. Wherefore heat, which has passed through one stratum of air, experiences a less absorption in each of the following strata, and may therefore be propagated to a greater distance before it is extinguished.

Since the power of penetrating glass increases in proportion as the radiating caloric approaches the state of light, it seemed to indicate that the same principle takes the form of light or heat according to the modification it receives, and that the hot rays are only invisible light, and light, luminous caloric. It was natural to infer that, in the gradual approach of invisible caloric to the condition and properties of luminous caloric, the invisible rays must at first be analogous to the least calorific part of the spectrum, which is at the violet extremity, —an analogy which appeared to be greater, by all flame being at first violet or blue, and only becoming white when it has attained its greatest intensity. Thus, as diaphanous bodies transmit light with the same facility whether proceeding from the sun or from a glow-worm,

and that no substance had hitherto been found which instantaneously transmits radiant caloric coming from a source of low temperature, it was concluded that no such substance exists, and the great difference between the transmission of light and radiant heat was thus referred to the nature of the agent of heat, and not to the action of matter upon the calorific rays. M. Melloni has, however, discovered in rock-salt a substance which transmits radiant heat with the same facility whether it originates in the brightest flame or lukewarm water, and which consequently possesses the same permeability with regard to heat that all diaphanous bodies have for light. It follows, therefore, that the impermeability of glass and other substances for heat arises from their action upon the calorific rays, and not from the principle of heat. But, although this discovery changes the received ideas drawn from M. De Laroche's experiments, it establishes a new and unlooked-for analogy between these two great agents of nature. The probability of light and heat being modifications of the same principle is not diminished by the calorific rays being unseen, for the condition of visibility or invisibility may only depend upon the construction of our eyes, and not upon the nature of the agent which produces these sensations in us. The sense of seeing may be confined within certain limits. The chemical rays beyond the violet end of the spectrum may be too rapid, or not sufficiently excursive in their vibrations to be visible to the human eye; and the calorific rays beyond the other end of the spectrum, may not be sufficiently rapid, or too extensive, in their undulations to affect our optic nerves, though both may be visible to certain animals or insects. We are altogether ignorant of the perceptions which direct the carrier-pigeon to his home, and

the vulture to his prey, before he himself is visible even as a speck in the heavens; or of those in the antennæ of insects which warn them of the approach of danger. So likewise beings may exist on earth, in the air, or in the waters, which hear sounds our ears are incapable of hearing, and which see rays of light and heat of which we are unconscious. Our perceptions and faculties are limited to a very small portion of that immense chain of existence which extends from the Creator to evanescence. The identity of action under similar circumstances is one of the strongest arguments in favour of the common nature of the chemical, visible, and calorific rays. They are all capable of reflection from polished surfaces, of refraction through diaphanous substances, of polarisation by reflection and by doubly refracting crystals; none of these rays add sensibly to the weight of matter; their velocity is prodigious; they may be concentrated and dispersed by convex and concave mirrors; light and heat pass with equal facility through rock-salt, and both are capable of radiation; the chemical rays are subject to the same law of interference with those of light; and although the interference of the calorific rays has not yet been proved, there is no reason to suppose that they differ from the others in this instance. As the action of matter in so many cases is the same on the whole assemblage of rays, visible and invisible, which constitute a solar beam, it is more than probable that the obscure, as well as the luminous part, is propagated by the undulations of an imponderable ether, and consequently comes under the same laws of analysis.

Coloured glasses transmit rays of certain degrees of refrangibility, and absorb those of other degrees. For example, red glass absorbs the more refrangible rays,

and transmits the red, which are the least refrangible. On the contrary, violet glass absorbs the least refrangible, and transmits the violet, which are the most refrangible. Now M. Melloni has found, that although the colouring matter of glass diminishes its power of transmitting heat, yet red, orange, yellow, blue, violet, and white glass, transmit calorific rays of all degrees of refrangibility. Whereas green glass possesses the peculiar property of transmitting the least refrangible calorific rays, and stopping those that are most refrangible. It has, therefore, the same elective action for heat that coloured glass has for light, and its action on heat is analogous to that of red glass on light. Alum, and sulphate of lime, are exactly opposed to green glass in their action on heat, by transmitting the most refrangible rays with the greatest facility.

Liquids, the various kinds of glass, and probably all substances, whether solid or liquid, that do not crystallise regularly, are more pervious to the calorific rays according as they possess a greater refracting power. For example, the chloride of sulphur, which has a high refracting power, transmits more of the calorific rays than the oils which have a less refracting power; oils transmit more radiant heat than the acids, the acids more than aqueous solutions; and the latter more than pure water, which, of all the series, has the least refracting power, and is the least pervious to heat. M. Melloni observed, also, that each ray of the solar spectrum follows the same law of action with that of terrestrial rays having their origin in sources of different temperatures, so that the very refrangible rays may be compared to the heat emanating from a focus of high temperature, and the least refrangible to the heat which comes from

a source of low temperature. Thus, if the calorific rays emerging from a prism be made to pass through a layer of water contained between two plates of glass, it will be found that these rays suffer a loss in passing through the liquid, as much greater as their refrangibility is less. The rays of heat that are mixed with the blue or violet light pass in great abundance, while those in the obscure part which follows the red light are almost totally intercepted. The first, therefore, act like the heat of a lamp, and the last like that of boiling water.

These circumstances explain the phenomena observed by several philosophers with regard to the point of greatest heat in the solar spectrum, which varies with the substance of the prism. Sir William Herschel, who employed a prism of flint glass, found that point to be a little beyond the red extremity of the spectrum; but, according to M. Seebeck, it is found to be upon the yellow, upon the orange, on the red, or at the dark limit of the red, according as the prism consists of water, sulphuric acid, crown or flint glass. If it be recollected that, in the spectrum from crown glass, the maximum heat is in the red part, and that the solar rays, in traversing a mass of water, suffer losses inversely as their refrangibility, it will be easy to understand the reason of the phenomenon in question. The solar heat which comes to the anterior face of the prism of water consists of rays of all degrees of refrangibility. Now, the rays possessing the same index of refraction with the red light suffer a greater loss in passing through the prism, than the rays possessing the refrangibility of the orange light, and the latter lose less in their passage than the heat of the yellow. Thus, the losses, being inversely proportional to the degree of refrangibility of each ray, cause

the point of maximum heat to tend from the red towards the violet, and therefore it rests upon the yellow part. The prism of sulphuric acid, acting similarly, but with less energy than that of water, throws the point of greatest heat on the orange, for the same reason, the crown and flint glass prisms transfer that point respectively to the red and to its limit. M. Melloni, observing that the maximum point of heat is transferred farther and farther towards the red end of the spectrum, according as the substance of the prism is more and more permeable to heat, inferred that a prism of rock-salt, which possesses a greater power of transmitting the calorific rays than any known body, ought to throw the point of greatest heat to a considerable distance beyond the visible part of the spectrum,—an anticipation which experiment fully confirmed, by placing it as much beyond the dark limit of the red rays, as the red part is distant from the bluish green band of the spectrum.

When radiant heat falls upon a surface, part of it is reflected and part of it is absorbed, consequently the best reflectors possess the least absorbing powers. The absorption of the sun's rays is the cause both of the colour and temperature of solid bodies. A black substance absorbs all the rays of light, and reflects none, and since it absorbs at the same time all the calorific rays, it becomes sooner warm, and rises to a higher temperature, than bodies of any other colour. Blue bodies come next to black in their power of absorption. Of all the colours of the solar spectrum, the blue possesses least of the heating power, and since substances of a blue tint absorb all the other colours of the spectrum, they absorb by far the greatest part of the calorific rays, and reflect the blue where they are least abundant. Next in order come the green, yellow, red,

and, last of all, white bodies, which reflect nearly all the rays both of light and heat. The temperature of very transparent fluids is not raised by the passage of the sun's rays, because they do not absorb any of them, and as his heat is very intense, transparent solids arrest a very small portion of it

Rays of heat proceed in diverging straight lines from each point in the surfaces of hot bodies, in the same manner as diverging rays of light dart from every point of the surfaces of those that are luminous. Heated substances, when exposed to the open air, continue to radiate caloric till they become nearly of the temperature of the surrounding medium. The radiation is very rapid at first, but diminishes according to a known law, with the temperature of a heated body It appears, also, that the radiating power of a surface is inversely as its reflecting power, and bodies that are most impermeable to heat radiate least According to the experiments of Sir John Leslie, radiation proceeds not only from the surfaces of substances, but also from the particles at a minute depth below it He found that the emission is most abundant in a direction perpendicular to the radiating surface, and is more rapid from a rough than from a polished surface radiation, however, can only take place in air and in vacuo, it is altogether imperceptible when the hot body is enclosed in a solid or liquid All substances may be considered to radiate caloric, whatever their temperature may be, though with different intensities, according to their nature, the state of their surfaces, and the temperature of the medium into which they are brought. But every surface absorbs, as well as radiates, caloric; and the power of absorption is always equal to that of radiation, for, under the same circumstances,

matter which becomes soon warm also cools rapidly There is a constant tendency to an equal diffusion of caloric, since every body in nature is giving and receiving it at the same instant, each will be of uniform temperature when the quantities of caloric given and received during the same time are equal, that is, when a perfect compensation takes place between each and all the rest. Our sensations only measure comparative degrees of heat when a body, such as ice, appears to be cold, it imparts fewer calorific rays than it receives, and when a substance seems to be warm,—for example, a fire,—it gives more caloric than it takes The phenomena of dew and hoar-frost are owing to this inequality of exchange, the caloric radiated during the night by substances on the surface of the earth into a clear expanse of sky is lost, and no return is made from the blue vault, so that their temperature sinks below that of the air, whence they abstract a part of that caloric which holds the atmospheric humidity in solution, and a deposition of dew takes place If the radiation be great, the dew is frozen, and becomes hoar-frost, which is the ice of dew. Cloudy weather is unfavourable to the formation of dew, by preventing the free radiation of caloric, and actual contact is requisite for its deposition, since it is never suspended in the air, like fog Plants derive a great part of their nourishment from this source; and as each possesses a power of radiation peculiar to itself, they are capable of procuring a sufficient supply for their wants.

Rain is formed by the mixing of two masses of air of different temperatures, the colder part, by abstracting from the other the heat which holds it in solution, occasions the particles to approach each other and form drops of water, which, becoming too heavy to be

sustained by the atmosphere, sink to the earth by gravitation in the form of rain. The contact of two strata of air of different temperatures, moving rapidly in opposite directions, occasions an abundant precipitation of rain. When the masses of air differ very much in temperature, and meet suddenly, hail is formed. This happens frequently in hot plains near a ridge of mountains, as in the South of France; but no explanation has hitherto been given of the cause of the severe hail-storms which occasionally take place on extensive plains within the tropics.

An accumulation of caloric invariably produces light: with the exception of the gases, all bodies which can endure the requisite degree of heat without decomposition, begin to emit light at the same temperature; but when the quantity of caloric is so great as to render the affinity of their component particles less than their affinity for the oxygen of the atmosphere, a chemical combination takes place with the oxygen, light and heat are evolved, and fire is produced. Combustion — so essential for our comfort, and even existence — takes place very easily, from the small affinity between the component parts of atmospheric air, the oxygen being nearly in a free state; but as the cohesive force of the particles of different substances is very variable, different degrees of heat are requisite to produce their combustion. The tendency of heat to a state of equal diffusion or equilibrium, either by radiation or contact, makes it necessary that the chemical combination which occasions combustion should take place instantaneously; for if the heat were developed progressively, it would be dissipated by degrees, and would never accumulate sufficiently to produce a temperature high enough for the evolution of flame.

It is a general law that all bodies expand by heat and contract by cold. The expansive force of caloric has a constant tendency to overcome the attraction of cohesion, and to separate the constituent particles of solids and fluids; by this separation the attraction of aggregation is more and more weakened, till at last it is entirely overcome, or even changed into repulsion. By the continual addition of caloric, solids may be made to pass into liquids, and from liquids to the aeriform state, the dilatation increasing with the temperature; and every substance expands according to a law of its own. Gases expand more than liquids, and liquids more than solids. The expansion of air is more than eight times that of water, and the increase in the bulk of water is at least forty-five times greater than that of iron. Metals dilate uniformly from the freezing to the boiling points of the thermometer; the uniform expansion of the gases extends between still wider limits; but as liquidity is a state of transition from the solid to the aeriform condition, the equable dilatation of liquids has not so extensive a range. This change of bulk, corresponding to the variation of heat, is one of the most important of its effects, since it furnishes the means of measuring relative temperature by the thermometer and pyrometer. The rate of expansion of solids varies at their transition to liquidity, and that of liquids is no longer equable near their change to an aeriform state. There are exceptions, however, to the general laws of expansion; some liquids have a maximum density corresponding to a certain temperature, and dilate whether that temperature be increased or diminished. For example—water expands whether it be heated above or cooled below 40°. The solidification of some liquids, and especially their crystallisation,

is always accompanied by an increase of bulk. Water dilates rapidly when converted into ice, and with a force sufficient to split the hardest substances The formation of ice is, therefore, a powerful agent in the disintegration and decomposition of rocks, operating as one of the most efficient causes of local changes in the structure of the crust of the earth, of which we have experience in the tremendous *éboulemens* of mountains in Switzerland

The dilatation of substances by heat, and their contraction by cold, occasion such irregularities in the rate of clocks and watches, as would render them unfit for astronomical or nautical purposes, were it not for a very beautiful application of the laws of unequal expansion. The oscillations of a pendulum are the same as if its whole mass were united in one dense particle, in a certain point of its length, called the centre of oscillation. If the distance of this point from the point by which the pendulum is suspended, were invariable, the rate of the clock would be invariable also The difficulty is to neutralise the effects of temperature, which is perpetually increasing or diminishing its length. Among many contrivances, Graham's compensation pendulum is the most simple. He employed a glass tube containing mercury. When the tube expands from the effects of heat, the mercury expands much more, so that its surface rises a little more than the end of the pendulum is depressed, and the centre of oscillation remains stationary Harrison invented a pendulum which consists of seven bars of steel and of brass, joined in the shape of a gridiron, in such a manner that the bars of brass raise the weight at the end of the pendulum as much as the bars of steel depress it. In general, only five bars are used, three being of

steel, and two a mixture of silver and zinc The effects of temperature are neutralised in chronometers upon the same principle, and to such perfection are they brought, that the loss or gain of one second in twenty-four hours, for two days running, would render one unfit for use Accuracy in surveying depends upon the compensation rods employed in measuring bases. Thus, the laws of the unequal expansion of matter judiciously applied, have an immediate influence upon our estimation of time, upon the motions of bodies in the heavens, and of their fall upon the earth, on the figure of the globe, and our system of weights and measures, on our commerce abroad, and the mensuration of our lands at home.

The expansion of crystalline substances takes place under very different circumstances from the dilatation of such as are not crystallised The latter become both longer and thicker by an accession of heat, whereas M Mitscherlich has found that the former expand differently in different directions, and, in a particular instance, extension in one direction is accompanied by contraction in another The internal structure of crystallised matter must be very peculiar, thus to modify the expansive power of heat, and so materially to influence the transmission of caloric and the visible rays of the spectrum.

Heat is propagated with more or less rapidity through all bodies; air is the worst conductor, and consequently mitigates the severity of cold climates by preserving the heat imparted to the earth by the sun On the contrary, dense bodies, especially metals, possess the power of conduction in the greatest degree, but the transmission requires time If a bar of iron, twenty inches long, be heated at one extremity, the caloric

takes four minutes in passing to the other. The particle of the metal that is first heated communicates its caloric to the second, and the second to the third; so that the temperature of the intermediate molecule, at any instant, is increased by the excess of the temperature of the first above its own, and diminished by the excess of its own temperature above that of the third. That, however, will not be the temperature indicated by the thermometer, because, as soon as the particle is more heated than the surrounding atmosphere, it will lose its caloric by radiation, in proportion to the excess of its actual temperature above that of the air. The velocity of the discharge is directly proportional to the temperature, and inversely as the length of the bar. As there are perpetual variations in the temperature of all terrestrial substances, and of the atmosphere, from the rotation of the earth and its revolution round the sun, from combustion, friction, fermentation, electricity, and an infinity of other causes, the tendency to restore the equability of temperature by the transmission of caloric must maintain all the particles of matter in a state of perpetual oscillation, which will be more or less rapid according to the conducting powers of the substances. From the motion of the heavenly bodies about their axes, and also round the sun, exposing them to perpetual changes of temperature, it may be inferred that similar causes will produce like effects in them too. The revolutions of the double stars show that they are not at rest; and though we are totally ignorant of the changes that may be going on in the nebulæ and millions of other remote bodies, it is more than probable that they are not in absolute repose; so that, as far as our knowledge extends, motion seems to be a law of matter.

Heat applied to the surface of a fluid is propagated downwards very slowly, the warmer, and consequently lighter strata, always remaining at the top. This is the reason why the water at the bottom of lakes fed from alpine chains is so cold; for the heat of the sun is transfused but a little way below the surface. When heat is applied below a liquid, the particles continually rise as they become specifically lighter, in consequence of the caloric, and diffuse it through the mass, their place being perpetually supplied by those that are more dense. The power of conducting heat varies materially in different liquids. Mercury conducts twice as fast as an equal bulk of water, which is the reason why it appears to be so cold. A hot body diffuses its caloric in the air by a double process. The air in contact with it, being heated, and becoming lighter, ascends and scatters its caloric, while, at the same time, another portion is discharged in straight lines by the radiating powers of the surface. Hence a substance cools more rapidly in air than in vacuo, because in the latter case the process is carried on by radiation alone. It is probable that the earth, having originally been of very high temperature, has become cooler by radiation only. The ethereal medium must be too rare to carry off much caloric.

Besides the degree of heat indicated by the thermometer, caloric pervades bodies in an imperceptible or latent state; and their capacity for heat is so various, that very different quantities of caloric are required to raise different substances to the same sensible temperature; it is therefore evident that much of the caloric is absorbed, or latent and insensible to the thermometer. The portion of caloric requisite to raise a body to a given temperature is its specific heat; but latent heat is that portion of caloric which is employed in changing

the state of bodies from solid to liquid, and from liquid to vapour. When a solid is converted into a liquid, a greater quantity of caloric enters into it, than can be detected by the thermometer; this accession of caloric does not make the body warmer, though it converts it into a liquid, and is the principal cause of its fluidity. Ice remains at the temperature of 32° of Fahrenheit till it has combined with or absorbed 140° of caloric, and then it melts, but without raising the temperature of the water above 32°; so that water is a compound of ice and caloric. On the contrary, when a liquid is converted into a solid, a quantity of caloric leaves it without any diminution of temperature. Water at the temperature of 32° must part with 140° of caloric before it freezes. The slowness with which water freezes, or ice thaws, is a consequence of the time required to give out or absorb 140° of latent heat. A considerable degree of cold is often felt during a thaw, because the ice, in its transition from a solid to a liquid state, absorbs sensible heat from the atmosphere and other bodies, and, by rendering it latent, maintains them at the temperature of 32° while melting. According to the same principle, vapour is a combination of caloric with a liquid. By the continued application of heat, liquids are converted into vapour or steam, which is invisible and elastic like common air. Under the ordinary pressure of the atmosphere, that is, when the barometer stands at 30 inches, water acquires a constant accession of heat till its temperature rises to 212° of Fahrenheit; after that it ceases to show any increase in heat, but when it has absorbed an additional 1000° of caloric it is converted into steam. Consequently, about 1000° of latent heat exists in steam without raising its temperature, and steam at 212° must part

with the same quantity of latent caloric when condensed into water. Water boils at different temperatures under different degrees of pressure. It boils at a lower temperature on the top of a mountain than in the plain below, because the weight of the atmosphere is less at the higher station. There is no limit to the temperature to which water might be raised; it might even be made red-hot, could a vessel be found strong enough to resist the pressure. The expansive force of steam is in proportion to the temperature at which the water boils, it may, therefore, be increased to a degree that is only limited by our inability to restrain it, and is the greatest power that has been made subservient to the wants of man.

It is found that the absolute quantity of heat consumed in the process of converting water into steam is the same at whatever temperature water may boil, but that the latent heat of steam is always greater exactly in the same proportion as its sensible heat is less. Steam raised at 212° under the ordinary pressure of the atmosphere, and steam raised at 180° under half that pressure, contain the same quantity of heat, with this difference, that the one has more latent heat and less sensible heat than the other. It is evident that the same quantity of heat is requisite for converting a given weight of water into steam, at whatever temperature or under whatever pressure the water may be boiled; and therefore, in the steam engine, equal weights of steam at a high pressure and a low pressure are produced by the same quantity of fuel, and whatever the pressure of the steam may be, the consumption of fuel is proportional to the quantity of water converted into vapour. Steam at a high pressure expands as soon as it comes into the air, by which some of its sensible heat becomes latent, and

as it naturally has less sensible heat than steam raised under low pressure, its actual temperature is reduced so much, that the hand may be plunged into it without injury the instant it issues from the orifice of a boiler.

The elasticity or tension of steam, like that of common air, varies inversely as its volume, that is, when the space it occupies is doubled, its elastic force is reduced one half. The expansion of steam is indefinite, the smallest quantity of water, when reduced to the form of vapour, will occupy many millions of cubic feet a wonderful illustration of the minuteness of the ultimate particles of matter! The latent heat absorbed in the formation of steam is given out again by its condensation

Steam is formed throughout the whole mass of a boiling liquid, whereas evaporation takes place only at the free surfaces of liquids, and that under the ordinary temperature and pressure of the atmosphere. There is a constant evaporation from the land and water all over the earth The rapidity of its formation does not altogether depend upon the dryness of the air, according to Dr Dalton's experiments, it depends also on the difference between the tension of the vapour which is forming and that which is already in the atmosphere In calm weather, vapour accumulates in the stratum of air immediately above the evaporating surface, and retards the formation of more, whereas a strong wind accelerates the process, by carrying off the vapour as soon as it rises, and making way for a succeeding portion of dry air

The latent heat of air, and of all elastic fluids, may be forced out by sudden compression, like squeezing water out of a sponge. The quantity of heat brought into action in this way is very well illustrated in the ex-

periment of igniting a piece of tinder by the sudden compression of air by a piston thrust into a cylinder closed at one end the developement of heat on a stupendous scale is exhibited in lightning, which is probably produced in part by the violent compression of the atmosphere during the passage of the electric fluid Prodigious quantities of heat are constantly becoming latent, or are disengaged by the changes of condition to which substances are liable in passing from the solid to the liquid, and from the liquid to the gaseous form, or the contrary, occasioning endless vicissitudes of temperature over the globe.

There are many other sources of heat, such as combustion, friction, and percussion, all of which are only means of calling a power into evidence which already exists.

The application of heat to the various branches of the mechanical and chemical arts has, within a few years, effected a greater change in the condition of man than had been accomplished in any equal period of his existence Armed by the expansion and condensation of fluids with a power equal to that of the lightning itself, conquering time and space, he flies over plains, and travels on paths cut by human industry even through mountains, with a velocity and smoothness more like planetary than terrestrial motion; he crosses the deep in opposition to wind and tide; by releasing the strain on the cable, he rides at anchor fearless of the storm, he makes the elements of air and water the carriers of warmth, not only to banish winter from his home, but to adorn it even during the snow-storm with the blossoms of spring, and, like a magician, he raises from the gloomy and deep abyss of the mine, the spirit of light to dispel the midnight darkness.

It has been observed that heat, like light and sound, probably consists in the undulations of an elastic medium. All the principal phenomena of heat may actually be illustrated by a comparison with those of sound. The excitation of heat and sound are not only similar, but often identical, as in friction and percussion; they are both communicated by contact and radiation; and Dr Young observes, that the effect of radiant heat in raising the temperature of a body upon which it falls, resembles the sympathetic agitation of a string, when the sound of another string, which is in unison with it, is transmitted through the air. Light, heat, sound, and the waves of fluids, are all subject to the same laws of reflection, and, indeed, their undulatory theories are perfectly similar. If, therefore, we may judge from analogy, the undulations of some of the heat-producing rays must be less frequent than those of the extreme red of the solar spectrum; but if the analogy were perfect, the interference of two hot rays ought to produce cold, since darkness results from the interference of two undulations of light, silence ensues from the interference of two undulations of sound, and still water, or no tide, is the consequence of the interference of two tides. The propagation of sound, however, requires a much denser medium than that either of light or heat; its intensity diminishes as the rarity of the air increases; so that, at a very small height above the surface of the earth, the noise of the tempest ceases, and the thunder is heard no more in those boundless regions where the heavenly bodies accomplish their periods in eternal and sublime silence.

A consciousness of the fallacy of our senses is one of the most important consequences of the study of nature. This study teaches us that no object is seen

by us in its true place, owing to aberration, that the colours of substances are solely the effects of the action of matter upon light, and that light itself, as well as heat and sound, are not real beings, but mere modes of action communicated to our perceptions by the nerves. The human frame may, therefore, be regarded as an elastic system, the different parts of which are capable of receiving the tremors of elastic media, and of vibrating in unison with any number of superposed undulations, all of which have their perfect and independent effect Here our knowledge ends; the mysterious influence of matter on mind will in all probability be for ever hid from man.

SECTION XXV

ATMOSPHERE OF THE PLANETS AND THE MOON.—CONSTITUTION OF THE SUN.—ESTIMATION OF THE SUN'S LIGHT.—ITS INFLUENCE ON THE DIFFERENT PLANETS.—TEMPERATURE OF SPACE.—INTERNAL HEAT OF THE EARTH.—ZONE OF CONSTANT TEMPERATURE.—HEAT INCREASES WITH THE DEPTH.—HEAT IN MINES AND WELLS.—CENTRAL HEAT.—VOLCANIC ACTION.—THE HEAT ABOVE THE ZONE OF CONSTANT TEMPERATURE ENTIRELY FROM THE SUN.—THE QUANTITY OF HEAT ANNUALLY RECEIVED FROM THE SUN.—ISOGEOTHERMAL LINES.—DISTRIBUTION OF HEAT ON THE EARTH.—CLIMATE.—LINE OF PERPETUAL CONGELATION.—CAUSES AFFECTING CLIMATE.—ISOTHERMAL LINES.—EXCESSIVE CLIMATES.—THE SAME QUANTITY OF HEAT ANNUALLY RECEIVED AND RADIATED BY THE EARTH.

THE ocean of light and heat perpetually flowing from the sun, must affect the bodies of the system very differently, on account of the varieties in their atmospheres, some of which appear to be very extensive and dense. According to the observations of Schroeter, the atmosphere of Ceres is more than 668 miles high, and that of Pallas has an elevation of 465 miles. These must refract the light and prevent the radiation of heat like our own. But it is remarkable that not a trace of atmosphere can be perceived in Vesta; and that Jupiter, Saturn, and Mars have very little. The action of the sun's rays must be very different on these bodies from what it is on the earth, and the heat imparted to them quickly lost by radiation; yet it is impossible to estimate their temperature, since the cold may be counteracted by their central heat, if, as there is reason to presume, they have originally been in a state of fusion, possibly of vapour. The attraction of the earth has probably deprived the moon of hers; for the refractive

power of the air, at the surface of the earth, is at least a thousand times as great as the refraction at the surface of the moon. The lunar atmosphere, therefore, must be of a greater degree of rarity than can be produced by our best air-pumps; consequently no terrestrial animal could exist in it.

The sun has a very dense atmosphere. What his body may be, it impossible to conjecture; but he seems to be surrounded by a mottled ocean of flame, through which his dark nucleus appears like black spots, often of enormous size. These spots are almost always comprised within a zone of the sun's surface, whose breadth, measured on a solar meridian, does not extend beyond 30½° on each side of his equator, though they have been seen at the distance of 39½°. From their extensive and rapid changes, there is every reason to suppose that the exterior and incandescent part of the sun is gaseous. The solar rays probably arising from chemical processes that continually take place at his surface, or from electricity, are transmitted, through space, in all directions; but, notwithstanding the sun's magnitude, and the inconceivable heat that must exist at his surface, as the intensity both of his light and heat diminishes as the square of the distance increases, his kindly influence can hardly be felt at the boundaries of our system.

The direct light of the sun has been estimated to be equal to that of 5563 wax candles of moderate size, supposed to be placed at the distance of one foot from the object. That of the moon is probably only equal to the light of one candle at the distance of twelve feet. Consequently the light of the sun is more than three hundred thousand times greater than that of the moon. Hence the light of the moon either imparts no heat, or

It is too feeble to penetrate the glass of the thermometer, even when brought to a focus by a mirror.[1] The intensity of the sun's light diminishes from the centre to the circumference of the solar disc, but in the moon the gradation is reversed.

In Uranus, the sun must be seen like a small but brilliant star, not above the hundred and fiftieth part so bright as he appears to us; but that is 1000 times brighter than our moon, so that he is really a sun to Uranus, and probably imparts some degree of warmth. But if we consider that water would not remain fluid in any part of Mars, even at his equator, and that in the temperate zones of the same planet even alcohol and quicksilver would freeze, we may form some idea of the cold that must reign in Uranus.

The climate of Venus more nearly resembles that of the earth, though, excepting perhaps at her poles, much too hot for animal and vegetable life as they exist here; but in Mercury, the mean heat arising only from the intensity of the sun's rays, must be above that of boiling quicksilver, and water would boil even at his poles. Thus the planets, though kindred with the earth in motion and structure, are totally unfit for the habitation of such a being as man.

It is found by experience, that heat is developed in opaque and translucent substances by their absorption of solar light, but that the sun's rays do not alter the temperature of perfectly transparent bodies through which they pass. As the temperature of the pellucid planetary space cannot be affected by the passage of the sun's light and heat, neither can it be sensibly raised by the heat now radiated from the earth; consequently its temperature must be invariable. The atmosphere, on the con-

[1] Note 210.

trary, gradually increasing in density towards the surface of the earth, becomes less pellucid, and therefore gradually increases in temperature, both from the direct action of the sun, and from the radiation of the earth. Lambert had proved that the capacity of the atmosphere for heat varies according to the same law with its capacity for absorbing a ray of light passing through it from the zenith, whence M. Svanberg found that the temperature of space is 58° below the zero point of Fahrenheit's thermometer. From other researches, founded upon the rate and quantity of atmospheric refraction, he obtained a result which only differs from the preceding by half a degree. M. Fourier has arrived at nearly the same conclusion from the law of the radiation of the heat of the terrestrial spheroid, on the hypothesis of its having nearly attained its limit of temperature in cooling down from its supposed primitive state of fusion. The difference in the result of these three methods, totally independent of one another, only amounts to the fraction of a degree.

Doubtless, the radiation of all the bodies in the universe maintains the ethereal medium at a higher temperature than it would otherwise have, and must eventually increase it, but by a quantity so evanescent that it is hardly possible to conceive a time when a change will become perceptible.

Thus, as the temperature of space is uniform, it follows that no part of Uranus can experience a degree of cold more than 90° below the freezing point of Fahrenheit; which only exceeds that which Sir Edward Parry suffered one day at Melville Island by 3°.

The temperature of space being so low, it becomes a matter of no small interest to ascertain whether the earth may not be ultimately reduced by radiation to

the temperature of the surrounding medium, what the sources of heat are, and whether they be sufficient to compensate the loss, and to maintain the earth in a state fit for the support of animal and vegetable life in time to come. All observations that have been made under the surface of the ground concur in proving, that there is a stratum at the depth of from 80 to 100 feet throughout the whole earth, where the temperature is invariable at all times and seasons, and which differs but little from the mean annual temperature of the country above. In the course of more than half a century, the temperature of the earth at the depth of 90 feet in the caves of the Observatory at Paris has never been above or below 53° of Fahrenheit's thermometer, which is only 2° above the mean annual temperature at Paris. This zone, unaffected by the sun's rays from above, or by the internal heat from below, serves as an origin whence the effects of the external heat are estimated on one side, and the internal temperature of the globe on the other.

As early as the year 1740, M. Gensanne discovered, in the lead mines of Giromagny, three leagues from Befort, that the heat of the ground increases with the depth below the zone of constant temperature. A vast number of observations have been made since that time in the mines of Europe and America, by MM. Saussure, Daubuisson, Humboldt, Cordier, Fox, and others, which agree, without an exception, in proving that the temperature of the earth becomes higher in descending towards its centre. The greatest depth that has been attained is in the silver mine of Guanaxato in Mexico, where M. de Humboldt found a temperature of 98° at the depth of 285 fathoms, the mean annual temperature of the country being only 61°. Next to that is

the Dalcoath copper mine in Cornwall, where Mr Fox's thermometer stood at 76° in a hole in the rock, at the depth of 230 fathoms, and at 82° in water at the depth of 240 fathoms, the mean annual temperature at the surface being about 50° But it is needless to multiply examples, all of which concur in showing that there is a very great difference between the temperature in the interior of the earth and at its surface. Mr. Fox's observations on the temperature of springs, which rise at profound depths in mines, afford the strongest testimony. He found considerable streams flowing into some of the Cornish mines at the temperature of 80° or 90°, which is about 30° or 40° above that of the surface; and also ascertained that nearly 2,000,000 gallons of water are daily pumped from the bottom of the Poldice mine, which is 176 fathoms deep, at 90° or 100° As this is higher than the warmth of the human body, Mr Fox justly observes, that it amounts to a proof that the increased temperature cannot proceed from the persons of the workmen employed in the mines Neither can the warmth of mines be attributed to the condensation of the currents of air which ventilate them Mr. Fox, whose opinion is of high authority in these matters, states that even in the deepest mines the condensation of the air would not raise the temperature more than 5° or 6°, and that if the heat could be attributed to this cause, the seasons would sensibly affect the temperature of mines, which it appears they do not where the depth is great Besides, the Cornish mines are generally ventilated by numerous shafts opening into the galleries from the surface or from a higher level. The air circulates freely in these, descending in some shafts and ascending in others In all cases, Mr. Fox found that the upward currents are of a higher temperature than

the descending currents; so much so, that in winter the moisture is often frozen in the latter to a considerable depth; the circulation of air, therefore, tends to cool the mine instead of increasing the heat. Mr. Fox has also removed the objections arising from the comparatively low temperature of the water in the shafts of abandoned mines, by showing that observations in them, from a variety of circumstances which he enumerates, are too discordant to furnish any conclusion as to the actual heat of the earth. The high temperature of mines might be attributed to the effects of the fires, candles, and gunpowder used by the miners, did not a similar increase obtain in deep wells and in borings to great depths in search of water, where no such causes of disturbance occur. In a well dug with a view to discover salt in the canton of Berne, and long deserted, M. de Saussure had the most complete evidence of increasing heat. The same has been confirmed by the temperature of many wells, both in France and England, especially by the Artesian wells, so named from a peculiar method of raising water first resorted to in Artois, and since become very general. An Artesian well consists of a shaft of a few inches in diameter, bored into the earth till a spring is found. To prevent the water being carried off by the adjacent strata, a tube is let down which exactly fills the bore from top to bottom, in which the water rises pure to the surface. It is clear the water could not rise unless it had previously descended from high ground through the interior of the earth to the bottom of the well. It partakes of the temperature of the strata through which it passes, and in every instance has been warmer in proportion to the depth of the well; but it is evident that the law of increase cannot be obtained in this manner. Perhaps the

most satisfactory experiments on record are those made by MM. August de la Rive and F Marcet during the year 1833, in a boring for water about a league from Geneva, at a place 318 feet above the level of the lake. The depth of the bore was 727 feet, and the diameter only between four and five inches. No spring was ever found, but the shaft filled with mud, from the moisture of the ground mixing with the earth displaced in boring, which was peculiarly favourable for the experiments, as the temperature at each depth may be considered to be that of the particular stratum In this case, where none of the ordinary causes of disturbance could exist, and where every precaution was employed by scientific and experienced observers, the temperature was found to increase regularly and uniformly with the depth at the rate of about 1° of Fahrenheit for every 52 feet Though there can be no doubt as to the increase of temperature in penetrating the crust of the earth, there is much uncertainty as to the law of increase, which varies with the nature of the soil and other local circumstances, but, on an average, it has been estimated at the rate of 1° for every 40 or 50 feet, which corresponds with the observations of MM Marcet and De la Rive

It is hardly to be expected that any information with regard to the internal temperature of the earth should be obtained from that of the ocean, on account of the mobility of fluids, by which the colder masses sink downwards, while those that are warmer rise to the surface Nevertheless it may be stated, that the temperature of the sea decreases with the depth, between the tropics, while, on the contrary, all our northern navigators found that the temperature increases with the

depth, in the polar seas. The change takes place about the 70th parallel of latitude.

Should the earth's temperature increase at the rate of 1° every 50 feet, it is clear that at the depth of 200 miles the hardest substances must be in a state of fusion, and our globe must, in that case, be a ball of liquid fire 7600 miles in diameter, enclosed in a thin coating of solid matter; for 200 miles are nothing when compared with the size of the earth. No doubt the form of the earth, as determined by the pendulum and arcs of the meridian, as well as by the motions of the moon, indicates original fluidity and a subsequent consolidation and reduction of temperature by radiation; but whether this really was the primitive condition of our planet, and whether the law of increasing temperature is uniform at still greater depths than those already attained by man, it is impossible to say. At all events, internal fluidity is not inconsistent with the present state of the earth's surface, since earthy matter is as bad a conductor of caloric as lava, which often retains its heat at a very little depth for years after its surface is cool. Whatever the radiation of the earth might have been in former times, certain it is that it goes on very slowly in our days; for M. Fourier has computed that the central heat is decreasing from radiation by only about the $\frac{1}{30000}$th part of a second in a century. If so, there can be no doubt that it will ultimately be dissipated; but, as far as regards animal and vegetable life, it is of very little consequence whether the centre of our planet be liquid fire or ice, since its condition in either case could have no sensible effect on the climate at its surface. The internal fire does not even impart heat enough to melt the snow at the poles, though so

much nearer to the centre than any other part of the globe.

The immense extent of active volcanic fire is one of the causes of heat which must not be overlooked.

The range of the Andes from Chili to the north of Mexico, probably from Cape Horn to California, or even to New Madrid in the United States, is one vast district of igneous action, including the Caribbean Sea and the West Indian islands on one hand; and stretching quite across the Pacific Ocean, through the Polynesian Archipelago, the New Hebrides, the Georgian and Friendly Islands, on the other. Another chain begins with the Aleutian Islands, extends to Kamtschatka, and from thence passes through the Kurile, Japanese, and Philippine Islands to the Moluccas, whence it spreads, with terrific violence, through the Indian Archipelago, even to the Bay of Bengal. Volcanic action may again be followed from the entrance of the Persian Gulf, to Madagascar, Bourbon, the Canaries, and Azores. Thence a continuous igneous region extends through about 1000 geographical miles to the Caspian Sea, including the Mediterranean, and extending north and south between the 35th and 40th parallels of latitude. In Central Asia, a volcanic region occupies 2500 square geographical miles, and to these may be added Iceland, within 25 degrees of the pole. Throughout this vast portion of the world, the subterraneous fire is often intensely active, producing such violent earthquakes and eruptions, that their effects, accumulated during millions of years, may account for the great geological changes of igneous origin that have already taken place in the earth, and may occasion others not less remarkable, should time — that essential

element in the vicissitudes of the globe — be granted, and their energy last.

Mr Lyell, who has shown the power of existing causes with great ingenuity, estimates that, on an average, twenty eruptions take place annually in different parts of the world, and many must occur, or have happened, even on the most extensive and awful scale, among people equally incapable of estimating their effects and of recording them. We should never have known the extent of the fearful eruption which took place in the island of Sumbawa, in 1815, but for the accident of Sir Stamford Raffles having been governor of Java at the time. It began on the 5th of April, and did not entirely cease till July. The ground was shaken through an area of 1000 English miles in circumference, the tremors were felt in Java, the Moluccas, a great part of Celebes, Sumatra, and Borneo. The detonations were heard in Sumatra, at the distance of 970 geographical miles in a straight line, and at Ternate, 720 miles in the opposite direction. The most dreadful whirlwinds carried men and cattle into the air, and, with the exception of 26 persons, the whole population of the island perished, to the amount of 12,000 Ashes were carried 300 miles, to Java, in such quantities, that the darkness, during the day, was more profound than ever had been witnessed in the most obscure night. The face of the country was changed by the streams of lava, the upheaving and the sinking of the soil. The town of Tomboro was submerged, and water stood to the depth of 18 feet in places which had been dry land. Ships grounded where they had previously anchored, and could hardly penetrate the mass of cinders which floated on the sur-

face of the sea for several miles to the depth of two feet A catastrophe similar to this, though of less magnitude, took place in the island of Bali in 1808, which was not heard of in Europe till years afterwards. Many volcanos, supposed to be extinct, have all at once burst out with inconceivable violence. Witness Vesuvius, on historical record, and the volcano in the island of St. Vincent in our own days, whose crater was lined with large trees, and which had not been active in the memory of man. Vast tracts are of volcanic origin, where volcanos have ceased to exist for ages Whence it may be inferred, that in some places the subterraneous fires are in the highest state of activity, in some they are inert, and in others they appear to be extinct. Yet there are few countries that are not subject to earthquakes of greater or less intensity, the tremors are propagated like a sonorous undulation to such distances, that it is impossible to say in what point they originate In some recent instances, their power must have been tremendous. In South America, so lately as 1822, an area of 100,000 square miles, which is equal in extent to the half of France, was raised several feet above its present level, a most able account of which is given in the "Transactions of the Geological Society," by an esteemed friend of the author's, Mrs. Graham, now Mrs. Callcott, who was present during the whole time of that formidable earthquake, which recurred at short intervals for more than two months, and who possesses talents to appreciate, and had opportunities of observing its effects under the most favourable circumstances at Valparaiso, and for miles along the coast, where it was most intense In 1819, a ridge of land stretching for 50 miles across the delta of the Indus, 16 feet broad, was raised 10

feet above the plain, yet the account of this marvellous event was only brought to Europe last year by Captain Burnes. The reader is referred to Mr Lyell's very excellent work on geology, already mentioned, for most interesting details of the phenomena and extensive effects of volcanos and earthquakes too numerous to find a place here. It may, however, be mentioned, that innumerable earthquakes are from time to time shaking the solid crust of the globe, and carrying destruction to distant regions, progressively though slowly accomplishing the great work of change. These terrible engines of ruin, fitful and uncertain as they may seem, must, like all durable phenomena, have a law, which may in time be discovered by long-continued and accurate observations.

The shell of volcanic fire that girds the globe at a small depth below our feet, has been attributed to three different causes. By some it is supposed to originate in an ocean of incandescent matter, still existing in the central abyss of the earth. Some conceive it to be superficial, and due to chemical action in strata at no very great depth when compared with the size of the globe. The more so, as matter on a most extensive scale is passing from old into new combinations, which, if rapidly effected, are capable of producing the most intense heat. According to others, electricity, which is so universally diffused in all its forms throughout the earth, if not the immediate cause of the volcanic phenomena, at least determines the chemical affinities that produce them. It is clear that a subject so involved in mystery must give rise to much speculation, in which every hypothesis is attended with difficulties that observation alone can remove. But to whatever cause the increasing heat of the earth and the sub-

terranean fires may ultimately be referred, it is certain that, except in some local instances, they have no sensible effect on the temperature of its surface. It may, therefore, be concluded, that the heat of the earth above the zone of uniform temperature is entirely owing to the sun.

The power of the solar rays depends much upon the manner in which they fall, as we readily perceive from the different climates on our globe. In winter, the earth is nearer the sun by about $\frac{1}{30}$ than in summer, but the rays strike the northern hemisphere more obliquely in winter than in the other half of the year.

M. Pouillet has estimated with singular ingenuity, from a series of observations made by himself, that the whole quantity of heat which the earth receives annually from the sun, is such as would be sufficient to melt a stratum of ice covering the whole globe 46 feet deep. Part of this heat is radiated back into space; but by far the greater part descends into the earth during the summer, towards the zone of uniform temperature, whence it returns to the surface in the course of the winter, and tempers the cold of the ground and the atmosphere in its passage to the ethereal regions, where it is lost, or rather where it combines with the radiation from the other bodies of the universe in maintaining the temperature of space. The sun's power being greatest between the tropics, the caloric sinks deeper there than elsewhere, and the depth gradually diminishes towards the poles, but the heat is also transmitted laterally from the warmer to the colder strata north and south of the equator, and aids in tempering the severity of the polar regions.

The mean heat of the earth above the stratum

of constant temperature is determined from that of springs; and if the spring be on elevated ground, the temperature is reduced by computation to what it would be at the level of the sea, assuming that the heat of the soil varies according to the same law as the heat of the atmosphere, which is about 1° of Fahrenheit's thermometer for every 344·7 feet. From a comparison of the temperature of numerous springs with that of the air, Sir David Brewster concludes that there is a particular line passing nearly through Berlin, at which the temperature of springs and that of the atmosphere coincide; that in approaching the Arctic Circle the temperature of springs is always higher than that of the air, while proceeding towards the equator it is lower.

Since the warmth of the superficial strata of the earth decreases from the equator to the poles, there are many places in both hemispheres where the ground has the same mean temperature. If lines were drawn through all those points in the upper strata of the globe which have the same mean annual temperature, they would be nearly parallel to the equator between the tropics, and would become more and more irregular and sinuous towards the poles. These are called isogeothermal lines. A variety of local circumstances disturb their parallelism, even between the tropics.

The temperature of the ground at the equator is lower on the coasts and islands than in the interior of continents; the warmest part is in the interior of Africa, but it is obviously affected by the nature of the soil, especially if it be volcanic.

Much has been done within a few years to ascertain the manner in which heat is distributed over the surface of our planet, and the variations of climate; which in a general view mean every change of the atmosphere, such

as of temperature, humidity, variations of barometric pressure, purity of air, the serenity of the heavens, the effects of winds, and electric tension Temperature depends upon the property which all bodies possess, more or less, of perpetually absorbing and emitting or radiating heat When the interchange is equal, the temperature of a body remains the same, but when the radiation exceeds the absorption, it becomes colder, and *vice versâ*. In order to determine the distribution of heat over the surface of the earth, it is necessary to find a standard by which the temperature in different latitudes may be compared For that purpose, it is requisite to ascertain by experiment the mean temperature of the day, of the month, and of the year, at as many places as possible throughout the earth The annual average temperature may be found by adding the mean temperatures of all the months in the year, and dividing the sum by 12. The average of ten or fifteen years will give it with tolerable accuracy, for, although the temperature in any place may be subject to very great variations, yet it never deviates more than a few degrees from its mean state, which consequently offers a good standard of comparison.

If climate depended solely upon the heat of the sun, all places having the same latitude would have the same mean annual temperature The motion of the sun in the ecliptic, indeed, occasions perpetual variations in the length of the day, and in the direction of the rays with regard to the earth, yet, as the cause is periodic, the mean annual temperature from the sun's motion alone must be constant in each parallel of latitude. For it is evident that the accumulation of heat in the long days of summer, which is but little diminished by radiation during the short nights, is balanced by the small quan-

tity of heat received during the short days in winter, and its radiation in the long frosty and clear nights. In fact, if the globe were every where on a level with the surface of the sea, and of uniform substance, so as to absorb and radiate heat equally, the mean heat of the sun would be regularly distributed over its surface in zones of equal annual temperature parallel to the equator, from which it would decrease to each pole as the square of the cosine of the latitude; and its quantity would only depend upon the altitudes of the sun, and atmospheric currents. The distribution of heat, however, in the same parallel, is very irregular in all latitudes, except between the tropics, where the isothermal lines, or the lines passing through places of equal mean annual temperature, are more nearly parallel to the equator. The causes of disturbance are very numerous; but such as have the greatest influence, according to M. De Humboldt, to whom we are indebted for the greater part of what is known on the subject, are the elevation of the continents, the distribution of land and water over the surface of the globe, exposing different absorbing and radiating powers, the variations in the surface of the land, as forests, sandy deserts, verdant plains, rocks, &c.; mountain-chains covered with masses of snow, which diminish the temperature; the reverberation of the sun's rays in the valleys, which increases it; and the interchange of currents, both of air and water, which mitigate the rigour of climates; the warm currents from the equator softening the severity of the polar frosts, and the cold currents from the poles tempering the intense heat of the equatorial regions. To these may be added cultivation, though its influence extends over but a small portion of the globe, only a fourth part of the land being inhabited.

Temperature does not vary so much with latitude as with the height above the level of the sea, the decrease is more rapid in the higher strata of the atmosphere than in the lower, because they are farther removed from the radiation of the earth, and being highly rarefied, the heat is diffused through a larger space A portion of air at the surface of the earth, whose temperature is 70° of Fahrenheit, if carried to the height of two miles and a half, would expand so much that its temperature would be reduced 50°, and in the ethereal regions the temperature is 90° below the point of congelation.

The height at which snow lies perpetually, decreases from the equator to the poles, and is higher in summer than in winter, but it varies from many circumstances. Snow rarely falls when the cold is intense and the atmosphere dry. Extensive forests produce moisture by their evaporation, and high table-lands, on the contrary, dry and warm the air. In the Cordilleras of the Andes, plains of only twenty-five square leagues raise the temperature as much as 3° or 4° above what is found at the same altitude on the rapid declivity of a mountain, consequently the line of perpetual snow varies according as one or other of these causes prevails Aspect has also a great influence The line of perpetual snow is much higher on the southern than on the northern side of the Himalaya mountains On the whole it appears that the mean height between the tropics at which the snow lies perpetually is about 15,207 feet above the level of the sea, whereas snow does not cover the ground continually at the level of the ocean till near the north pole In the southern hemisphere, however, the cold is greater than in the northern In Sandwich land, between the 54th and 58th degrees

of latitude, perpetual snow and ice extend to the sea-beach; and in the island of St. George's, in the 53d degree of south latitude, which corresponds with the latitude of the central counties of England, perpetual snow descends even to the level of the ocean. It has been shown that this excess of cold in the southern hemisphere cannot be attributed to the winter being longer than ours by 7¾ days. It is probably owing to the open sea round the south pole, which permits the icebergs to descend to a lower latitude by 10° than they do in the northern hemisphere, on account of the numerous obstructions opposed to them by the islands and continents about the north pole. Icebergs seldom float farther to the south than the Azores; whereas those that come from the south pole descend as far as the Cape of Good Hope, and occasion a continual absorption of heat in melting.

The influence of mountain-chains does not wholly depend upon the line of perpetual congelation. They attract and condense the vapours floating in the air, and send them down in torrents of rain. They radiate heat into the atmosphere at a lower elevation, and increase the temperature of the valleys by the reflection of the sun's rays, and by the shelter they afford against prevailing winds. But, on the contrary, one of the most general and powerful causes of cold arising from the vicinity of mountains, is the freezing currents of wind which rush from their lofty peaks along the rapid declivities, chilling the surrounding valleys: such is the cutting north wind called the bise in Switzerland.

Next to elevation, the difference in the radiating and absorbing powers of the sea and land has the greatest influence in disturbing the regular distribution of heat. The extent of the dry land is not above the fourth part

of that of the ocean, so that the general temperature of the atmosphere, regarded as the result of the partial temperatures of the whole surface of the globe, is most powerfully modified by the sea. Besides, the ocean acts more uniformly on the atmosphere than the diversified surface of the solid mass does, both by the equality of its curvature and its homogeneity. In opaque substances the accumulation of heat is confined to the stratum nearest the surface. The seas become less heated at their surface than the land, because the solar rays, before being extinguished, penetrate the transparent liquid to a greater depth, and in greater numbers than in the opaque masses. On the other hand, water has a considerable radiating power, which, together with evaporation, would reduce the surface of the ocean to a very low temperature, if the cold particles did not sink to the bottom, on account of their superior density. The seas preserve a considerable portion of the heat they receive in summer, and, from their saltness, do not freeze so soon as fresh water. So that, in consequence of all these circumstances, the ocean is not subject to such variations of heat as the land, and, by imparting its temperature to the winds, it diminishes the rigor of climate on the coasts and in the islands, which are never subject to such extremes of heat and cold as are experienced in the interior of continents, though they are liable to fogs and rain from the evaporation of the adjacent seas. On each side of the equator, to the 48th degree of latitude, the surface of the ocean is in general warmer than the air above it. The mean of the difference of temperature at noon and midnight is about 1°·87, the greatest deviation never exceeding from 0°·36 to 2°·16, which is much cooler than the air over the land.

On land the temperature depends upon the nature of the soil and its products, its habitual moisture or dryness. From the eastern extremity of the Sahara desert quite across Africa, the soil is almost entirely barren sand, and the Sahara desert itself, without including Dafour or Dongola, extends over an area of 194,000 square leagues, equal to twice the area of the Mediterranean Sea, and raises the temperature of the air by radiation from 90° to 100°, which must have a most extensive influence. On the contrary, vegetation cools the air by evaporation and the apparent radiation of cold from the leaves of plants, because they absorb more caloric than they give out. The graminiferous plains of South America cover an extent ten times greater than France, occupying no less than about 50,000 square leagues, which is more than the whole chain of the Andes, and all the scattered mountain-groups of Brazil. These, together with the plains of North America and the steppes of Europe and Asia, must have an extensive cooling effect on the atmosphere, if it be considered that, in calm and serene nights, they cause the thermometer to descend 12° or 14°, and that, in the meadows and heaths in England, the absorption of heat by the grass is sufficient to cause the temperature to sink to the point of congelation during the night for ten months in the year. Forests cool the air also, by shading the ground from the rays of the sun, and by evaporation from the boughs. Hales found that the leaves of a single plant of helianthus, three feet high, exposed nearly forty feet of surface; and if it be considered that the woody regions of the river Amazons, and the higher part of the Oroonoko, occupy an area of 260,000 square leagues, some idea may be formed of the torrents of vapour which arise from the leaves of

the forests all over the globe. However, the frigorific effects of their evaporation are counteracted in some measure by the perfect calm which reigns in the tropical wildernesses. The innumerable rivers, lakes, pools, and marshes interspersed through the continents absorb caloric, and cool the air by evaporation, but on account of the chilled and dense particles sinking to the bottom, deep water diminishes the cold of winter, so long as ice is not formed.

In consequence of the difference in the radiating and absorbing powers of the sea and land, their configuration greatly modifies the distribution of heat over the surface of the globe Under the equator, only one sixth part of the circumference is land; and the superficial extent of land in the northern and southern hemispheres is in the proportion of three to one. The effect of this unequal division is greater in the temperate than in the torrid zones, for the area of land in the northern temperate zone is to that in the southern as thirteen to one, whereas the proportion of land between the equator and each tropic is as five to four. It is a curious fact, noticed by Mr Gardner, that only one twenty-seventh part of the land of the globe has land diametrically opposite to it. This disproportionate arrangement of the solid part of the globe has a powerful influence on the temperature of the southern hemisphere. But, besides these greater modifications, the peninsulas, promontories, and capes, running out into the ocean, together with bays and internal seas, all affect temperature. To these may be added, the position of continental masses with regard to the cardinal points. All these diversities of land and water influence temperature by the agency of the winds. On this account the temperature is lower on the eastern coasts, both of

the New and Old World, than on the western; for, considering Europe as an island, the general temperature is mild in proportion as the aspect is open to the western ocean, the superficial temperature of which, as far north as the 45th and 50th degrees of latitude, does not fall below 48° to 51° of Fahrenheit, even in the middle of winter. On the contrary, the cold of Russia arises from its exposure to the northern and eastern winds. But the European part of that empire has a less rigorous climate than the Asiatic, because the whole northern extremity of Europe is separated from the polar ice by a zone of open sea, whose winter temperature is much above that of a continental country under the same latitude.

The interposition of the atmosphere modifies all the effects of the sun's heat. The earth communicates its temperature so slowly, that M. Arago has occasionally found as much as from 14° to 18° of difference between the heat of the soil and that of the air two or three inches above it.

The circumstances which have been enumerated, and many more, concur in disturbing the regular distribution of heat over the globe, and occasion numberless local irregularities. Nevertheless the mean annual temperature becomes gradually lower from the equator to the poles. But the diminution of mean heat is most rapid between the 40th and 45th degree of latitude, both in Europe and America, which accords perfectly with theory, whence it appears, that the variation in the square of the cosine of the latitude[1] which expresses the law of the change of temperature, is a maximum towards the 45th degree of latitude. The mean annual temperature under the line in America is about 81½°

[1] Note 181.

of Fahrenheit, in Africa it is said to be nearly 83°. The difference probably arises from the winds of Siberia and Canada, whose chilly influence is sensibly felt in Asia and America, even within 18° of the equator.

The isothermal lines are nearly parallel to the equator, till about 22° of latitude on each side of it, where they begin to lose their parallelism, and continue to do so more and more as the latitude augments. With regard to the northern hemisphere, the isothermal line of 59° of Fahrenheit passes between Rome and Florence, in latitude 43°, and near Raleigh, in North Carolina, latitude 36°, that of 50° of equal annual temperature runs through the Netherlands, latitude 51°, and near Boston, in the United States, latitude 42½°, that of 41° passes near Stockholm, latitude 59½°, and St George's Bay, Newfoundland, latitude 48°; and lastly, the line of 32°, the freezing point of water, passes between Ulea, in Lapland, latitude 66°, and Table Bay, on the coast of Labrador, latitude 54°.

Thus it appears, that the isothermal lines which are nearly parallel to the equator for about 22°, afterwards deviate more and more. From the observations of Sir Charles Giesecke in Greenland, of Mr. Scoresby in the Arctic Seas, and also from those of Sir Edward Parry and Sir John Franklin, it is found that the isothermal lines of Europe and America entirely separate in the high latitudes, and surround two poles of maximum cold, one in America and the other in the north of Asia, neither of which coincides with the pole of the earth's rotation. These poles are both situate in about the 80th parallel of north latitude. The Transatlantic pole is in the 100th degree of west longitude, about 5° to the north of Sir Graham Moore's Bay, in the Polar Seas, and the Asiatic pole is in the 95th degree of east

longitude, a little to the north of the Bay of Taimura, near the North-east Cape. According to the estimation of Sir David Brewster, from the observations of M. De Humboldt and Captains Parry and Scoresby, the mean annual temperature of the Asiatic pole is nearly 1° of Fahrenheit's thermometer, and that of the Transatlantic pole about $3\frac{1}{2}$° below zero, whereas he supposes the mean annual temperature of the pole of rotation to be 4° or 5°. It is believed that two corresponding poles of maximum cold exist in the southern hemisphere, though observations are wanting to trace the course of the southern isothermal lines with the same accuracy as the northern.

The isothermal lines, or such as pass through places where the mean annual temperature of the air is the same, do not always coincide with the isogeothermal lines, which are those passing through places where the mean temperature of the ground is the same. Sir David Brewster, in discussing this subject, finds that the isogeothermal lines are always parallel to the isothermal lines; consequently the same general formula will serve to determine both, since the difference is a constant quantity, obtained by observation, and depending upon the distance of the place from the neutral isothermal line. These results are confirmed by the observations of M. Kupffer, of Kasan, during his excursions to the north, which show that the European and the American portions of the isogeothermal line of 32° of Fahrenheit actually separate, and go round the two poles of maximum cold. This traveller remarked, also, that the temperature both of the air and of the soil decreases most rapidly towards the 45th degree of latitude.

It is evident that places may have the same mean annual temperature, and yet differ materially in climate.

In one, the winters may be mild and the summers cool: whereas another may experience the extremes of heat and cold. Lines passing through places having the same mean summer or winter temperature, are neither parallel to the isothermal, the geothermal lines, nor to one another, and they differ still more from the parallels of latitude. In Europe, the latitude of two places which have the same annual heat never differs more than 8° or 9°, whereas the difference in the latitude of those having the same mean winter temperature is sometimes as much as 18° or 19°. At Kasan, in the interior of Russia, in latitude 55° 48, nearly the same with that of Edinburgh, the mean annual temperature is about 37°·6, at Edinburgh it is 47°·84. At Kasan, the mean summer temperature is 64°·84, and that of winter 2°·12, whereas at Edinburgh the mean summer temperature is 58°·28, and that of winter 38°·66. Whence it appears that the difference of winter temperature is much greater than that of summer. At Quebec, the summers are as warm as those in Paris, and grapes sometimes ripen in the open air, whereas the winters are as severe as in Petersburgh, the snow lies five feet deep for several months, wheel carriages cannot be used, the ice is too hard for skating, travelling is performed in sledges, and frequently on the ice of the river St. Lawrence. The cold at Melville Island, on the 15th of January, 1820, according to Sir Edward Parry, was 55° below the zero of Fahrenheit's thermometer, only 3° above the temperature of the ethereal regions, yet the summer heat in these high latitudes is insupportable.

Observations tend to prove that all the climates of the earth are stable, and that their vicissitudes are only periods or oscillations of more or less extent, which vanish in the mean annual temperature of a sufficient

number of years. This constancy of the mean annual temperature of the different places on the surface of the globe shows that the same quantity of heat, which is annually received by the earth, is annually radiated into space. Nevertheless, a variety of causes may disturb the climate of a place; cultivation may make it warmer, but it is at the expense of some other place, which becomes colder in the same proportion. There may be a succession of cold summers and mild winters, but in some other country the contrary takes place to effect the compensation; wind, rain, snow, fog, and the other meteoric phenomena, are the ministers employed to accomplish the changes. The distribution of heat may vary with a variety of circumstances, but the absolute quantity lost and gained by the whole earth in the course of a year is invariably the same.

SECTION XXVI.

INFLUENCE OF TEMPERATURE ON VEGETATION — VEGETATION VARIES WITH THE LATITUDE AND HEIGHT ABOVE THE SEA — GEOGRAPHICAL DISTRIBUTION OF LAND PLANTS — DISTRIBUTION OF MARINE PLANTS — CORALLINES, SHELL FISH, REPTILES, INSECTS, BIRDS, AND QUADRUPEDS — VARIETIES OF MANKIND, YET IDENTITY OF SPECIES.

THE gradual decrease of temperature in the air and in the earth, from the equator to the poles, is clearly indicated by its influence on vegetation. In the valleys of the torrid zone, where the mean annual temperature is very high, and where there is abundance of moisture, nature adorns the soil with all the luxuriance of perpetual summer. The palm, the bombax ceiba, and a variety of magnificent trees, tower to the height of 150 or 200 feet above the banana, the bamboo, the arborescent fern, and numberless other tropical productions, so interlaced by creeping and parasitical plants as often to present an impenetrable barrier. But the richness of vegetation gradually diminishes with the temperature; the splendour of the tropical forest is succeeded by the regions of the olive and vine; these again yield to the verdant meadows of more temperate climes; then follow the birch and the pine, which probably owe their existence in very high latitudes more to the warmth of the soil than to that of the air. But even these enduring plants become dwarfish stunted shrubs, till a verdant carpet of mosses and lichens enamelled with flowers exhibits the last signs of vegetable life during

the short but fervent summers of the polar regions. Such is the effect of cold on the vegetable kingdom, that the number of species growing under the line, and in the northern latitudes of 45° and 68°, are in the proportion of the numbers 12, 4, and 1. Notwithstanding the remarkable difference between a tropical and polar Flora, moisture seems to be almost the only requisite for vegetation, since neither heat, cold, nor even darkness, destroys the fertility of nature. In salt plains and sandy deserts alone, hopeless barrenness prevails. Plants grow on the borders of hot springs — they form the oases wherever moisture exists, among the burning sands of Africa — they are found in caverns void of light, though generally blanched and feeble. The ocean teems with vegetation. The snow itself not only produces a red alga, discovered by Saussure in the frozen declivities of the Alps, found in abundance by the author crossing the Col de Bonhomme from Savoy to Piedmont, and by the polar navigators in the Arctic regions, but it affords shelter to the productions of those inhospitable climes, against the piercing winds that sweep over fields of everlasting ice. Those interesting mariners narrate, that under this cold defence plants spring up, dissolve the snow a few inches round, and the part above being again quickly frozen into a transparent sheet of ice, admits the sun's rays, which warm and cherish the plant in this natural hot-house, till the returning summer renders such protection unnecessary.

By far the greater part of the hundred and ten thousand known species of plants are indigenous in Equinoctial America. Europe contains about half the number; Asia, with its islands, somewhat less than Europe; New Holland, with the islands in the Pacific,

still less; and in Africa there are fewer vegetable productions than in any part of the globe of equal extent. Very few social plants, such as grasses and heaths that cover large tracts of land, are to be found between the tropics, except on the sea-coasts and elevated plains: some exceptions to this, however, are to be met with in the jungles of the Deccan, Khandish, &c. In the equatorial regions where the heat is always great, the distribution of plants depends upon the mean annual temperature; whereas in temperate zones, the distribution is regulated in some degree by the summer heat. Some plants require a gentle warmth of long continuance, others flourish most where the extremes of heat and cold are greater. The range of wheat is very great: it may be cultivated as far north as the 60th degree of latitude, but in the torrid zone it will seldom form an ear below an elevation of 4500 feet above the level of the sea, from exuberance of vegetation; nor will it ripen above the height of 10,800 feet, though much depends upon local circumstances. Colonel Sykes states that, in the Deccan, wheat thrives 1800 feet above the level of the sea. The best wines are produced between the 30th and 45th degrees of north latitude. With regard to the vegetable kingdom, elevation is equivalent to latitude, as far as temperature is concerned. In ascending the mountains of the torrid zone, the richness of the tropical vegetation diminishes with the height; a succession of plants similar, though not identical with those found in latitudes of corresponding mean temperature, takes place; the lofty forests by degrees lose their splendour, stunted shrubs succeed, till at last the progress of the lichen is checked by eternal snow. On the volcano of Teneriffe there are five successive zones, each producing a distinct race of plants. The first is the

region of vines, the next that of laurels; these are followed by the districts of pines, of mountain-broom, and of grass; the whole covering the declivity of the peak through an extent of 11,200 feet of perpendicular height.

Near the equator, the oak flourishes at the height of 9200 feet above the level of the sea; and on the lofty range of the Himalaya, the primula, the convallaria, and the veronica blossom, but not the primrose, the lily of the valley, or the veronica which adorn our meadows; for although the herbarium collected by Mr. Moorcroft, on his route from Neetee to Daba and Garlope in Chinese Tartary, at elevations as high or even higher than Mont Blanc, abounds in Alpine and European genera, the species are universally different, with the single exception of the rhodiola rosea, which is identical with the species that blooms in Scotland. It is not in this instance alone that similarity of climate obtains without identity of productions; throughout the whole globe, a certain analogy both of structure and appearance is frequently discovered between plants under corresponding circumstances, which are yet specifically different. It is even said, that a distance of 25° of latitude occasions a total change, not only of vegetable productions, but of organized beings. Certain it is, that each separate region both of land and water, from the frozen shores of the polar circles to the burning regions of the torrid zone, possesses a Flora of species peculiarly its own. The whole globe has been divided by botanical geographers into twenty-seven botanical districts, differing almost entirely in their specific vegetable productions; the limits of which are most decided when they are separated by a wide expanse of ocean, mountain-chains, sandy deserts, salt plains, or

internal seas. A considerable number of plants are common to the northern regions of Asia, Europe, and America, where the continents almost unite, but, in approaching the south, the Floras of these three great divisions of the globe differ more and more even in the same parallels of latitude, which shows that temperature alone is not the cause of the almost complete diversity of species that every where prevails. The Floras of China, Siberia, Tartary, of the European district including Central Europe and the coasts of the Mediterranean, and the Oriental region, comprising the countries round the Black and Caspian Seas, all differ in specific character. Only twenty-four species were found by MM. Bonpland and Humboldt in Equinoctial America identical with those of the Old World; and Mr. Brown not only found that a peculiar vegetation exists in New Holland, between the 33d and 35th parallels of south latitude, but that, at the eastern and western extremities of these parallels, not one species is common to both, and that certain genera also are almost entirely confined to these spots. The number of species common to Australia and Europe are only 166 out of 4100, and probably some of these have been conveyed thither by the colonists. This proportion exceeds what is observed in Southern Africa, and, from what has been already stated, the proportion of European species in Equinoctial America is still less.

Islands partake of the vegetation of the nearest continents, but when very remote from land their Floras are altogether peculiar. The Aleutian Islands, extending between Asia and America, partake of the vegetation of the northern parts of both these continents, and may have served as a channel of communication. In Madeira and Teneriffe, the plants of Portugal, Spain, the

Azores, and of the north coast of Africa are found, and the Canaries contain a great number of plants belonging to the African coast. But each of these islands possesses a Flora that exists nowhere else; and St Helena, standing alone in the midst of the Atlantic Ocean, out of sixty-one indigenous species, produces only two or three recognised as belonging to any other part of the world.

It appears from the investigations of M. De Humboldt, that between the tropics the monocotyledonous plants, such as grasses and palms, which have only one seed-lobe, are to the dicotyledonous tribe, which have two seed-lobes, like most of the European species, in the proportion of one to four; in the temperate zones they are as one to six; and in the Arctic regions, where mosses and lichens, which form the lowest order of the vegetable creation, abound, the proportion is as one to two. The annual monocotyledonous and dicotyledonous plants in the temperate zones amount to one sixth of the whole, omitting the Cryptogamia[1]; in the torrid zone, they scarcely form one twentieth, and in Lapland one thirtieth part. In approaching the equator, the ligneous exceed the number of herbaceous plants; in America, there are a hundred and twenty different species of forest trees, whereas in the same latitudes in Europe only thirty-four are to be found.

Similar laws appear to regulate the distribution of marine plants. M. Lamouroux has discovered that the groups of algæ, or marine plants, affect particular temperatures or zones of latitude, though some few genera prevail throughout the ocean. The polar Atlantic basin, to the 40th degree of north latitude, presents a well-defined vegetation. The West Indian seas, including the Gulf of

[1] Note 211

Mexico, the eastern coast of South America, the Indian Ocean and its gulfs, the shores of New Holland, and the neighbouring islands, have each their distinct species. The Mediterranean possesses a vegetation peculiar to itself, extending to the Black Sea; and the species of marine plants on the coasts of Syria and in the port of Alexandria differ almost entirely from those of Suez and the Red Sea, notwithstanding the proximity of their geographical situation. It is observed that shallow seas have a different set of plants from such as are deeper and colder; and, like terrestrial vegetation, the algæ are most numerous towards the equator, where the quantity must be prodigious, if we may judge from the gulf-weed, which certainly has its origin in the tropical seas, and is drifted, though not by the gulf stream, to higher latitudes, where it accumulates in such quantities, that the early Portuguese navigators, Columbus and Lerius, compared the sea to extensively inundated meadows, in which it actually impeded their ships and alarmed their sailors. M. De Humboldt, in his Personal Narrative, mentions, that the most extensive bank of sea-weed is in the northern Atlantic, a little west of the meridian of Fayal, one of the Azores, between the 25th and 36th degrees of latitude. Vessels returning to Europe from Monte Video, or from the Cape of Good Hope, cross this bank nearly at an equal distance from the Antilles and Canary Islands. The other bank occupies a smaller space, between the 22d and 26th degrees of north latitude, about eighty leagues west of the meridian of the Bahama Islands, and is generally traversed by vessels on their passage from the Caicos to the Bermuda Islands. These masses consist chiefly of one or two species of Sargassum, the most extensive genus of the order Fucoideæ.

Some of the sea-weeds grow to the enormous length of several hundred feet, and all are highly coloured, though many of them must grow in the deep caverns of the ocean, in total or almost total darkness; light, however, may not be the only principle on which the colour of vegetables depends, since M. De Humboldt met with green plants growing in complete darkness at the bottom of one of the mines at Freyberg.

It appears that in the dark and tranquil caves of the ocean, on the shores alternately covered and deserted by the restless waves, on the lofty mountain and extended plain, in the chilly regions of the north and in the genial warmth of the south, specific diversity is a general law of the vegetable kingdom, which cannot be accounted for by diversity of climate, and yet the similarity though not identity of species is such, under the same isothermal lines, that if the number of species belonging to one of the great families of plants be known in any part of the globe, the whole number of the phanerogamous or more perfect plants, and also the number of species composing the other vegetable families, may be estimated with considerable accuracy.

Various opinions have been formed on the original or primitive distribution of plants over the surface of the globe; but since botanical geography became a regular science, the phenomena observed have led to the conclusion that vegetable creation must have taken place in a number of distinctly different centres, each of which was the original seat of a certain number of peculiar species, which at first grew there and nowhere else. Heaths are exclusively confined to the Old World, and no indigenous rose tree has ever been discovered in the New; the whole southern hemisphere being destitute of that beautiful and fragrant plant. But this is still more

confirmed by multitudes of particular plants having an entirely local and insulated existence, growing spontaneously in some particular spot and in no other place, for example, the cedar of Lebanon, which grows indigenously on that mountain and in no other part of the world

The same laws obtain in the distribution of the animal creation. The zoophite[1], occupying the lowest place in animated nature, is widely scattered through the seas of the torrid zone, each species being confined to the district best fitted to its existence. Shell-fish decrease in size and beauty with their distance from the equator, and, as far as is known, each sea has its own kind, and every basin of the ocean is inhabited by its peculiar tribe of fish. Indeed, MM. Peron and Le Sueur assert, that among the many thousands of marine animals which they had examined, there is not a single animal of the southern regions which is not distinguishable by essential characters from the analogous species in the northern seas Reptiles are not exempt from the general law. The saurian[2] tribes of the four quarters of the globe differ in species; and although warm countries abound in venomous snakes, they are specifically different, and decrease both in the numbers and in the virulence of their poison with decrease of temperature. The dispersion of insects necessarily follows that of the vegetables which supply them with food; and in general it is observed, that each kind of plant is peopled by its peculiar inhabitants. Each species of bird has its particular haunt, notwithstanding the locomotive powers of the winged tribes The emu is confined to Australia, the condor never leaves the Andes, nor the great eagle the Alps, and although

[1] Note 212 [2] Note 213.

some birds are common to every country, they are few in number Quadrupeds are distributed in the same manner wherever man has not interfered Such as are indigenous in one continent are not the same with their congeners in another, and with the exception of some kinds of bats, no warm-blooded animal is indigenous in the Polynesian Archipelago, nor in any of the islands on the borders of the central part of the Pacific

In reviewing the infinite variety of organised beings that people the surface of the globe, nothing is more remarkable than the distinctions which characterise the different tribes of mankind, from the ebony skin of the torrid zone to the fair and ruddy complexion of Scandinavia, — a difference which existed in the earliest recorded times, since the African is represented in the sacred writings to have been as black as he is at the present day, and the most ancient Egyptian paintings confirm that truth, yet it appears from a comparison of the principal circumstances relating to the animal economy or physical character of the various tribes of mankind, that the different races are identical in species. Many attempts have been made to trace the various tribes back to a common origin, by collating the numerous languages which are, or have been, spoken. Some classes of these have few or no words in common, yet exhibit a remarkable analogy in the laws of their grammatical construction. The languages spoken by the native American nations afford examples of these, indeed, the refinement in the grammatical construction of the tongues of the American savages leads to the belief that they must originally have been spoken by a much more civilised class of mankind. Some tongues have little or no resemblance in structure, though they correspond extensively in their vocabularies, as in the

Syrian dialects In all of these cases it may be inferred, that the nations speaking the languages in question are descended from the same stock, but the probability of a common origin is much greater in the Indo-European nations, whose languages, such as the Sanscrit, Greek, Latin, German, &c., have an affinity both in structure and correspondence of vocables. In many tongues not the smallest resemblance can be traced, length of time, however, may have obliterated original identity The conclusion drawn from the whole investigation is, that although the distribution of organised beings does not follow the direction of the isothermal lines, temperature has a very great influence on their physical development. The heat of the air is so intimately connected with its electrical condition, that electricity must also affect the distribution of plants and animals over the face of the earth, the more so as it seems to have a great share in the functions of animal and vegetable life It is the sole cause of many atmospheric and terrestrial phenomena, and performs an important part in the economy of nature.

SECTION XXVII.

OF ORDINARY ELECTRICITY, GENERALLY CALLED ELECTRICITY OF TENSION.—METHODS OF EXCITING BODIES.—TRANSFERENCE.—ELECTRICS AND NON-ELECTRICS.—LAW OF ITS INTENSITY.—DISTRIBUTION.—TENSION.—ELECTRIC HEAT AND LIGHT.—ATMOSPHERIC ELECTRICITY.—ITS CAUSE.—ELECTRIC CLOUDS.—BACK STROKE.—VIOLENT EFFECTS OF LIGHTNING.—ITS VELOCITY.—PHOSPHORESCENCE.—AURORA.

ELECTRICITY is one of those imponderable agents pervading the earth and all substances, without affecting their volume or temperature, or even giving any visible sign of its existence when in a latent state, but when elicited, developing forces capable of producing the most sudden, violent, and destructive effects in some cases, while in others, their action, though less energetic, is of indefinite and uninterrupted continuance. These modifications of the electric force, incidentally depending upon the manner in which it is excited, present phenomena of great diversity, but yet so connected as to justify the conclusion that they originate in a common principle.

Electricity may be called into activity by mechanical power, by chemical action, by heat, and by magnetic influence. We are totally ignorant why it is roused from its neutral state by such means, or of the manner of its existence in bodies; whether it be a material agent, or merely a property of matter. As some hypothesis is necessary for explaining the phenomena observed, it is assumed to be a highly elastic fluid, capable

of moving with various degrees of facility through the pores or even the substance of matter. And as experience shows that bodies in one electric state attract and in another repel each other, the hypothesis of two kinds, called positive and negative electricity, is adopted. But whether there really be two different fluids, or that the mutual attraction and repulsion of bodies arise from the redundancy and defect of their electricities, is of no consequence, since all the phenomena can be explained on either hypothesis. As each electricity has its peculiar properties, the science may be divided into branches, of which the following notice is intended to convey some idea.

Substances in which the positive and negative electricities are combined, being in a neutral state, neither attract nor repel. There is a numerous class called electrics, in which the electric equilibrium is destroyed by friction: then the positive and negative electricities are called into action or separated; the positive is impelled in one direction, and the negative in another; those of the same kind repel, whereas those of different kinds attract each other. The attractive power is exactly equal to the repulsive force at equal distances, and when not opposed, they coalesce with great rapidity and violence, producing the electric flash, explosion, and shock: then equilibrium is restored, and the electricity remains latent till again called forth by a new exciting cause. One kind of electricity cannot be evolved without the evolution of an equal quantity of the opposite kind. Thus, when a glass rod is rubbed with a piece of silk, as much positive electricity is elicited in the glass as there is negative in the silk. The kind of electricity depends more upon the mechanical condition than on the nature of the surface, for

when two plates of glass, one polished and the other rough, are rubbed against each other, the polished surface acquires positive and the rough negative electricity. The manner in which friction is performed also alters the kind of electricity Equal lengths of black and white ribbon, applied longitudinally to one another, and drawn between the finger and thumb, so as to rub their surfaces together, become electric. When separated, the black ribbon is found to have acquired negative electricity, and the white positive: but if the whole length of the black ribbon be drawn across the breadth of the white, the black will be positively and the white negatively electric when separate Electricity may be transferred from one body to another in the same manner as heat is communicated, and, like it too, the body loses by the transmission. Although no substance is altogether impervious to the electric fluid, nor is there any that does not oppose some resistance to its passage, yet it moves with much more facility through a certain class of substances called conductors, such as metals, water, the human body, &c, than through atmospheric air, glass, silk, &c, which are therefore called non-conductors. The conducting power is affected both by temperature and moisture.

Bodies surrounded with non-conductors are said to be insulated, because, when charged, the electricity cannot escape When that is not the case, the electricity is conveyed to the earth, which is formed of conducting matter; consequently it is impossible to accumulate electricity in a conducting substance that is not insulated There are a great many substances called non-electrics, in which electricity is not sensibly developed by friction, unless they be insulated, probably because it is carried off by their conducting power

as soon as elicited. Metals, for example, which are said to be non-electrics, can be excited, but, being conductors, they cannot retain this state if in communication with the earth. It is probable that no bodies exist which are either perfect non-electrics or perfect non-conductors. But it is evident that electrics must be non-conductors to a certain degree, otherwise they could not retain their electric state.

It has been supposed that an insulated body remains at rest, because the tension of the electricity, or its pressure on the air which restrains it, is equal on all sides; but when a body in a similar state, and charged with the same kind of electricity, approaches it, that the mutual repulsion of the particles of the electric fluid diminishes the pressure of the fluid on the air on the adjacent sides of the two bodies, and increases it on their remote ends; consequently that equilibrium will be destroyed, and the bodies, yielding to the action of the preponderating force, will recede from or repel each other. When, on the contrary, they are charged with opposite electricities, it is alleged that the pressure upon the air on the adjacent sides will be increased by the mutual attraction of the particles of the electric fluid, and that on the further sides diminished; consequently that the force will urge the bodies towards one another, the motion in both cases corresponding to the forces producing it. An attempt has thus been made to attribute electrical attractions and repulsions to the mechanical pressure of the atmosphere. It is, however, more than doubtful whether these phenomena can be referred to that cause; but certain it is that, whatever the nature of these forces may be, they are not impeded in their action by the intervention of any substance whatever, provided it be not itself in an electric state.

A body charged with electricity, although perfectly insulated, so that all escape of electricity is precluded, tends to produce an electric state of the opposite kind in all bodies in its vicinity. Positive electricity tends to produce negative electricity in a body near it, and *vice versâ*, the effect being greater as the distance diminishes. This power which electricity possesses of causing an opposite electrical state in its vicinity is called induction When a body charged with either species of electricity is presented to a neutral one, its tendency, in consequence of the law of induction, is to disturb the electrical condition of the neutral body. The electrified body induces electricity contrary to its own in the adjacent part of the neutral one, and therefore an electrical state similar to its own in the remote part Hence the neutrality of the second body is destroyed by the action of the first, and the adjacent parts of the two, having now opposite electricities, will attract each other The attraction between electrified and unelectrified substances is therefore merely a consequence of their altered state, resulting directly from the law of induction, and not an original law. The effects of induction depend upon the facility with which the equilibrium of the neutral state of a body can be overcome, —a facility which is proportional to the conducting power of the body Consequently, the attraction exerted by an electrified substance upon another substance previously neutral will be much more energetic if the latter be a conductor than if it be a non-conductor.

The law of electrical attraction and repulsion has been determined by suspending a needle of gum-lac horizontally by a silk fibre, the needle carrying at one end a piece of electrified gold-leaf. A globe charged with the same, or with the opposite kind of electricity,

when presented to the gold-leaf, will repel or attract it, and will therefore cause the needle to vibrate more or less rapidly according to the distance of the globe. A comparison of the number of oscillations performed in a given time, at different distances, will determine the law of the variation of the electrical intensity, in the same manner that the force of gravitation is measured by the oscillations of the pendulum. Coulomb invented an instrument which balances the forces in question by the force of the torsion of a thread, which consequently measures their intensity. By this method he found that the intensity of the electrical attraction and repulsion varies inversely as the square of the distance. Since electricity can only be in equilibrio from the mutual repulsion of its particles, — which, according to these experiments, varies inversely as the square of the distance, — its distribution in different bodies depends upon the laws of mechanics, and therefore becomes a subject of analysis and calculation. The distribution of electricity has been so successfully determined by the analytical investigations of M. Poisson and Mr Ivory, that all the computed phenomena have been confirmed by observation.

It is found by direct experiment that a metallic globe or cylinder contains the same quantity of electricity when hollow that it does when solid. Thus, electricity is entirely confined to the surface of bodies, or, if it does penetrate their substance, the depth is inappreciable, so that the quantity bodies are capable of receiving does not follow the proportion of their bulk, but depends principally upon the extent of surface over which it is spread, so that the exterior may be positively or negatively electric, while the interior is in a state of perfect neutrality.

Electricity of either kind may be accumulated to a great extent in insulated bodies, and so long as it is quiescent it occasions no sensible change in their properties, though it is spread over their surfaces in indefinitely thin layers. When restrained by the non-conducting power of the atmosphere, the tension or pressure exerted by the electric fluid against the air which opposes its escape, is in the ratio compounded of the repulsive force of its own particles at the surface of the stratum of the fluid, and of the thickness of that stratum. But as one of these elements is always proportional to the other, the total pressure on every point must be proportional to the square of the thickness. If this pressure be less than the coercive force of the air, the electricity is retained; but the instant it exceeds that force in any one point, the electricity escapes, which it will do when the air is attenuated, or becomes saturated with moisture.

The power of retaining electricity depends also upon the shape of the body. It is most easily retained by a sphere, next to that by a spheroid, but it readily escapes from a point; and a pointed object receives it with most facility. It appears from analysis, that electricity when in equilibrio, spreads itself in a thin stratum over the surface of a sphere, in consequence of the repulsion of its particles, which force is directed from the centre to the surface. In an oblong spheroid, the intensity or thickness of the stratum of electricity at the extremities of the two axes, is exactly in the proportion of the axes themselves; hence, when the ellipsoid is much elongated, the electricity becomes very feeble at the equator and powerful at the poles. A still greater difference in the intensities takes place in bodies of a cylindrical or prismatic form, and the

more so in proportion as their length exceeds their breadth; therefore the electrical intensity is very powerful at a point, where nearly the whole electricity in the body is concentrated.

A perfect conductor is not mechanically affected by the passage of electricity, if it be of sufficient size to carry off the whole, but it is shivered to pieces in an instant, if it be too small to carry off the charge this also happens to a bad conductor In that case the physical change is generally a separation of the particles, though it may occasionally be attributed to chemical action, or expansion from the heat evolved during the passage of the fluid, but all these effects are in proportion to the obstacles opposed to the freedom of its course. The heat produced by the electric shock is intense, fusing metals, and even volatilising substances, though it is only accompanied by light when the fluid is obstructed in its passage. Electrical light is perfectly similar to solar light in its composition, according to M. Biot, it arises from the condensation of the air during the rapid motion of the electricity, and varies both in intensity and colour with the density of the atmosphere. When the air is dense, it is white and brilliant, whereas, in rarefied air, it is diffuse and of a reddish colour. The experiments of Sir Humphry Davy, however, seem to be at variance with this opinion. He passed the electric spark through a vacuum over mercury, which from green became successively sea-green, blue, and purple, on admitting different quantities of air. When the vacuum was made over a fusible alloy of tin and bismuth, the spark was yellowish and extremely pale. Sir Humphry thence concluded, that electrical light principally depends upon some properties belonging to the pon-

derable matter through which it passes, and that space is capable of exhibiting luminous appearances, though it does not contain an appreciable quantity of this matter. He thought it not improbable that the superficial particles of bodies which form vapour, when detached by the repulsive power of heat, might be equally separated by the electric forces, and produce luminous appearances in vacuo, by the destruction of their opposite electric states. Pressure is a source of electricity which M. Becquerel has found to be common to all bodies, but it is necessary to insulate them to prevent its escape. When two substances of any kind whatever are insulated and pressed together, they assume different electric states, but they only show contrary electricities when one of them is a good conductor. When both are good conductors, they must be separated with extreme rapidity, to prevent the two fluids from reuniting. When the separation is very sudden, the tension of the two electricities may be great enough to produce light. M. Becquerel attributes the light produced by the collision of icebergs to this cause. Iceland spar is made electric by the smallest pressure between the finger and thumb, and retains it for a long time. All these circumstances are modified by the temperature of the substances, the state of their surfaces, and that of the atmosphere. Several crystalline substances become electric when heated, especially tourmaline, one end of which acquires positive, and the other negative electricity, while the intermediate part is neutral. If a tourmaline be broken through the middle, each fragment is found to possess positive electricity at one end, and negative at the other, like the entire crystal. Electricity is evolved by bodies passing from a liquid to a solid state; also by chemical action, during

the production and condensation of vapour, which is consequently a great source of atmospheric electricity. In short, it may be stated generally, that when any cause whatever, such as friction, pressure, heat, fracture, chemical action, &c. tends to destroy molecular attraction, there is a development of electricity. If, however, the molecules be not immediately separated, there will be an instantaneous reunion of the two fluids.

The atmosphere, when clear, is almost always positively electric. Its electricity is stronger in winter than in summer, during the day than in the night. The intensity increases for two or three hours from the time of sunrise, comes to a maximum between seven and eight, then decreases towards the middle of the day, arrives at its minimum between one and two, and again augments as the sun declines, till about the time of sunset, after which it diminishes, and continues feeble during the night. Atmospheric electricity arises partly from an evolution of the electric fluid during the evaporation that is so abundant at the surface of the earth, though not under all circumstances. M. Pouillet has recently come to the conclusion, that simple evaporation never produces electricity, unless accompanied by chemical action, but that electricity is always disengaged when the water holds a salt or some other substance in solution. He found, when water contains lime, chalk, or any solid alkali, that the vapour arising from it is negatively electric, and when the body held in solution is either a gas, acid, or some of the salts, that the vapour given out is positively electric. The ocean must therefore afford a great supply of positive electricity to the atmosphere, but as M. Becquerel has shown that electricity of one kind or other is developed, whenever the molecules of bodies are deranged from

their natural positions of equilibrium by any cause whatever, the chemical changes on the surface of the globe must occasion many variations in the electrical state of the atmosphere. M. Pouillet affirms, that plants afford abundance of positive electricity during their growth, and that more positive electricity is disengaged, in the course of one day, from a surface of a hundred square yards in full vegetation, than would charge a powerful battery; but it is difficult to reconcile this with the fact of the atmosphere being more charged with electricity during the winter than in summer. M. De la Rive has come to results in his experiments so discordant with those of M. Pouillet, that he finds it impossible to regard vegetation as the source of the positive electricity of the air, and agrees with M. Becquerel, in attributing it to the more general cause of the unequal distribution of heat in the atmosphere. Clouds probably owe their existence, or at least their form, to electricity, for they consist of hollow vesicles of vapour coated with it. As the electricity is either entirely positive or negative, the vesicles repel each other, which prevents them from uniting and falling down in rain. The friction of the surfaces of two strata of air moving in different directions, probably developes electricity; and if the strata be of different temperatures, a portion of the vapour they always contain will be deposited; the electricity evolved will be taken up by the vapour, and cause it to assume the vesicular state constituting a cloud. A vast deal of electricity may be accumulated in this manner, which may be either positive or negative, and should two clouds charged with opposite kinds, approach within a certain distance, the thickness of the coating of electricity will increase on the two sides of

the clouds that are nearest to one another, and when the accumulation becomes so great as to overcome the coercive pressure of the atmosphere, a discharge takes place, which occasions a flash of lightning The actual quantity of electricity in any one part of a cloud is extremely small The intensity of the flash arises from the very great extent of surface occupied by the electricity, so that the clouds may be compared to enormous Leyden jars thinly coated with the electric fluid, which only acquires its intensity by its instantaneous condensation. The rapid and irregular motions of thunder clouds are, in all probability, more owing to strong electrical attractions and repulsions among themselves than to currents of air, though both are no doubt concerned in these hostile movements

An interchange frequently takes place between the clouds and the earth, but so rapid is the motion of lightning, that it is difficult to ascertain when it goes from the clouds to the earth, or shoots upwards from the earth to the clouds, though there can be no doubt that it does both M. Gay-Lussac has ascertained that a flash of lightning sometimes darts more than three miles at once in a straight line.

A person may be killed by lightning, although the explosion takes place at the distance of twenty miles, by what is called the back stroke Suppose that the two extremities of a cloud highly charged with electricity hang down towards the earth, they will repel the electricity from the earth's surface, if it be of the same kind with their own, and will attract the other kind, and if a discharge should suddenly take place at one end of the cloud, the equilibrium will instantly be restored by a flash at that point of the earth which is under the other. Though the back stroke is often sufficiently

powerful to destroy life, it is never so terrible in its effects as the direct shock, which is frequently of inconceivable intensity. Instances have occurred in which large masses of iron and stone, and even many feet of a stone wall, have been conveyed to a considerable distance by a stroke of lightning. Rocks and the tops of mountains often bear the marks of fusion from its action, and occasionally vitreous tubes, descending many feet into banks of sand, mark the path of the electric fluid. Some years ago Dr. Fiedler exhibited several of these fulgorites in London, of considerable length, which had been dug out of the sandy plains of Silesia and Eastern Prussia. One found at Paderborn was forty feet long. Their ramifications generally terminate in pools or springs of water below the sand, which are supposed to determine the course of the electric fluid. No doubt the soil and substrata must influence its direction, since it is found by experience, that places which have been struck by lightning are often struck again. A school-house in Lammer-muir in East Lothian, has been struck three different times.

The atmosphere, at all times positively electric, becomes intensely so on the approach of rain, snow, wind, hail, or sleet, but it afterwards varies, and the transitions are very rapid on the approach of a thunder-storm. An isolated conductor then gives out such quantities of sparks that it is dangerous to approach it, as was fatally experienced by Professor Richman, at Petersburg, who was struck dead by a globe of fire from the extremity of a conductor, while making experiments on atmospheric electricity. There is no instance on record of an electric cloud being dispelled by a conducting rod silently withdrawing the electric fluid; yet it may mitigate the stroke, or render

it harmless if it should come. Sir John Leslie thought that the efficacy of conductors depends upon the rapidity with which they transmit the electric energy, and as copper is found to transmit the fluid twenty times faster than iron, and as iron conducts it four hundred millions of times more rapidly than water, which conveys it several thousand times faster than dry stone, copper conductors afford the best protection, especially if they expose a broad surface, since the electric fluid is conveyed chiefly along the exterior of bodies The object of a conductor being to carry off the electricity in case of a stroke, and not to invite an enemy, it ought to project very little, if at all, above the building

The velocity of electricity is so great, that the most rapid motion which can be produced by art, appears to be actual rest when compared with it A wheel revolving with celerity sufficient to render its spokes invisible, when illuminated by a flash of lightning, is seen for an instant with all its spokes distinct, as if it were in a state of absolute repose Because, however rapid the rotation may be, the light has come and already ceased before the wheel has had time to turn through a sensible space. This beautiful experiment is due to Professor Wheatstone, as well as the following variation of it, which is not less striking.—Since a sun-beam consists of a mixture of blue, yellow, and red light, if a circular piece of pasteboard be divided into three sectors, one of which is painted blue, another yellow, and the third red, it will appear to be white when revolving quickly, because of the rapidity with which the impressions of the colours succeed each other on the retina But the instant it is illuminated by an electric spark, it seems to stand still, and each colour is as distinct as if it were at rest.—This transcendent speed of the electric

fluid has been ingeniously measured by Professor Wheatstone, and although his experiments are not far enough advanced to enable him to state its absolute celerity, he has ascertained that it much surpasses the velocity of light

An insulated copper wire, half a mile long, is so disposed that its centre and two extremities terminate in the horizontal diameter of a small disc, or circular plate of metal, fixed on the wall of a darkened room. When an electric spark is sent through the wire, it is seen at the three points apparently at the same instant. At the distance of about ten feet, a small revolving mirror is placed so as to reflect these three sparks during its revolution From the extreme velocity of the electricity, it is clear, that if the three sparks be simultaneous, they will be reflected, and will vanish before the mirror has sensibly changed its position, however rapid its rotation may be, and they will be seen in a straight line But if the three sparks be not simultaneously transmitted to the disc — if one, for example, be later than the other two — the mirror will have time to revolve through an indefinitely small arc in the interval between the reflection of the two sparks and the single one However, the only indication of this small motion of the mirror will be, that the single spark will not be reflected in the same straight line with the other two, but a little above or below it, for the reflection of all three will still be apparently simultaneous, the time intervening being much too short to be appreciated.

Since the distance of the revolving mirror from the disc, and the number of revolutions which it makes in a second, are known, the deviation of the reflection of the single spark from the reflection of the other two can be computed, and consequently the time elapsed between

their consecutive reflections can be ascertained. And as the length of that part of the wire through which the electricity has passed is given, its velocity may be found.

Since the number of pulses in a second requisite to produce a musical note of any pitch is known, the number of revolutions accomplished by the mirror in a given time is determined from the musical note produced by a tooth or peg in its axis of rotation striking against a card, or from the notes of a siren attached to the axis. It was thus that Mr Wheatstone found the velocity of the mirror to be such, that an angular deviation of 25° in the appearance of the two sparks would indicate an interval not exceeding the millionth of a second. The use of sound as a measure of velocity is a happy illustration of the connexion of the physical sciences.

When the atmosphere is highly charged with electricity, it not unfrequently happens that electric light in the form of a star is seen on the topmasts and yard-arms of ships. In 1831, the French officers at Algiers were surprised to see brushes of light on the heads of their comrades, and at the points of their fingers, when they held up their hands. This phenomenon was well known to the ancients, who reckoned it a lucky omen.

Many substances in decaying emit light, which is attributed to electricity, such as fish and rotten wood. Oyster shells, and a variety of minerals, become phosphorescent at certain temperatures, or when exposed to electric shocks. The minerals possessing this property are generally coloured or imperfectly transparent; and though the colour of this light varies in different substances, it has no fixed relation to the colour of the mineral. An intense heat entirely destroys this property, and the phosphorescent light developed by heat

has no connection with light produced by friction, for Sir David Brewster observed, that bodies deprived of the faculty of emitting the one are still capable of giving out the other. Among the bodies which generally become phosphorescent when exposed to heat, there are some specimens which do not possess this property, wherefore phosphorescence cannot be regarded as an essential character of the minerals possessing it. Multitudes of fish are endowed with the power of emitting light at pleasure, no doubt to enable them to pursue their prey at depths where the sunbeams cannot penetrate Flashes of light are frequently seen to dart along a shoal of herrings or pilchards, and the Medusa tribes are noted for their phosphorescent brilliancy, many of which are extremely small, and so numerous as to make the wake of a vessel look like a stream of silver Nevertheless, the luminous appearance which is frequently observed in the sea during the summer months cannot always be attributed to marine animalculæ, as the following narrative will show:—

Captain Bonnycastle, coming up the Gulf of St. Lawrence on the 7th of September, 1826, was roused by the mate of the vessel in great alarm from an unusual appearance. It was a starlight night, when suddenly the sky became overcast in the direction of the high land of Cornwallis country, and an instantaneous and intensely vivid light, resembling the aurora, shot out of the hitherto gloomy and dark sea on the lee bow, which was so brilliant that it lighted every thing distinctly even to the mast-head. The light spread over the whole sea between the two shores, and the waves, which before had been tranquil, now began to be agitated. Captain Bonnycastle describes the scene as that of a blazing sheet of awful and most brilliant

light. A long and vivid line of light, superior in brightness to the parts of the sea not immediately near the vessel, showed the base of the high, frowning, and dark land abreast, the sky became lowering and more intensely obscure. Long tortuous lines of light showed immense numbers of very large fish darting about as if in consternation. The spritsail-yard and mizen-boom were lighted by the reflection, as if gas lights had been burning directly below them, and until just before day-break, at four o'clock, the most minute objects were distinctly visible. Day broke very slowly, and the sun rose of a fiery and threatening aspect Rain followed. Captain Bonnycastle caused a bucket of this fiery water to be drawn up; it was one mass of light when stirred by the hand, and not in sparks as usual, but in actual coruscations. A portion of the water preserved its luminosity for seven nights. On the third night, the scintillations of the sea reappeared, this evening the sun went down very singularly, exhibiting in its descent a double sun, and when only a few degrees high, its spherical figure changed into that of a long cylinder, which reached the horizon In the night the sea became nearly as luminous as before, but on the fifth night the appearance entirely ceased. Captain Bonnycastle does not think it proceeded from animalculæ, but imagines it might be some compound of phosphorus, suddenly evolved and disposed over the surface of the sea; perhaps from the exuviæ or secretions of fish connected with the oceanic salts, muriate of soda, and sulphate of magnesia.

The aurora borealis is decidedly an electrical phenomenon, which takes place in the highest regions of the atmosphere, since it is visible at the same time from places very far distant from each other It is somehow

connected with the magnetic poles of the earth, but it has never been seen so far north as the pole of the earth's rotation, nor does it extend to low latitudes It generally appears in the form of a luminous arch, stretching more or less from east to west, but never from north to south, across the arch the coruscations are rapid, vivid, and of various colours. A similar phenomenon occurs in the high latitudes of the southern hemisphere. Dr. Faraday conjectures that the electric equilibrium of the earth is restored by the aurora conveying the electricity from the poles to the equator.

SECTION XXVIII.

VOLTAIC ELECTRICITY.—THE VOLTAIC BATTERY.—INTENSITY.—QUANTITY.—COMPARISON OF THE ELECTRICITY OF TENSION WITH ELECTRICITY IN MOTION.—LUMINOUS EFFECTS.—DECOMPOSITION OF WATER.—FORMATION OF CRYSTALS BY VOLTAIC ELECTRICITY.—ELECTRICAL FISH.

Voltaic electricity is of that peculiar kind which is elicited by the force of chemical action. It is connected with one of the most brilliant periods of British science, from the splendid discoveries to which it led Sir Humphry Davy; and has acquired additional interest since the discovery of the reciprocal action of Voltaic and magnetic currents, which has proved that magnetism is only an effect of electricity, and has no existence as a distinct or separate principle. Consequently Voltaic electricity, as immediately connected with the theory of the earth and planets, forms a part of the physical account of their nature.

In 1790, while Galvani, Professor of Anatomy in Bologna, was making experiments on electricity, he was surprised to see convulsive motions in the limbs of a dead frog accidentally lying near the machine during an electrical discharge. Though a similar action had been noticed long before his time, he was so much struck with this singular phenomenon, that he examined all the circumstances carefully, and at length found that convulsions take place when the nerve and muscle of a frog are connected by a metallic conductor. This excited the attention of all Europe, and it was not long before Professor Volta, of Pavia, showed

that the mere contact of different bodies is sufficient to disturb electrical equilibrium, and that a current of electricity flows in one direction through a circuit of three conducting substances. From this he was led, by acute reasoning and experiment, to the construction of the Voltaic pile, which, in its early form, consisted of alternate discs of zinc and copper, separated by pieces of wet cloth, the extremities being connected by wires. This simple apparatus, perhaps the most wonderful instrument that has been invented by the ingenuity of man, by divesting electricity of its sudden and uncontrollable violence, and giving in a continued stream a greater quantity at a diminished intensity, has exhibited that fluid under a new and manageable form, possessing powers the most astonishing and unexpected. As the Voltaic battery has become one of the most important engines of physical research, some account of its present condition may not be out of place.

The disturbance of electric equilibrium, and a development of electricity, invariably accompanies the chemical action of a fluid on metallic substances, and is most plentiful when that action occasions oxidation. Metals vary in the quantity of electricity afforded by their combination with oxygen. But the greatest abundance is developed by the oxidation of zinc by weak sulphuric acid. And in conformity with the law that one kind of electricity cannot be evolved without an equal quantity of the other being brought into activity, it is found that the acid is positively, and the zinc negatively electric. It has not yet been ascertained why equilibrium is not restored by the contact of these two substances, which are both conductors, and in opposite electrical states. However, the electrical

and chemical changes are so connected, that unless equilibrium be restored, the action of the acid will go on languidly, or stop as soon as a certain quantity of electricity is accumulated in it. Equilibrium, nevertheless, will be restored, and the action of the acid will be continuous, if a plate of copper be placed in contact with the zinc, both being partly immersed in the fluid, for the copper, not being acted upon by the acid, will serve as a conductor to convey the positive electricity from the acid to the zinc, and will at every instant restore the equilibrium, and then the oxidation of the zinc will go on rapidly. Thus, three substances are concerned in forming a voltaic circuit, but it is indispensable that one of them should be a fluid The electricity so obtained will be very feeble, but it may be augmented by increasing the number of plates. In the common voltaic battery, the electricity which the fluid has acquired from the first plate of zinc exposed to its action, is taken up by the copper plate belonging to the second pair, and transferred to the second zinc plate, with which it is connected The second plate of zinc having thus acquired a larger portion of electricity than its natural share, communicates a larger quantity to the fluid in the second cell This increased quantity is again transferred to the next pair of plates, and thus every succeeding alternation is productive of a further increase in the quantity of the electricity developed. This action, however, would stop unless a vent were given to the accumulated electricity, by establishing a communication between the positive and negative poles of the battery, by means of wires attached to the extreme plate at each end. When the wires are brought into contact, the voltaic circuit is completed, the electricities

meet and neutralize each other, producing the shock and other electrical phenomena, and then the electric current continues to flow uninterruptedly in the circuit, as long as the chemical action lasts. The stream of positive electricity flows from the zinc to the copper, but, as the battery ends in a zinc plate which communicates with the wire, the zinc end becomes the positive, and the copper the negative, poles of a compound battery, which is exactly the reverse of what obtains in a single circuit

Galvanic or voltaic, like common electricity, may either be considered to consist of two fluids passing in opposite directions through the circuit, the positive stream coming from the zinc, and the negative from the copper end of the battery, or, if the hypothesis of one fluid be adopted, the zinc end of the battery may be supposed to have an excess of electricity, and the copper end a deficiency

Voltaic electricity is distinguished by two marked characters Its intensity increases with the number of plates — its quantity with the extent of their surfaces. The most intense concentration of force is displayed by a numerous series of large plates, light and heat are copiously evolved, and chemical decomposition is accomplished with extraordinary energy; whereas the electricity from one pair of plates, whatever their size may be, is so feeble that it gives no sign either of attraction or repulsion, and, even with a battery consisting of a very great number of plates, it is difficult to render the mutual attraction of its two wires sensible, though of opposite electricities.

The action of voltaic electricity differs materially from that of the ordinary kind. When a quantity of common electricity is accumulated, the restoration of

equilibrium is attended by an instantaneous violent explosion, accompanied by the development of light, heat, and sound The concentrated power of the fluid forces its way through every obstacle, disrupting and destroying the cohesion of the particles of the bodies through which it passes, and occasionally increasing its destructive effects by the conversion of fluids into steam from the intensity of the momentary heat, as when trees are torn to pieces by a stroke of lightning Even the vivid light which marks the path of the electric fluid is probably owing in part to the sudden compression of the air and other particles of matter during the rapidity of its passage, or to the violent and abrupt reunion of the two fluids But the instant equilibrium is restored by this energetic action the whole is at an end On the contrary, when an accumulation takes place in a voltaic battery, equilibrium is restored the moment the circuit is completed But so far is the electric stream from being exhausted, that it continues to flow silently and invisibly in an uninterrupted current supplied by a perpetual reproduction. And although its action on bodies is neither so sudden nor so intense as that of common electricity, yet it acquires such power from constant accumulation and continued action, that it ultimately surpasses the energy of the other The two kinds of electricity differ in no circumstance more than in the development of heat Instead of a momentary evolution, which seems to arise from a forcible compression of the particles of matter during the passage of the common electric fluid, the circulation of the voltaic electricity is accompanied by a continued development of heat, lasting as long as the circuit is complete, without producing either light or sound, and this appears to be its immediate direct

effect, independent of mechanical action. Its intensity is greater than that of any heat that can be obtained by artificial means, so that it fuses substances which resist the action of the most powerful furnaces. The temperature of every part of a voltaic battery itself is raised during its activity

When the battery is powerful, the luminous effects of voltaic electricity are very brilliant. But considerable intensity is requisite to enable the electricity to force its way through the air on bringing the wires together from the opposite poles Its transit is accompanied by light, and in consequence of the continuous supply of the fluid, sparks occur every time the contact of the wires is either broken or renewed. The most splendid artificial light known is produced by fixing pencils of charcoal at the extremities of the wires, and bringing them into contact This light is the more remarkable, as it appears to be independent of combustion, since the charcoal suffers no change, and likewise because it is equally vivid in such gases as do not contain oxygen. Though nearly as bright as solar light, it differs from it in possessing some of those rays of which the sunbeams are deficient, according to the experimens of M. Fraunhofer. Notwithstanding, M Arago is inclined to attribute the intense light and heat of the sun to electric action.

Voltaic electricity is a powerful agent in chemical analysis When transmitted through conducting fluids it separates them into their constituent parts, which it conveys in an invisible state through a considerable space or quantity of liquid to the poles, where they come into evidence Numerous instances might be given, but the decomposition of water is perhaps the most simple and elegant. Suppose a glass tube filled with very

pure water, and corked at both ends, if one of the wires of an active voltaic battery be made to pass through one cork and the other through the other cork, into the water, so that the extremities of the two wires shall be opposite and about a quarter of an inch asunder, chemical action will immediately take place, and gas will continue to rise from the extremities of both wires till the water has vanished. If an electric spark be then sent through the tube the water will reappear By arranging the experiment so as to have the gas given out by each wire separately, it is found that water consists of two volumes of hydrogen and one of oxygen The hydrogen is given out at the positive wire of the battery, and the oxygen at the negative Electro-chemical decomposition has generally been attributed to the attraction of the poles of the electrical machine and voltaic battery, whereas Dr Faraday has now accomplished decomposition through air and water without making use of poles, or at least without using metallic terminations commonly called poles. He, therefore, concludes that electro-chemical decomposition is not to be referred to the attractions and repulsions of the poles. He considers it to be the result of an internal corpuscular action excited in the direction of the electric current, and that it is due to a force either superadded to, or giving a direction to the ordinary chemical affinity of the body undergoing decomposition For example, in the decomposition of water, the stream of electricity issuing from the negative pole of the battery, as from a vent, gives the particles of hydrogen which it meets with a disposition to go to the positive pole, whereas the stream of positive electricity coming through the positive pole gives the particles of oxygen which it finds in its path a tendency to go to the negative wire.

The oxides are also decomposed: the oxygen appears at the positive pole, and the metal at the negative. The decomposition of the alkalies and earths by Sir Humphry Davy formed a remarkable era in the history of science. Soda, potash, lime, magnesia, and other substances heretofore considered to be simple bodies incapable of decomposition, were resolved by electric agency into their constituent parts, and proved to be metallic oxides, by that illustrious philosopher. All chemical changes produced by the electric fluid are accomplished on the same principle, and it appears that, in general, combustible substances, metals, and alkalies go to the negative wire, while acids and oxygen are evolved at the positive. The transfer of these substances to the poles is not the least wonderful effect of the voltaic battery. Though the poles be at a considerable distance from one another, nay, even in separate vessels, if a communication be only established by a quantity of wet thread, as the decomposition proceeds the component parts pass through the thread in an invisible state, and arrange themselves at their respective poles. The powerful efficacy of voltaic electricity in chemical decomposition arises from the continuance of its action, and its agency appears to be most exerted on fluids and substances which, by conveying the electricity partially and imperfectly, impede its progress. But it is now proved to be as efficacious in the composition as in the decomposition or analysis of bodies.

It had been observed that, when metallic solutions are subjected to galvanic action, a deposition of metal, generally in the form of minute crystals, takes place on the negative wire. By extending this principle, and employing a very feeble voltaic action, M. Becquerel has succeeded in forming crystals of a great proportion

of the mineral substances, precisely similar to those produced by nature The electric state of metallic veins makes it possible that many natural crystals may have taken their form from the action of electricity bringing their ultimate particles, when in solution, within the narrow sphere of molecular attraction already mentioned as the great agent in the formation of solids Both light and motion favour crystallisation. Crystals which form in different liquids are generally more abundant on the side of the jar exposed to the light, and it is well known that still water, cooled below 32°, starts into crystals of ice the instant it is agitated. Light and motion are intimately connected with electricity, which may therefore have some influence on the laws of aggregation, this is the more likely, as a feeble action is alone necessary, provided it be continued for a sufficient time Crystals formed rapidly are generally imperfect and soft, and M. Becquerel found that even years of constant voltaic action were necessary for the crystallisation of some of the hard substances If this law be general, how many ages may be required for the formation of a diamond!

Common electricity, on account of its high tension, passes through water and other liquids, as soon as it is formed, whatever the length of its course may be. Voltaic electricity, on the contrary, is weakened by the distance it has to traverse Pure water is a bad conductor, but ice absolutely stops a current of voltaic electricity altogether, whatever be the power of the battery, although common electricity has sufficient tension to overcome its resistance Dr Faraday has discovered, that this property is not peculiar to water, that, with a few exceptions, bodies which do not conduct electricity when solid, acquire that property and are

immediately decomposed when they become fluid, and, in general, that decomposition takes place as soon as the solution acquires the capacity of conduction, which has led him to suspect that the power of conduction may be only a consequence of decomposition.

Heat increases the conducting power of some substances for voltaic electricity, and of the gases for both kinds. Dr Faraday has given a new proof of the connection between heat and electricity, by showing that, in general, when a solid which is not a metal becomes fluid, it almost entirely loses its power of conducting heat, while it acquires a capacity for conducting electricity in a high degree.

The galvanic fluid affects all the senses. Nothing can be more disagreeable than the shock, which may even be fatal if the battery be very powerful. A bright flash of light is perceived with the eyes shut, when one of the wires touches the face and the other the hand. By touching the ear with one wire and holding the other, strange noises are heard, and an acid taste is perceived when the positive wire is applied to the tip of the tongue and the negative wire touches some other part of it. By reversing the poles the taste becomes alkaline. It renders the pale light of the glowworm more intense. Dead animals are roused by it, as if they started again into life, and it may ultimately prove to be the cause of muscular action in the living.

Several fish possess the faculty of producing electrical effects. The most remarkable are the gymnotus electricus, found in South America, and the torpedo, a species of ray, frequent in the Mediterranean. The electrical action of the torpedo depends upon an apparatus perfectly analogous to the voltaic pile, which the animal has the power of charging at will, consisting

of membranous columns filled throughout with laminæ, separated from one another by a fluid. The absolute quantity of electricity brought into circulation by the torpedo is so great, that it effects the decomposition of water, has power sufficient to make magnets, and gives very severe shocks. It is identical in kind with that of the galvanic battery, the electricity of the under surface of the fish being the same with the negative pole, and that in the upper surface the same with the positive pole. Its manner of action is, however, somewhat different, for, although the evolution of the electricity is continued for a sensible time, it is interrupted, being communicated by a succession of discharges.

SECTION XXIX

TERRESTRIAL MAGNETISM. — MAGNETIC MERIDIANS. — VARIATION OF THE COMPASS. — LINES OF NO VARIATION. — MAGNETIC POLES. — THEIR NUMBER AND POSITION. — DIURNAL AND NOCTURNAL VARIATIONS. — THE DIP. — THE MAGNETIC EQUATOR. — ITS POSITION. — VARIATION IN THE DIP. — CAUSE OF MAGNETIC CHANGES UNKNOWN. — ORIGIN OF THE MARINER'S COMPASS. — NATURAL MAGNETS. — ARTIFICIAL MAGNETS. — POLARITY. — INDUCTION. — INTENSITY. — HYPOTHESIS OF TWO MAGNETIC FLUIDS. — DISTRIBUTION OF THE MAGNETIC FLUID. — ANALOGY BETWEEN MAGNETISM AND ELECTRICITY.

In order to explain the other methods of exciting electricity, and the recent discoveries that have been made in that science, it is necessary to be acquainted with the general theory of magnetism, and also with the magnetism of the earth, the director of the mariner's compass, his guide through the ocean. Its influence extends over every part of the earth's surface, but its action on the magnetic needle determines the poles of this great magnet, which by no means coincide with the poles of the earth's rotation. In consequence of their attraction and repulsion, a needle freely suspended, whether it be magnetic or not, only remains in equilibrio when in the magnetic meridian, that is, in the plane which passes through the north and south magnetic poles. There are places where the magnetic meridian coincides with the terrestrial meridian. In these a magnetic needle freely suspended points to the true north; but, if it be carried successively to different places on the earth's surface, its direction will deviate sometimes to the east and sometimes to the west of

north. Lines drawn on the globe, through all the places where the needle points due north and south, are called lines of no variation, and they are extremely complicated The direction of the needle is not even constant in the same place, but changes in a few years according to a law not yet determined. In 1657, the line of no variation passed through London, from that time it has moved slowly, but irregularly, westward, and is now in North America In the year 1819, Sir Edward Parry, in his voyage to discover the north-west passage round America, sailed near the magnetic pole, and in 1824, Captain Lyon, on an expedition for the same purpose, found that the magnetic pole was then situate in 63° 26′ 51″ north latitude, and in 80° 51′ 25″ west longitude. It appears from later researches, that the law of terrestrial magnetism is of considerable complexity, and the existence of more than one magnetic pole in either hemisphere has been rendered highly probable That there is one in Siberia seems to be decided by the recent observations of M. Hansteen: it is in longitude 102° east of Greenwich, and a little to the north of the 60th degree of latitude so that, by these data, the two magnetic poles in the northern hemisphere are about 180° distant from each other Captain Ross places the American magnetic pole in 70° 14′ north latitude, and 96° 40′ west longitude.

The needle is also subject to diurnal variations In our latitudes it moves slowly westward during the forenoon, and returns to its mean position about ten in the evening, it then deviates to the eastward, and again returns to its mean position about ten in the morning. These changes seem to be intimately connected with the motion of the sun with regard to the magnetic meridian. M. Kupffer, of Casan, ascertained, in the year

1831, that there is a nightly, as well as a diurnal variation, depending, in his opinion, upon a variation in the magnetic equator.

A magnetic needle, suspended so as to be moveable only in the vertical plane, dips, or becomes more and more inclined to the horizon the nearer it is brought to the magnetic pole, and there becomes vertical. Captain Lyon found that the dip in the latitude and longitude mentioned, very near the magnetic pole, was 86° 32', and Captain Sabine determined it to be 69° 38' at Woolwich in 1830. According to Captain Sabine, it appears to have been decreasing for the last fifty years, at the rate of three minutes annually.

In some places the dipping needle is horizontal. A line passing through all these points is called the magnetic equator. The needle assumes every degree of inclination between the magnetic equator and the magnetic poles. The magnetic equator does not coincide with the terrestrial equator; it appears to be an irregular curve passing round the earth, and inclined to the earth's equator at an angle of about 12°, and crossing it in several points, the position of which seem still to be uncertain. According to some accounts, that curve cuts the equator in three points, whereas Captain Duperrey, who crossed it repeatedly during his voyage of discovery, affirms that, from his own observations, combined with those of M. Jules de Blosville and Captain Sabine, it crosses the terrestrial equator in only two points, diametrically opposite to one another, and not far from the meridian of Paris. One of these nodes he places in the Atlantic, the other in the Pacific. He finds that the magnetic equator deviates but little from the terrestrial equator in that part of the South Sea where there are only a few scattered islands; that

as the islands become more frequent the deviation increases, and arrives at a maximum, both to the north and south, in traversing the African and American continents, and that the symmetry of the northern and southern segments of this curve is much greater than was imagined

The variation in the dip arises from a change in the magnetic latitude, caused by a small annual translation of the whole magnetic equator from east to west, discovered by M Morlet, and confirmed by the investigations of M Arago

If a magnetised needle freely suspended, and at rest in the magnetic meridian, be drawn any number of degrees from its position, it will make a certain number of oscillations before it resumes its state of rest. The intensity of the magnetic force is determined from those oscillations in the same manner that the intensity of the gravitating and electrical forces are known from the vibrations of the pendulum and the balance of torsion, and in all these cases it is proportional to the square of the number of oscillations performed in a given time Consequently, a comparison of the number of vibrations accomplished by the same needle, during the same time, in different parts of the earth's surface, will determine the variations in the magnetic action. By this method MM de Humboldt and Rossel have discovered that the intensity of the magnetic force increases from the equator to the poles, where it is probably at its maximum. It appears to be doubled in the ascent from the equator to the western limits of Baffin's Bay. According to the magnetic observations of Professor Hansteen, of Christiania, the magnetic intensity has been decreasing annually at Christiania, London, and Paris, at the rate of its 235th, 725th, and 1020th parts respectively, which

he attributes to the revolution of the Siberian magnetic pole A diurnal variation in the horizontal intensity has also been observed by M. Hansteen at Christiania and by Mr Christie at Woolwich.

The translation of the magnetic equator, the motion of the magnetic poles, the changes in the intensity of the magnetic force, and the variations of the dipping needle and mariner's compass, have been attributed to the heat of the sun, and M Hansteen has even found a general resemblance between the isothermal lines and the lines of equal dip on the surface of the earth, yet in the present state of our knowledge they can only be regarded as effects of some unknown cause, and so much uncertainty prevails in the magnetic phenomena of the earth, that the results already obtained require to be continually corrected by new observations.

The inventor of the mariner's compass, like most of the early benefactors of mankind, is unknown It is even doubted which nation first made use of magnetic polarity to determine positions on the surface of the globe But it is said that a rude form of the compass was invented in Upper Asia, and conveyed thence by the Tartars to China, where the Jesuit missionaries found traces of this instrument having been employed as a guide to land travellers in very remote antiquity. From that the compass spread over the East, and was imported into Europe by the Crusaders, and its construction improved by an artist of Amalfi, on the coast of Calabria. It seems that the Romans and Chinese only employed eight cardinal divisions, which the Germans successively bisected till there were thirty-two, and gave the points the names which they still bear.

The variation of the compass was unknown till Columbus, during his first voyage, observed that the

needle declined from the meridian as he advanced across the Atlantic The dip of the magnetic needle was first noticed by Robert Norman, in the year 1576

Very delicate experiments have shown that all bodies are more or less susceptible of magnetism. Many of the gems give signs of it, cobalt, titanium, and nickel sometimes even possess the properties of attraction and repulsion But the magnetic agency is most powerfully developed in iron, and in that particular ore of iron called the loadstone, which consists of the protoxide and the peroxide of iron, together with small portions of silica and alumina. A metal is often susceptible of magnetism if it only contains the 130,000th part of its weight of iron, a quantity too small to be detected by any chemical test.

The bodies in question are naturally magnetic, but that property may be imparted by a variety of methods, as by friction with magnetic bodies, or juxtaposition to them, but none is more simple than percussion A bar of hard steel, held in the direction of the dip, will become a magnet on receiving a few smart blows with a hammer on its upper extremity, and M Hansteen has ascertained that every substance has magnetic poles when held in that position, whatever the materials may be of which it is composed.

One of the most distinguishing marks of magnetism is polarity, or the property a magnet possesses, when freely suspended, of spontaneously pointing nearly north and south, and always returning to that position when disturbed. Another property of a magnet is the attraction of unmagnetised iron. Both poles of a magnet attract iron, which in return attracts either pole of the magnet with an equal and contrary force. The magnetic intensity is most powerful at the poles, as may

easily be seen by dipping the magnet into iron filings, which will adhere abundantly to each pole, while scarcely any attach themselves to the intermediate parts. The action of the magnet on unmagnetised iron is confined to attraction, whereas the reciprocal agency of magnets is characterised by a repulsive as well as an attractive force, for a north pole repels a north pole, and a south repels a south pole. But a north and a south pole mutually attract one another, which proves that there are two distinct kinds of magnetic forces, directly opposite in their effects, though similar in their mode of action.

Induction is the power which a magnet possesses of exciting temporary or permanent magnetism in such bodies in its vicinity as are capable of receiving it. By this property the mere approach of a magnet renders iron or steel magnetic, the more powerfully the less the distance. When the north pole of a magnet is brought near to, and in the line with an unmagnetised iron bar, the bar acquires all the properties of a perfect magnet, the end next the north pole of the magnet becomes a south pole, while the remote end becomes a north pole. Exactly the reverse takes place when the south pole is presented to the bar, so that each pole of a magnet induces the opposite polarity in the adjacent end of the bar, and the same polarity in the remote extremity, consequently the nearest extremity of the bar is attracted, and the farther repelled, but as the action is greater on the adjacent than on the distant part, the resulting force is that of attraction. By induction, the iron bar not only acquires polarity, but the power of inducing magnetism in a third body; and although all these properties vanish from the iron as soon as the magnet is removed, a lasting increase of

intensity is generally imparted to the magnet itself by the reaction of the temporary magnetism of the iron Iron acquires magnetism more rapidly than steel, yet it loses it as quickly on the removal of the magnet, whereas the steel is impressed with a lasting polarity.

A certain time is requisite for the induction of magnetism, and it may be accelerated by any thing that excites a vibratory motion in the particles of the steel, such as the smart stroke of a hammer, or heat succeeded by sudden cold A steel bar may be converted into a magnet by the transmission of an electric discharge through it, and as its efficacy is the same in whatever direction the electricity passes, the magnetism arises from its mechanical operation exciting a vibration among the particles of the steel It has been observed that the particles of iron easily resume their neutral state after induction, but that those of steel resist the restoration of magnetic equilibrium, or a return to the neutral state it is therefore evident, that any cause which removes or diminishes the resistance of the particles will tend to destroy the magnetism of the steel, consequently, the same mechanical means which develope magnetism will also destroy it On that account, a steel bar may lose its magnetism by any mechanical concussion, such as by falling on a hard substance, a blow with a hammer, and heating to redness, which reduces the steel to the state of soft iron The circumstances which determine whether it shall gain or lose being, its position with respect to the magnetic equator, and the higher or lower intensity of its previous magnetic state.

Polarity of one kind only cannot exist in any portion of iron or steel, for in whatever manner the intensities of the two kinds of polarity may be diffused through a

magnet, they exactly balance or compensate one another. The northern polarity is confined to one half of a magnet, and the southern to the other, and they are generally concentrated in or near the extremities of the bar. When a magnet is broken across its middle, each fragment is at once converted into a perfect magnet, the part which originally had a north pole acquires a south pole at the fractured end, the part that originally had a south pole gets a north pole, and as far as mechanical division can be carried, it is found that each fragment however small, is a perfect magnet.

A comparison of the number of vibrations accomplished by the same needle, during the same time, at different distances from a magnet, gives the law of magnetic intensity, which, like every known force that emanates from a centre, follows the inverse ratio of the square of the distance, a law that is not affected by the intervention of any substance whatever between the magnet and the needle, provided that substance be not itself susceptible of magnetism Induction and the reciprocal action of magnets are, therefore, subject to the laws of mechanics, but the composition and resolution of the forces are complicated, in consequence of four forces being constantly in activity, two in each magnet.

Mr Were Fox, who has paid much attention to this branch of the science, has lately discovered that the law of the magnetic force changes from the inverse square of the distance to the simple inverse ratio, when the distance between two magnets is as small as from the fourth to the eighth of an inch, or even as much as half an inch when the magnets are large. He found, that in the case of repulsion, the change takes place at a still greater distance, especially when the two magnets differ materially in intensity.

The phenomena of magnetism may be explained on the hypothesis of two extremely rare fluids pervading all the particles of iron, and incapable of leaving them. Whether the particles of these fluids are coincident with the molecules of the iron, or that they only fill the interstices between them, is unknown and immaterial But it is certain that the sum of all the magnetic molecules, added to the sum of all the spaces between them, whether occupied by matter or not, must be equal to the whole volume of the magnetic body When the two fluids in question are combined they are inert, so that the substances containing them show no signs of magnetism; but when separate they are active, the molecules of each of the fluids attracting those of the opposite kind, and repelling those of the same kind. The decomposition of the united fluids is accomplished by the inductive influence of either of the separate fluids, that is to say, a ferruginous body acquires polarity by the approach of either the south or north pole of a magnet The electric fluids are confined to the surfaces of bodies, whereas the magnetic fluids pervade each molecule of the mass, besides, the electric fluid has a perpetual tendency to escape, and does escape, when not prevented by the coercive power of the surrounding air and other non-conducting bodies Such a tendency does not exist in the magnetic fluids, which never quit the substance that contains them under any circumstances whatever, nor is any sensible quantity of either kind of polarity ever transferred from one part to another of the same piece of steel It appears that the two magnetic fluids, when decomposed by the influence of magnetising forces, only undergo a displacement to an insensible degree within the body. The action of all the particles so displaced upon a par-

ticle of the magnetic fluid in any particular situation, compose a resultant force, the intensity and direction of which it is the province of the analyst to determine. In this manner M. Poisson has proved that the result of the action of all the magnetic elements of a magnetised body, is a force equivalent to the action of a very thin stratum covering the whole surface of a body, and consisting of the two fluids—the austral and the boreal, occupying different parts of it. In other words, the attractions and repulsions externally exerted by a magnet, are exactly the same as if they proceeded from a very thin stratum of each fluid occupying the surface only, both fluids being in equal quantities, and so distributed that their total action upon all the points in the interior of the body are equal to nothing. Since the resulting force is the difference of the two polarities, its intensity must be greatly inferior to that of either.

In addition to the forces already mentioned, there must be some coercive force analogous to friction, which arrests the particles of both fluids, so as first to oppose their separation, and then to prevent their reunion. In soft iron the coercive force is either wanting or extremely feeble, since the iron is easily rendered magnetic by induction, and as easily loses its magnetism; whereas in steel the coercive force is extremely energetic, because it prevents the steel from acquiring the magnetic properties rapidly, and entirely hinders it from losing them when acquired. The feebleness of the coercive force in iron, and its energy in steel, with regard to the magnetic fluids, is perfectly analogous to the facility of transmission afforded to the electric fluids by non-electrics, and the resistance they experience in electrics. At every step the analogy between magnetism and electricity becomes more striking. The agency of attraction

and repulsion is common to both, the positive and negative electricities are similar to the northern and southern polarities, and are governed by the same laws, namely, that between like powers there is repulsion, and between unlike powers there is attraction. Each of these four forces is capable of acting most energetically when alone, but the electric equilibrium is restored by the union of the two electricities, and magnetic neutrality by the combination of the two polarities, thus respectively neutralising each other when joined. All these forces vary inversely as the square of the distance, and consequently come under the same mechanical laws A like analogy extends to magnetic and electrical induction. Iron and steel are in a state of equilibrium when the two magnetic polarities conceived to reside in them are equally diffused throughout the whole mass, so that they are altogether neutral But this equilibrium is immediately disturbed on the approach of the pole of a magnet, which by induction transfers one kind of polarity to one end of the iron or steel bar, and the opposite kind to the other,—effects exactly similar to electrical induction. There is even a correspondence between the fracture of a magnet and that of an electric conductor, for if an oblong conductor be electrified by induction, its two extremities will have opposite electricities, and if in that state it be divided across the middle, the two portions, when removed to a distance from one another, will each retain the electricity that has been induced upon it The analogy, however, does not extend to transference A body may transfer a redundant quantity of positive or negative electricity to another, the one gaining at the expense of the other; but there is no instance of a body

possessing only one kind of polarity With this exception, there is such perfect correspondence between the theories of magnetic attractions and repulsions and electric forces in conducting bodies, that they not only are the same in principle, but are determined by the same formulæ. Experiment concurs with theory in proving the identity of these two unseen influences.

SECTION XXX.

DISCOVERY OF ELECTRO-MAGNETISM. — DEFLECTION OF THE MAGNETIC NEEDLE BY A CURRENT OF ELECTRICITY. — DIRECTION OF THE FORCE. — ROTATORY MOTION BY ELECTRICITY. — ROTATION OF A WIRE AND A MAGNET. — ROTATION OF A MAGNET ABOUT ITS AXIS. — OF MERCURY AND WATER. — ELECTRO-MAGNETIC CYLINDER OR HELIX. — SUSPENSION OF A NEEDLE IN A HELIX. — ELECTRO-MAGNETIC INDUCTION. — TEMPORARY MAGNETS. — THE GALVANOMETER.

THE disturbing effects of the aurora borealis and lightning on the mariner's compass had been long known. In the year 1819, Mr. Oersted, Professor of Natural Philosophy at Copenhagen, discovered that a current of voltaic electricity exerts a powerful influence on a magnetised needle. This observation has given rise to the theory of electro-magnetism, the most interesting science of modern times, whether it be considered as leading us a step farther in generalization, by identifying two agencies hitherto referred to different causes, or as developing a new force, unparalleled in the system of the world, which, overcoming the retardation from friction, and the obstacle of a resisting medium, maintains a perpetual motion, often vainly attempted, but apparently impossible to be accomplished by means of any other force or combination of forces than the one in question.

When the two poles of a voltaic battery are connected by a metallic wire, so as to complete a circuit, the electricity flows without ceasing. If a straight portion of that wire be placed parallel to, and horizontally, above a magnetised needle at rest in the magnetic me-

ridian, but freely poised like the mariner's compass, the action of the electric current flowing through the wire, will instantly cause the needle to change its position. Its extremity will deviate from the north towards the east or west, according to the direction in which the current is flowing; and on reversing the direction of the current, the motion of the needle will be reversed also. The numerous experiments that have been made on the magnetic and electric fluids, as well as those on the various relative motions of a magnetic needle under the influence of galvanic electricity, arising from all possible positions of the conducting wire, and every direction of the voltaic current, together with all the other phenomena of electro-magnetism, are explained by Dr. Roget in some excellent articles on these subjects in the Library of Useful Knowledge.

All the experiments tend to prove that the force emanating from the electric current, which produces such effects on the magnetic needle, acts at right angles to the current, and is therefore unlike any force hitherto known. The action of all the forces in nature is directed in straight lines, as far as we know, for the curves described by the heavenly bodies result from the composition of two forces, whereas, that which is exerted by an electrical current upon either pole of a magnet has no tendency to cause the pole to approach or recede, but to rotate about it. If the stream of electricity be supposed to pass through the centre of a circle whose plane is perpendicular to the current, the direction of the force exerted by the electricity will always be in the tangent to the circle, or at right angles to its radius.[1] Consequently the tangential force of the electricity has a tendency to make the pole of a magnet

[1] Note 214.

move in a circle round the wire of the battery. Mr. Barlow has proved that the action of each particle of the electric fluid in the wire, on each particle of the magnetic fluid in the needle, varies inversely as the square of the distance.

Rotatory motion was suggested by Dr. Wollaston. Dr Faraday was the first who actually succeeded in making the pole of a magnet rotate about a vertical conducting wire In order to limit the action of the electricity to one pole, about two-thirds of a small magnet was immersed in mercury, the lower end being fastened by a thread to the bottom of the vessel containing the mercury When the magnet was thus floating almost vertically with its north pole above the surface, a current of positive electricity was made to descend perpendicularly through a wire touching the mercury, and immediately the magnet began to rotate from left to right about the wire. The force being uniform, the rotation was accelerated till the tangential force was balanced by the resistance of the mercury, when it became constant Under the same circumstances, the south pole of the magnet rotates from right to left. It is evident from this experiment, that the wire may also be made to perform a rotation round the magnet, since the action of the current of electricity on the pole of the magnet must necessarily be accompanied by a corresponding reaction of the pole of the magnet on the electricity in the wire. This experiment has been accomplished by a vast number of contrivances, and even a small battery, consisting of two plates, has performed the rotation Dr. Faraday produced both motions at the same time in a vessel containing mercury, the wire and the magnet revolved in one direction

about a common centre of motion, each following the other.

The next step was to make a magnet, and also a cylinder, revolve about their own axes, which they do with great rapidity. Mercury has been made to rotate by means of voltaic electricity, and Professor Ritchie has exhibited in the Royal Institution the singular spectacle of the rotation of water by the same means, while the vessel containing it remained stationary. The water was in a hollow double cylinder of glass, and on being made the conductor of electricity, was observed to revolve in a regular vortex, changing its direction as the poles of the battery were alternately reversed. Professor Ritchie found that all the different conductors hitherto tried by him, such as water, charcoal, &c. give the same electro-magnetic results, when transmitting the same quantity of electricity, and that they deflect the magnetic needle in an equal degree, when their respective axes of conduction are at the same distance from it. But one of the most extraordinary effects of the new force is exhibited by coiling a copper wire, so as to form a helix, or corkscrew, and connecting the extremities of the wires with the poles of a galvanic battery. If a magnetised steel bar, or needle, be placed within the screw, so as to rest upon the lower part, the instant a current of electricity is sent through the wire of the helix, the steel bar starts up by the influence of this invisible power, and remains suspended in the air in opposition to the force of gravitation.[1] The effect of the electro-magnetic power exerted by each turn of the wire is to urge the north pole of the magnet in one direction, and the south pole in the other. The force thus exerted is multiplied in degree and in-

[1] Note 215

creased in extent by each repetition of the turns of the wire, and in consequence of these opposing forces the bar remains suspended. This helix has all the properties of a magnet while the electrical current is flowing through it, and may be substituted for one in almost every experiment. It acts as if it had a north pole at one extremity and a south pole at the other, and is attracted and repelled by the poles of a magnet exactly as if it were one itself All these results depend upon the course of the electricity, that is, on the direction of the turns of the screw, according as it is from right to left, or from left to right, being contrary in the two cases.

The action of voltaic electricity on a magnet is not only precisely the same with the action of two magnets on one another, but its influence in producing temporary magnetism in iron and steel is also the same with magnetic induction The term induction, when applied to electric currents, expresses the power which these currents possess of inducing any particular state upon matter in their immediate neighbourhood, otherwise neutral or indifferent For example, the connecting wire of a galvanic battery holds iron filings suspended like an artificial magnet, as long as the current continues to flow through it, and the most powerful temporary magnets that have ever been made are obtained by bending a thick cylinder of soft iron into the form of a horseshoe, and surrounding it with a coil of thick copper wire covered with silk, to prevent communication between its parts. When this wire forms part of a galvanic circuit, the iron becomes so highly magnetic, that a temporary magnet of this kind, made by Professor Henry, of the Albany Academy, in the United States,

sustained nearly a ton weight The iron loses its magnetic power the instant the electricity ceases to circulate, and acquires it again as instantaneously when the circuit is renewed Temporary magnets have been made by Professor Moll, of Utrecht, upon the same principle, capable of supporting 200 pounds weight, by means of a battery of one plate less than half an inch square, consisting of two metals soldered together It is truly wonderful that an agent, evolved by so small an instrument, and diffused through a large mass of iron, should communicate a force which seems so disproportionate Steel needles are rendered permanently magnetic by electrical induction; the effect is produced in a moment, and as readily by juxtaposition as by contact, the nature of the poles depends upon the direction of the current, and the intensity is proportional to the quantity of electricity.

It appears, that the principle and characteristic phenomena of the electro-magnetic science are, the evolution of a tangential and rotatory force exerted between a conducting body and a magnet, and the transverse induction of magnetism by the conducting body in such substances as are susceptible of it.

The action of an electric current causes a deviation of the compass from the plane of the magnetic meridian. In proportion as the needle recedes from the meridian, the intensity of the force of terrestrial magnetism increases, while at the same time the electro-magnetic force diminishes, the number of degrees at which the needle stops, showing where the equilibrium between these two forces takes place, will indicate the intensity of the galvanic current. The galvanometer, constructed upon this principle, is employed to measure the intensity of galvanic currents collected and conveyed to it by

wires This instrument is rendered much more sensible by neutralizing the effects of the earth's magnetism on the needle, which is accomplished by placing a second magnetised needle so as to counteract the action of the earth on the first, a precaution requisite in all delicate magnetical experiments.

SECTION XXXI.

ELECTRO-DYNAMICS — RECIPROCAL ACTION OF ELECTRIC CURRENTS — IDENTITY OF ELECTRO-DYNAMIC CYLINDERS AND MAGNETS — DIFFERENCES BETWEEN THE ACTION OF VOLTAIC ELECTRICITY AND ELECTRICITY OF TENSION — VELOCITY OF A VOLTAIC CURRENT UNKNOWN — AMPÈRE'S THEORY.

THE science of electro-magnetism, which must render the name of M. Oersted ever memorable, relates to the reciprocal action of electrical and magnetic currents: M. Ampère, by discovering the mutual action of electrical currents on one another, has added a new branch to the subject, to which he has given the name of electro-dynamics.

When electric currents are passing through two conducting wires, so suspended or supported as to be capable of moving both towards and from one another, they show mutual attraction or repulsion, according as the currents are flowing in the same or in contrary directions; the phenomena varying with the relative inclinations and positions of the streams of electricity. The mutual action of such currents, whether they flow in the same or in contrary directions, whether they be parallel, perpendicular, diverging, converging, circular, or helical, all produce different kinds of motion in a conducting wire, both rectilineal and circular, and also the rotation of a wire helix, such as that described, now called an electro-dynamic cylinder on account of some improvements in its con-

struction [1] And as the hypothesis of a force varying inversely as the square of the distance accords perfectly with all the observed phenomena, these motions come under the same laws of dynamics and analysis as any other branch of physics

Electro-dynamic cylinders act on each other precisely as if they were magnets during the time the electricity is flowing through them All the experiments that can be performed with the cylinder might be accomplished with a magnet. That end of the cylinder in which the current of positive electricity is moving in a direction similar to the motion of the hands of a watch, acts as the south pole of a magnet, and the other end, in which the current is flowing in a contrary direction, exhibits northern polarity.

The phenomena mark a very decided difference between the action of electricity in motion or at rest, that is, between voltaic and common electricity, the laws they follow are in many respects of an entirely different nature, though the electricities themselves are identical Since voltaic electricity flows perpetually, it cannot be accumulated, and consequently has no tension, or tendency to escape from the wires which conduct it Nor do those wires either attract or repel light bodies in their vicinity, whereas ordinary electricity can be accumulated in insulated bodies to a great degree, and in that state of rest the tendency to escape is proportional to the quantity accumulated and the resistance it meets with. In ordinary electricity, the law of action is, that dissimilar electricities attract and similar electricities repel one another. In voltaic electricity, on the contrary, similar currents, or such as are moving in the same direction, attract one another,

[1] Note 210.

while a mutual repulsion is exerted between dissimilar currents, or such as flow in opposite directions. Common electricity escapes when the pressure of the atmosphere is removed, but the electro-dynamical effects are the same whether the conductors be in air or in vacuo.

Although the effects produced by a current of electricity depend upon the celerity of its motion, the velocity with which it moves through a conducting wire is unknown. We are equally ignorant whether it be uniform or varied, but the method of transmission has a marked influence on the results, for when it flows without intermission, it occasions a deviation in the magnetic needle, but it has no effect whatever when its motion is discontinuous or interrupted, like the current produced by the common electrical machine when a communication is made between the positive and negative conductors

M Ampère has established a theory of electro-magnetism suggested by the analogy between electro-dynamic cylinders and magnets, founded upon the reciprocal attraction of electric currents, to which all the phenomena of magnetism and electro-magnetism may be reduced, by assuming that the magnetic properties which bodies possess, derive these properties from currents of electricity circulating about every part in one uniform direction Although every particle of a magnet possess like properties with the whole, yet the general effect is the same as if the magnetic properties were confined to the surface. Consequently the internal electro-currents must compensate one another, and therefore the magnetism of a body is supposed to arise from a superficial current of electricity constantly circulating in a direction perpendicular to the axis of

the magnet, so that the reciprocal action of magnets, and all the phenomena of electro-magnetism, are reduced to the action and reaction of superficial currents of electricity acting at right angles to their direction. Notwithstanding the experiments made by M Ampère to elucidate the subject, there is still an uncertainty in the theory of the induction of magnetism by an electric current in a body near it. It does not appear whether electric currents which did not previously exist are actually produced by induction, or if its effect be only to give one uniform direction to the infinite number of electric currents previously existing in the particles of the body, and thus rendering them capable of exhibiting magnetic phenomena, in the same manner as polarisation reduces those undulations of light to one plane, which had previously been performed in every plane Possibly both may be combined in producing the effect, for the action of an electric current may not only give a common direction to those already existing, but may also increase their intensity However that may be, by assuming that the attraction and repulsion of the elementary portions of electric currents vary inversely as the square of the distance, the action being at right angles to the direction of the current, it is found that the attraction and repulsion of a current of indefinite length on the elementary portion of a parallel current at any distance from it, is in the simple ratio of the shortest distance between them. Consequently the reciprocal action of electric currents is reduced to the composition and resolution of forces, so that the phenomena of electro-magnetism are brought under the laws of dynamics by the theory of M. Ampère.

SECTION XXXII.

MAGNETO-ELECTRICITY.—VOLTA-ELECTRIC INDUCTION.—MAGNETO-ELECTRIC INDUCTION.—IDENTITY IN THE ACTION OF ELECTRICITY AND MAGNETISM.—DESCRIPTION OF A MAGNETO-ELECTRIC APPARATUS AND ITS EFFECTS.—IDENTITY OF MAGNETISM AND ELECTRICITY.

FROM the law of action and reaction being equal and contrary, it might be expected that, as electricity powerfully affects magnets, so, conversely, magnetism ought to produce electrical phenomena. By proving this very important fact from the following series of interesting and ingenious experiments, Dr. Faraday has added another branch to the science, which he has named magneto-electricity. A great quantity of copper wire was coiled in the form of a helix round one half of a ring of soft iron, and connected with a galvanic battery, while a similar helix connected with a galvanometer was wound round the other half of the ring, but not touching the first helix. As soon as contact was made with the battery, the needle of the galvanometer was deflected. But the action was transitory; for when the contact was continued, the needle returned to its usual position, and was not affected by the continual flow of the electricity through the wire connected with the battery. As soon, however, as the contact was broken, the needle of the galvanometer was again deflected, but in the contrary direction. Similar effects

were produced by an apparatus consisting of two helices of copper wire coiled round a block of wood, instead of iron, from which Dr Faraday infers that the electric current passing from the battery through one wire, induces a similar current through the other wire, but only at the instant of contact, and that a momentary current is induced in a contrary direction when the passage of the electricity is suddenly interrupted These brief currents or waves of electricity were found to be capable of magnetising needles, of passing through a small extent of fluid, and when charcoal points were interposed in the current of the induced helix, a minute spark was perceived as often as the contacts were made or broken, but neither chemical action nor any other electric effects were obtained A deviation of the needle of the galvanometer took place when common magnets were employed instead of the voltaic current, so that the magnetic and electric fluids are identical in their effects in this experiment Again, when a helix formed of 220 feet of copper wire, into which a cylinder of soft iron was introduced, was placed between the north and south poles of two bar magnets, and connected with the galvanometer by means of wires from each extremity, as often as the magnets were brought into contact with the iron cylinder, it became magnetic by induction, and produced a deflection in the needle of the galvanometer On continuing the contact, the needle resumed its natural position, and when the contact was broken, deflection took place in the opposite direction; when the magnetic contacts were reversed, the deflection was reversed also. With strong magnets, so powerful was the action, that the needle of the galvanometer whirled round several times successively, and similar effects were produced by the mere approxi-

mation or removal of the helix to the poles of the magnets. Thus it was proved that magnets produce the very same effects on the galvanometer that electricity does. Though at that time no chemical decomposition was effected by those momentary currents which emanate from the magnets, they agitated the limbs of a frog; and Dr. Faraday justly observes, that "an agent which is conducted along metallic wires in the manner described, which, whilst so passing, possesses the peculiar magnetic actions and force of a current of electricity, which can agitate and convulse the limbs of a frog, and which finally can produce a spark by its discharge through charcoal, can only be electricity." Hence it appears that electrical currents are evolved by magnets, which produce the same phenomena with the electrical currents from the voltaic battery: they, however, differ materially in this respect — that time is required for the exercise of the magnetico-electric induction, whereas volta-electric induction is instantaneous.

After Dr. Faraday had proved the identity of the magnetic and electric fluids by producing the spark, heating metallic wires, and accomplishing chemical decomposition, it was easy to increase those effects by more powerful magnets and other arrangements. The apparatus now in use is in effect a battery, where the agent is the magnetic, instead of the voltaic fluid, or, in other words, electricity, and is thus constructed.

A very powerful horse-shoe magnet, formed of twelve steel plates in close approximation, is placed in a horizontal position. An armature, consisting of a bar of the purest soft iron, has each of its ends bent at right angles, so that the faces of those ends may be brought directly opposite and close to the poles of the magnet

when required. Ten copper wires — covered with silk, in order to insulate them — are wound round one half of the bar of soft iron, as a compound helix: ten other wires, also insulated, are wound round the other half of the bar. The extremities of the first set of wires are in metallic connection with a circular disc, which dips into a cup of mercury, while the ends of the other ten wires in the opposite direction are soldered to a projecting screw-piece, which carries a slip of copper with two opposite points. The steel magnet is stationary; but when the armature, together with its appendages, is made to rotate vertically, the edge of the disc always remains immersed in the mercury, while the points of the copper slip alternately dip in it and rise above it. By the ordinary laws of induction, the armature becomes a temporary magnet while its bent ends are opposite the poles of the steel magnet, and ceases to be magnetic when they are at right angles to them. It imparts its temporary magnetism to the helices which concentrate it; and while one set conveys a current to the disc, the other set conducts the opposite current to the copper slip. As the edge of the revolving disc is always immersed in the mercury, one set of wires is constantly maintained in contact with it, and the circuit is only completed when a point of the copper slip dips in the mercury also; but the circuit is broken the moment that point rises above it. Thus, by the rotation of the armature, the circuit is alternately broken and renewed; and as it is only at these moments that electric action is manifested, a brilliant spark takes place every time the copper point leaves the surface of the mercury. Platina wire is ignited, shocks smart enough to be disagreeable are given, and water is de-

composed with astonishing rapidity by the same means, which proves beyond a doubt the identity of the magnetic and electric agencies, and places Dr Faraday, whose experiments established the principle, in the first rank of experimental philosophers.

SECTION XXXIII

ELECTRICITY PRODUCED BY ROTATION — DIRECTION OF THE CURRENTS — ELECTRICITY FROM THE ROTATION OF A MAGNET — M. ARAGO'S EXPERIMENT EXPLAINED — ROTATION OF A PLATE OF IRON BETWEEN THE POLES OF A MAGNET — RELATION OF SUBSTANCES TO MAGNETS OF THREE KINDS — THERMO-ELECTRICITY

M. ARAGO discovered an entirely new source of magnetism in rotatory motion If a circular plate of copper be made to revolve immediately above or below a magnetic needle or magnet, suspended in such a manner that the magnet may rotate in a plane parallel to that of the copper plate, the magnet tends to follow the circumvolution of the plate; or if the magnet revolves, the plate tends to follow its motion so powerful is the effect, that magnets and plates of many pounds weight have been carried round This is quite independent of the motion of the air, since it is the same when a pane of glass is interposed between the magnet and the copper. When the magnet and the plate are at rest, not the smallest effect, attractive, repulsive, or of any kind, can be perceived between them In describing this phenomenon, M Arago states that it takes place not only with metals, but with all substances, solids, liquids, and even gases, although the intensity depends upon the kind of substance in motion. Experiments made by Dr Faraday explain this singular action A plate of copper, twelve inches in diameter and one fifth of an inch thick, was placed between the poles of a powerful horse-shoe magnet,

and connected at certain points with a galvanometer by copper wires When the plate was at rest no effect was produced, but as soon as the plate was made to revolve rapidly, the galvanometer needle was deflected sometimes as much as 90°, and by a uniform rotation, the deflection was constantly maintained at 45°. When the motion of the copper plate was reversed, the needle was deflected in the contrary direction, and thus a permanent current of electricity was evolved by an ordinary magnet The intensity of the electricity collected by the wires, and conveyed by them to the galvanometer, varied with the position of the plate relatively to the poles of the magnet

The motion of the electricity in the copper plate may be conceived, by considering, that merely from moving a single wire like the spoke of a wheel before a magnetic pole, a current of electricity tends to flow through it from one end to the other Hence, if a wheel be constructed of a great many such spokes, and revolved near the pole of a magnet in the manner of the copper disc, each radius or spoke will tend to have a current produced in it as it passes the pole. Now, as the circular plate is nothing more than an infinite number of radii or spokes in contact, the currents will flow in the direction of the radii if a channel be open for their return, and in a continuous plate that channel is afforded by the lateral portions on each side of the particular radius close to the magnetic pole. This hypothesis is confirmed by observation, for the currents of positive electricity set from the centre to the circumference, and the negative from the circumference to the centre, and *vice versâ*, according to the position of the magnetic poles and the direction of rotation. So that a collecting wire at the centre of the copper plate con-

veys positive electricity to the galvanometer in one case, and negative in another, that collected by a conducting wire in contact with the circumference of the plate is always the opposite of the electricity conveyed from the centre. It is evident that when the plate and magnet are both at rest, no effect takes place, since the electric currents which cause the deflection of the galvanometer cease altogether The same phenomena may be produced by electro-magnets The effects are similar when the magnet rotates and the plate remains at rest When the magnet revolves uniformly about its own axis, electricity of the same kind is collected at its poles, and the opposite electricity at its equator

The phenomena which take place in M Arago's experiments may be explained on this principle. When both the copper plate and the magnet are revolving, the action of the induced electric current tends continually to diminish their relative motion, and to bring the moving bodies into a state of relative rest, so that if one be made to revolve by an extraneous force, the other will tend to revolve about it in the same direction, and with the same velocity

When a plate of iron, or of any substance capable of being made either a temporary or permanent magnet, revolves between the poles of a magnet, it is found that dissimilar poles on opposite sides of the plate neutralise each other's effects, so that no electricity is evolved, while similar poles on each side of the revolving plate increase the quantity of electricity, and a single pole end-on is sufficient But when copper, and substances not sensible to ordinary magnetic impressions, revolve, similar poles on opposite sides of the plate neutralise each other, dissimilar poles on each side exalt the action, and a single pole at the edge of the revolving

plate, or end-on, does nothing. This forms a test for distinguishing the ordinary magnetic force from that produced by rotation. If unlike poles, that is, a north and a south pole, produce more effect than one pole, the force will be due to electric currents; if similar poles produce more effect than one, then the power is not electric. These investigations show that there are really very few bodies magnetic in the manner of iron. Dr. Faraday therefore arranges substances in three classes, with regard to their relation to magnets. Those affected by the magnet when at rest, like iron, steel, and nickel, which possess ordinary magnetic properties; those affected when in motion, in which electric currents are evolved by the inductive force of the magnet, such as copper; and lastly, those which are perfectly indifferent to the magnet, whether at rest or in motion.

It has already been observed, that three bodies are requisite to form a galvanic circuit, one of which must be fluid. But in 1822, Professor Seebeck, of Berlin, discovered that electric currents may be produced by the partial application of heat to a circuit formed of two solid conductors. For example, when a semicircle of bismuth, joined to a semicircle of antimony, so as to form a ring, is heated at one of the junctions by a lamp, a current of electricity flows through the circuit from the antimony to the bismuth, and such thermo-electric currents produce all the electro-magnetic effects. A compass needle placed either within or without the circuit, and at a small distance from it, is deflected from its natural position, in a direction corresponding to the way in which the electricity is flowing. If such a ring be suspended so as to move easily in any direction, it will obey the action of a magnet brought near it, and may even be made to revolve. According to the re-

searches of M Seebeck, the same substance, unequally heated, exhibits electrical currents, and M Nobili observed that in all metals, except zinc, iron, and antimony, the electricity flows from the hot part towards that which is cold That philosopher attributes terrestrial magnetism to a difference in the action of heat on the various substances of which the crust of the earth is composed, and in confirmation of his views he has produced electrical currents by the contact of two pieces of moist clay, of which one was hotter than the other

M. Becquerel constructed a thermo-electric battery of one kind of metal, by which he has determined the relation between the heat employed and the intensity of the resulting electricity. He found that in most metals the intensity of the current increases with the heat to a certain limit, but that this law extends much farther in metals that are difficult to fuse, and which do not rust. The experiments of Professor Cumming show that the mutual action of a magnet and a thermo-electric current is subject to the same laws as those of magnets and galvanic currents, consequently all the phenomena of repulsion, attraction, and rotation, may be exhibited by a thermo-electric current M. Bottot, of Turin, has decomposed water and some solutions by thermo-electricity, it is, however, so feeble that neither heat, light, or any other effects of tension have been perceived

SECTION XXXIV.

THE ACTION OF TERRESTRIAL MAGNETISM UPON ELECTRIC CURRENTS — INDUCTION OF ELECTRIC CURRENTS BY TERRESTRIAL MAGNETISM — THE EARTH MAGNETIC BY INDUCTION — MR. BARLOW'S EXPERIMENT OF AN ARTIFICIAL SPHERE — THE HEAT OF THE SUN THE PROBABLE CAUSE OF ELECTRIC CURRENTS IN THE CRUST OF THE EARTH AND OF THE VARIATIONS IN TERRESTRIAL MAGNETISM — TERRESTRIAL MAGNETISM POSSIBLY OWING TO ROTATION — MAGNETIC PROPERTIES OF THE CELESTIAL BODIES — IDENTITY OF THE FIVE KINDS OF ELECTRICITY — CONNECTION BETWEEN LIGHT, HEAT, AND ELECTRICITY OR MAGNETISM.

IN all the experiments hitherto described, artificial magnets alone were used; but it is obvious that the magnetism of the terrestrial spheroid, which has so powerful an influence on the mariner's compass, must also affect electrical currents. It consequently appears that a piece of copper wire bent into a rectangle, and free to revolve on a vertical axis, arranges itself with its plane at right angles to the magnetic meridian, as soon as a stream of electricity is sent through it. Under the same circumstances a similar rectangle, suspended on a horizontal axis at right angles to the magnetic meridian, assumes the same inclination with the dipping needle. So that terrestrial magnetism has the same influence on electrical currents as an artificial magnet. But the magnetic action of the earth also induces electric currents. When a hollow helix of copper wire, whose extremities are connected with the galvanometer, is placed in the magnetic dip, and suddenly inverted several times, accommodating the motion to the oscil-

lations of the needle, the latter is soon made to vibrate through an arc of 80° or 90°. Hence it is evident, that whatever may be the cause of terrestrial magnetism, it produces currents of electricity by its direct inductive power upon a metal not capable of exhibiting any of the ordinary magnetic properties The action on the galvanometer is much greater when a cylinder of soft iron is inserted into the helix, and the same results follow the simple introduction of the iron cylinder into, or removal out of the helix These effects arise from the iron being made a temporary magnet by the inductive action of terrestrial magnetism, for a piece of iron, such as a poker, becomes a magnet for the time, when placed in the line of the magnetic dip

M Biot has formed a theory of terrestrial magnetism upon the observations of M de Humboldt as data Assuming that the action of the two opposite magnetic poles of the earth upon any point is inversely as the square of the distance, he obtains a general expression for the direction of the magnetic needle, depending upon the distance between the north and south magnetic poles; so that if one of these quantities varies, the corresponding variation of the other will be known. By making the distance between the poles vary, and comparing the resulting direction of the needle with the observations of M de Humboldt, he found that the nearer the poles are supposed to approach to one another, the more did the computed and observed results agree, and when the poles were assumed to coincide, or nearly so, the difference between theory and observation was the least possible It is evident, therefore, that the earth does not act as if it were a permanently magnetic body, the distinguishing characteristic of which is, to have two poles at a distance from one another Mr.

Barlow has investigated this subject with much skill and success He first proved that the magnetic power of an iron sphere resides in its surface, he then enquired what the superficial action of an iron sphere in a state of transient magnetic induction, on a magnetised needle, would be, if insulated from the influence of terrestrial magnetism. The results obtained, corroborated by the profound analysis of M Poisson, on the hypothesis of the two poles being indefinitely near the centre of the sphere, are identical with those obtained by M. Biot for the earth from M de Humboldt's observations. Whence it follows, that the laws of terrestrial magnetism deduced from the formulæ of M Biot, are inconsistent with those which belong to a permanent magnet, but that they are perfectly concordant with those belonging to a body in a state of transient magnetic induction. The earth, therefore, is to be considered as only transiently magnetic by induction, and not a real magnet. Mr Barlow has rendered this extremely probable by forming a wooden globe, with grooves admitting of a copper wire being coiled round it parallel to the equator from pole to pole When a current of electricity was sent through the wire, a magnetic needle suspended above the globe, and neutralised from the influence of the earth's magnetism, exhibited all the phenomena of the dipping and variation needles, according to its positions with regard to the wooden globe. As there can be no doubt that the same phenomena would be exhibited by currents of thermo, instead of voltaic, electricity, if the grooves of the wooden globe were filled by rings constituted of two metals, or of one metal unequally heated, it seems highly probable that the heat of the sun may be the great agent in developing electric currents in or near the surface of the earth, by its ac-

tion upon the substances of which the globe is composed, and, by changes in its intensity, may occasion the diurnal variation of the compass, and the other vicissitudes in terrestrial magnetism evinced by the disturbance in the directions of the magnetic lines, in the same manner as it influences the parallelism of the isothermal lines. That such currents do exist in metalliferous veins appears from the experiments of Mr Fox in the Cornish copper-mines. However, it is probable, that the secular and periodic disturbances in the magnetic force are occasioned by a variety of combining circumstances. Among others, M. Biot mentions the vicinity of mountain chains to the place of observation, and still more the action of extensive volcanic fires, which change the chemical state of the terrestrial surface, they themselves varying from age to age, some becoming extinct, while others burst into activity.

It is moreover probable, that terrestrial magnetism may be owing, in a certain extent, to the earth's rotation. Dr. Faraday has proved that all the phenomena of revolving plates may be produced by the inductive action of the earth's magnetism alone. If a copper plate be connected with a galvanometer by two copper wires, one from the centre and another from the circumference, in order to collect and convey the electricity, it is found that, when the plate revolves in a plane passing through the line of the dip, the galvanometer is not affected. But as soon as the plate is inclined to that plane, electricity begins to be developed by its rotation; it becomes more powerful as the inclination increases, and arrives at a maximum when the plate revolves at right angles to the line of the dip. When the revolution is in the same direction with that of the

hands of a watch, the current of electricity flows from its centre to the circumference; and when the rotation is in the opposite direction, the current sets the contrary way. The greatest deviation of the galvanometer amounted to 50° or 60°, when the direction of the rotation was accommodated to the oscillations of the needle. Thus a copper plate, revolving in a plane at right angles to the line of the dip, forms a new electrical machine, differing from the common plate glass machine, by the material of which it is composed being the most perfect conductor, whereas glass is the most perfect non-conductor; besides, insulation, which is essential in the glass machine, is fatal in the copper one. The quantity of electricity evolved by the metal does not appear to be inferior to that developed by the glass, though very different in intensity.

From the experiments of Dr Faraday, and also from theory, it is possible that the rotation of the earth may produce electric currents in its own mass. In that case, they would flow superficially in the meridians, and if collectors could be applied at the equator and poles, as in the revolving plate, negative electricity would be collected at the equator, and positive at the poles; but without something equivalent to conductors to complete the circuit, these currents could not exist.

Since the motion, not only of metals but even of fluids, when under the influence of powerful magnets, evolves electricity, it is probable that the gulf stream may exert a sensible influence upon the forms of the lines of magnetic variation, in consequence of electric currents moving across it, by the electro-magnetic induction of the earth. Even a ship, passing over the surface of the water in northern or southern latitudes, ought to have electric currents running directly across

the line of her motion Dr Faraday observes, that such is the facility with which electricity is evolved by the earth's magnetism, that scarcely any piece of metal can be moved in contact with others without a development of it, and consequently, among the arrangements of steam engines and metallic machinery, curious electro-magnetic combinations probably exist, which have never yet been noticed.

What magnetic properties the sun and planets may have, it is impossible to conjecture, although their rotation might lead us to infer that they are similar to the earth in this respect. According to the observations of MM. Biot and Gay-Lussac, during their aerostatic expedition, the magnetic action is not confined to the surface of the earth, but extends into space A decrease in its intensity is perceptible, and as it most likely follows the ratio of the inverse square of the distance, it must extend indefinitely. It is probable that the moon has become highly magnetic by induction, in consequence of her proximity to the earth, and because her greatest diameter always points towards it. Should the magnetic, like the gravitating force, extend through space, the induction of the sun, moon, and planets, must occasion perpetual variations in the intensity of terrestrial magnetism, by the continual changes in their relative positions.

In the brief sketch that has been given of the five kinds of electricity, those points of resemblance have been pointed out which are characteristic of one individual power. But as many anomalies have been lately removed, and the identity of the different kinds placed beyond a doubt, by Dr. Faraday, it may be satisfactory to take a summary view of the various coincidences in their modes of action on which their identity has been

so ably and completely established by that great electrician.

The points of comparison are attraction and repulsion at sensible distances, discharged from points through air, the heating power, magnetic influence, chemical decomposition, action on the human frame, and lastly the spark.

Attraction and repulsion at sensible distances, which are so eminently characteristic of ordinary electricity, and also in a lesser degree, of the voltaic and magnetic currents, have not been perceived in either the thermo or animal electricities, not on account of difference of kind, but owing to inferiority in tension, for even ordinary electricity, when much reduced in quantity and intensity, is incapable of exhibiting these phenomena.

Ordinary electricity is readily discharged from points through air, but Dr. Faraday found that no sensible effect takes place from a battery consisting of 140 double plates, either through air or in the exhausted receiver of an air pump, the tests of the discharge being the electrometer and chemical action, — a circumstance owing to the small degree of tension, for an enormous quantity of electricity is required to make these effects sensible, and for that reason they cannot be expected from the other kinds, which are much inferior in degree. Common electricity passes easily through rarefied and hot air, and also through flame. Dr. Faraday effected chemical decomposition and a deflection of the galvanometer by the transmission of voltaic electricity through heated air, and observes that these experiments are only cases of the discharge which takes place through air between the charcoal terminations of the poles of a powerful battery when they are gradually separated

after contact—for the air is then heated Sir Humphry Davy mentions that, with the original voltaic apparatus at the Royal Institution, the discharge passed through four inches of air; that, in the exhausted receiver of an air-pump, the electricity would strike through nearly half an inch of space, and the combined effects of rarefaction and heat, upon the included air, were such as to enable it to conduct the electricity through a space of six or seven inches A Leyden jar may be instantaneously charged with voltaic, and also with magneto-electricity—another proof of their tension. Such effects cannot be obtained from the other kinds, on account of their weakness only

The heating powers of ordinary and voltaic electricity have long been known, but the world is indebted to Dr Faraday for the wonderful discovery of the heating power of the magnetic fluid there is no indication of heat either from the animal or thermo-electricities. All kinds of electricity have strong magnetic powers, those of the voltaic fluid are highly exalted, and the existence of the magneto and thermo-electricities was discovered by their magnetic influence alone The needle has been deflected by all in the same manner, and, with the exception of thermo-electricity, magnets have been made by all according to the same laws Ordinary electricity was long supposed incapable of deflecting the needle, and it required Dr. Faraday's ingenuity to produce that effect. He has, however, proved that, in this respect, also, ordinary electricity agrees with voltaic, but that time must be allowed for its action It deflected the needle, whether the current was sent through rarefied air, water, or wire. Numerous chemical decompositions have been effected by ordinary and voltaic electricity, according to the same laws and modes of

arrangement. Dr. Davy decomposed water by the electricity of the torpedo, — Dr. Faraday accomplished its decomposition, and Dr. Ritchie its composition, by means of magnetic action; and M. Bottot, of Turin, has shown the chemical effects of the thermo-electricity in the decomposition of water, and some other substances. The electric and galvanic shock, the flash in the eyes, and the sensation on the tongue, are well known. All these effects are produced by magneto-electricity, even to a painful degree. The torpedo and gymnotus electricus give severe shocks, and the limbs of a frog have been convulsed by thermo-electricity. The last point of comparison is the spark, which is common to the ordinary, voltaic, and magnetic fluids; and although it has not yet been seen from the thermo and animal electricities, there can be no doubt that it is only on account of their feebleness. Indeed, the conclusion drawn by Dr. Faraday is, that the five kinds of electricity are identical and that the differences of intensity and quantity are quite sufficient to account for what were supposed to be their distinctive qualities. He has given still greater assurance of their identity by showing that the magnetic force and the chemical action of electricity are in direct proportion to the absolute quantity of the fluid which passes through the galvanometer, whatever its intensity may be.

In light, heat, and electricity, or magnetism, nature has exhibited principles which do not occasion any appreciable change in the weight of bodies, although their presence is manifested by the most remarkable mechanical and chemical action. These agencies are so connected, that there is reason to believe they will ultimately be referred to some one power of a higher order, in conformity with the general economy of the system of

the world, where the most varied and complicated effects are produced by a small number of universal laws. These principles penetrate matter in all directions; their velocity is prodigious, and their intensity varies inversely as the square of the distance. The development of electric currents, as well by magnetic as electric induction, the similarity in their mode of action in a great variety of circumstances, but, above all, the production of the spark from a magnet, the ignition of metallic wires, and chemical decomposition, show that magnetism can no longer be regarded as a separate independent principle. That light is visible heat, seems highly probable, and although the evolution of light and heat during the passage of the electric fluid may be from the compression of the air, yet the development of electricity by heat, the influence of heat on magnetic bodies, and that of light on the vibrations of the compass, show an occult connection between all these agents, which probably will one day be revealed. In the mean time it opens a noble field of experimental research to philosophers of the present, perhaps of future ages.

SECTION XXXV.

ETHEREAL MEDIUM.—COMETS.—DO NOT DISTURB THE SOLAR SYSTEM.—THEIR ORBITS AND DISTURBANCES.—PERIODS OF THREE KNOWN.—ACCELERATION IN THE MEAN MOTIONS OF ENCKE'S AND BIELA'S COMETS.—THE SHOCK OF A COMET.—VELOCITY AND PHYSICAL CONSTITUTION.—SHINE BY BORROWED LIGHT.—ESTIMATION OF THEIR NUMBER.

IN considering the constitution of the earth and the fluids which surround it, various subjects have presented themselves to our notice, of which some, for aught we know, are confined to the planet we inhabit; some are common to it and to the other bodies of our system. But an all-pervading ether probably fills the whole visible creation, and conveys, in the form of light, tremors which may have been excited in the deepest recesses of the universe thousands of years before we were called into being. The existence of such a medium, though at first hypothetical, is nearly proved by the undulatory theory of light, and rendered all but certain within a few years by the motion of comets, and by its action upon the vapours of which they are chiefly composed. It has often been imagined that, in addition to the effects of heat and electricity, the tails of comets have infused new substances into our atmosphere. Possibly the earth may attract some of that nebulous matter, since the vapours raised by the sun's heat, when the comets are in perihelio, and which form their tails, are scattered through space in their passage to their aphelion; but it has hitherto produced no effect, nor have the seasons ever been influenced by these

bodies In all probability, the tails of comets may have passed over the earth without its inhabitants being conscious of their presence

The passage of comets has never sensibly disturbed the stability of the solar system, their nucleus, being in general only a mass of vapours, is so rare, and their transit so rapid, that the time has not been long enough to admit of a sufficient accumulation of impetus to produce a perceptible action. Indeed, M Dusejour has proved that, under the most favourable circumstances, a comet cannot remain longer than two hours and a half at a less distance from the earth than 10,500 leagues The comet of 1770 passed within about six times the distance of the moon from the earth, without even affecting our tides, and as the moon has no sensible influence on the equilibrium of the atmosphere, a comet must have still less. According to La Place, the action of the earth on the comet of 1770 augmented the period of its revolution by more than two days; and if comets had any perceptible disturbing energy, the reaction of the comet ought to have increased the length of our year. Had the mass of that comet been equal to the mass of the earth, its disturbing action would have increased the length of the sideral year by $2^h\,53^m$, but as Delambre's computations from the Greenwich observations of the sun, show that the length of the year has not been increased by the fraction of a second, its mass could not have been equal to the $\frac{1}{5000}$ part of that of the earth. This accounts for the same comet having twice swept through the system of Jupiter's satellites without deranging the motions of these moons. M. Dusejour has computed that a comet, equal in mass to the earth, passing at the distance of 12,150 leagues from our planet, would increase the length of the year

to $367^d\ 16^h\ 5^m$, and the obliquity of the ecliptic as much as 2°. So the principal action of comets would be to alter the calendar, even if they were dense enough to affect the earth.

Comets traverse all parts of the heavens; their paths have every possible inclination to the plane of the ecliptic, and, unlike the planets, the motion of more than half of those that have appeared have been retrograde, that is, from east to west. They are only visible when near their perihelia; then their velocity is such, that its square is twice as great as that of a body moving in a circle at the same distance: they consequently remain but a very short time within the planetary orbits. And as all the conic sections of the same focal distance sensibly coincide, through a small arc on each side of the extremity of their axis, it is difficult to ascertain in which of those curves the comets move, from observations made, as they necessarily must be, at their perihelia. Probably they all move in extremely excentric ellipses, although in most cases the parabolic curve coincides most nearly with their observed motions. Some few seem to describe hyperbolas; such being once visible to us, would vanish for ever, to wander through boundless space, to the remote systems of the universe. If a planet be supposed to revolve in a circular orbit, whose radius is equal to the perihelion distance of a comet moving in a parabola, the areas described by these two bodies in the same time will be as unity to the square root of two, which forms such a connection between the motion of comets and planets, that, by Kepler's law, the ratio of the areas described during the same time by the comet and the earth may be found. So that the place of a comet at any time in its parabolic orbit, estimated from the instant of its passage

at the perihelion, may be computed. It is a problem of very great difficulty to determine all the other elements of parabolic motion — namely, the comet's perihelion distance, or shortest distance from the sun, estimated in parts of the mean distance of the earth from the sun; the longitude of the perihelion, the inclination of the orbit on the plane of the ecliptic, and the longitude of the ascending node. Three observed longitudes and latitudes of a comet are sufficient for computing the approximate values of these quantities, but an accurate estimation of them can only be obtained by successive corrections, from a number of observations, distant from one another. When the motion of a comet is retrograde, the place of the ascending node is exactly opposite to what it is when the motion is direct. Hence the place of the ascending node, together with the direction of the comet's motion, show whether the inclination of the orbit is on the north or south side of the plane of the ecliptic. If the motion be direct, the inclination is on the north side; if retrograde, it is on the south side.

The identity of the elements is the only proof of the return of a comet to our system. Should the elements of a new comet be the same, or nearly the same, with those of any one previously known, the probability of the identity of the two bodies is very great, since the similarity extends to no less than four elements, every one of which is capable of an infinity of variations. But even if the orbit be determined with all the accuracy the case admits of, it may be difficult, or even impossible, to recognise a comet on its return, because its orbit would be very much changed if it passed near any of the large planets of this, or of any other system, in consequence of their disturbing energy, which would

be very great on bodies of so rare a nature. Halley computed the elements of the orbit of a comet that appeared in the year 1682, which agreed so nearly with those of the comets of 1607 and 1531, that he concluded it to be the same body returning to the sun, at intervals of about seventy-five years. He consequently predicted its re-appearance in the year 1758, or in the beginning of 1759. Science was not sufficiently advanced in the time of Halley, to enable him to determine the perturbations this comet might experience; but Clairaut computed that it would be retarded in its motion a hundred days by the attraction of Saturn, and 518 by that of Jupiter, and consequently, that it would pass its perihelion about the middle of April, 1759, requiring 618 days more to arrive at that point than in its preceding revolution. This, however, he considered only to be an approximation, and that it might be thirty days more or less: the return of the comet on the 12th of March, 1759, proved the truth of the prediction. MM. Damoiseau and Pontecoulant have ascertained that this comet will return either on the 4th or the 7th of November, 1835; the difference of three days in their computations arises from their having employed different values for the masses of the planets. This is the first comet whose periodicity has been established. It is also the first whose elements have been determined from observations made in Europe, for although the comets which appeared in the years 240, 539, 565, and 837, are the most ancient whose orbits have been traced, their elements were computed from Chinese observations.

By far the most curious and interesting instance of the disturbing action of the great bodies of our system is found in the comet of 1770. The elements of its

orbit, determined by Messier, did not agree with those of any comet that had hitherto been computed, yet Lexel ascertained that it described an ellipse about the sun, whose major axis was only equal to three times the length of the diameter of the terrestrial orbit, and consequently that it must return to the sun at intervals of five years and a half. This result was confirmed by numerous observations, as the comet was visible through an arc of 170°; yet this comet had never been observed before the year 1770, nor has it ever again been seen, though very brilliant. The disturbing action of the larger planets affords a solution of this anomaly, as Lexel ascertained that in 1767 the comet must have passed Jupiter at a distance less than the fifty-eighth part of its distance from the sun, and that in 1779 it would be 500 times nearer Jupiter than the sun, consequently the action of the sun on the comet would not be the fiftieth part of what it would experience from Jupiter, so that Jupiter became the primum mobile. Assuming the orbit to be such as Lexel had determined in 1770, La Place found that the action of Jupiter, previous to the year 1770, had so completely changed the form of it, that the comet which had been invisible to us before 1770, was then brought into view, and that the action of the same planet producing a contrary effect, has, subsequently to that year, removed it, probably for ever, from our system. This comet might have been seen from the earth in 1776, had its light not been eclipsed by that of the sun.

Besides Halley's comet, two others are now proved to form part of our system, that is to say, they return to the sun at intervals, one of 1207 days, and the other of $6\frac{3}{4}$ years, nearly. The first, generally called Encke's comet, or the comet of the short period, was first seen

by MM. Messier and Mechain in 1786, again by Miss Herschel in 1795, and its returns in the years 1805 and 1819 were observed by other astronomers, under the impression that all four were different bodies. However, Professor Encke not only proved their identity, but determined the circumstances of the comet's motion Its re-appearance in the years 1825, 1828, and 1832, accorded with the orbit assigned by M. Encke, who thus established the length of its period to be 1207 days, nearly This comet is very small, of feeble light, and invisible to the naked eye, except under very favourable circumstances, and in particular positions. It has no tail, it revolves in an ellipse of great excentricity inclined at an angle of 13° 22′ to the plane of the ecliptic, and is subject to considerable perturbations from the attraction of the planets. Among the many perturbations to which the planets are liable, their mean motions, and, therefore, the major axes of their orbits, experience no change; while, on the contrary, the mean motion of the moon is accelerated from age to age, a circumstance at first attributed to the resistance of an etherial medium pervading space, but subsequently proved to arise from the secular diminution of the excentricity of the terrestrial orbit. Although the resistance of such a medium has not hitherto been perceived in the motions of such dense bodies as the planets and satellites, its effects on the revolutions of the two small periodic comets hardly leave a doubt of its existence From the numerous observations that have been made on each return of the comet of the short period, the elements have been computed with great accuracy on the hypothesis of its moving in vacuo. Its perturbations occasioned by the disturbing action of the planets have been determined, and after

every thing that could influence its motion had been duly considered, M. Encke found that an acceleration of about two days on each revolution has taken place in its mean motion, precisely similar to that which would be occasioned by the resistance of an etherial medium. And as it cannot be attributed to a cause like that which produces the acceleration of the moon, it must be concluded that the celestial bodies do not perform their revolutions in an absolute void, and that although the medium be too rare to have a sensible effect on the masses of the planets and satellites, it nevertheless has a considerable influence on so rare a body as a comet. Contradictory as it may seem, that the motion of a body should be accelerated by the resistance of an etherial medium, the truth becomes evident if it be considered that both planets and comets are retained in their orbits by two forces which exactly balance one another, namely, the centrifugal force producing the velocity in the tangent, and the attraction of the gravitating force directed to the centre of the sun. If one of these forces be diminished by any cause, the other will be proportionally increased Now, the necessary effect of a resisting medium is to diminish the tangential velocity, so that the balance is destroyed, gravity preponderates, the body descends towards the sun till equilibrium is again restored between the two forces; and as it then describes a smaller orbit, it moves with increased velocity. Thus, the resistance of an etherial medium actually accelerates the motion of a body, but as the resisting force is confined to the plane of the orbit, it has no influence whatever on the inclination of the orbit, or on the place of the nodes. The other comet belonging to our system, which returns to its perihelion after a period of 6¾ years, has been acceler-

ated in its motion by a whole day during its last revolution, which puts the existence of ether nearly beyond a doubt, and forms a strong presumption in corroboration of the undulating theory of light The comet in question was discovered by M Biela at Johannisberg on the 27th of February, 1826, and ten days afterwards it was seen by M Gambart at Marseilles, who computed its parabolic elements, and found that they agreed with those of the comets which had appeared in the years 1789 and 1795, whence he concluded them to be the same body moving in an ellipse, and accomplishing its revolution in 2460 days The perturbations of this comet were computed by M. Damoiseau, who predicted that it would cross the plane of the ecliptic on the 29th of October, 1832, a little before midnight, at a point nearly 18,484 miles within the earth's orbit; and as M. Olbers, of Bremen, in 1805, had determined the radius of the comet's head to be about 21,136 miles, it was evident that its nebulosity would envelope a portion of the earth's orbit, a circumstance which caused some alarm in France, from the notion that if any disturbing cause had delayed the arrival of the comet for one month, the earth must have passed through its head. M. Arago dispelled these fears by his excellent treatise on comets in the Annuaire of 1832, where he proves, that as the earth would never be nearer the comet than 24,800,000 British leagues, there could be no danger of collision.

The earth would fall to the sun in 64½ days, if it were struck by a comet with sufficient impetus to destroy its centrifugal force. What the earth's primitive velocity may have been it is impossible to say. Therefore a comet may have given it a shock without changing the

axis of rotation, but only destroying part of its tangential velocity, so as to diminish the size of the orbit, a thing by no means impossible, though highly improbable. At all events, there is no proof of this having occurred; and it is manifest that the axis of the earth's rotation has not been changed, because, as the ether offers no sensible resistance to so dense a body as the earth, the libration would to this day be evident in the variation it must have occasioned in the terrestrial latitudes. Supposing the nucleus of a comet to have a diameter only equal to the fourth part of that of the earth, and that its perihelion is nearer to the sun than we are ourselves, its orbit being otherwise unknown, M. Arago has computed that the probability of the earth receiving a shock from it is only one in 281 millions, and that the chance of our coming in contact with its nebulosity is about ten or twelve times greater. In general the substance of comets is so rare, that it is likely they would not do much harm if they were to impinge, and even then the mischief would probably be local, and the equilibrium soon restored, provided the nucleus were gaseous, or very small. It is, however, more probable that the earth would only be deflected a little from its course by the approach of a comet, without being touched by it. The comets that have come nearest to the earth were that of the year 837, which remained four days within less than 1,240,000 leagues from our orbit, that of 1770, which approached within about six times the distance of the moon. The celebrated comet of 1680 also came very near to us; and the comet whose period is $6\frac{3}{4}$ years was ten times nearer the earth in 1805 than in 1832, when it caused so much alarm.

Comets in or near their perihelion move with pro-

digious velocity. That of 1680 appears to have gone half round the sun in ten hours and a half, moving at the rate of 880,000 miles an hour. If its enormous centrifugal force had ceased when passing its perihelion, it would have fallen to the sun in about three minutes, as it was then only 147,000 miles from his surface. So near the sun, it would be exposed to a heat 27,500 times greater than that received by the earth; and as the sun's heat is supposed to be in proportion to the intensity of his light, it is probable that a degree of heat so very intense would be sufficient to convert into vapour every terrestrial substance with which we are acquainted. At the perihelion distance the sun's diameter would be seen from the comet under an angle of 73°, so that the sun, viewed from the comet, would nearly cover the whole extent of the heavens from the horizon to the zenith. As this comet is presumed to have a period of 575 years, the major axis of its orbit must be so great, that at the aphelion the sun's diameter would only subtend an angle of about fourteen seconds, which is not so great as half the diameter of Mars appears to us when in opposition. The sun would consequently impart no heat, so that the comet would then be exposed to the temperature of the ethereal regions, which is 58° below the zero point of Fahrenheit. A body of such tenuity as the comet, moving with such velocity, must have met with great resistance from the dense atmosphere of the sun, while passing so near his surface at its perihelion. The centrifugal force must consequently have been diminished, and the sun's attraction proportionally augmented, so that it must have come nearer to the sun in 1680 than in its preceding revolution, and would subsequently describe a smaller orbit. As this diminution of its orbit

will be repeated at each revolution, the comet will infallibly end by falling on the surface of the sun, unless its course be changed by the disturbing influence of some large body in the unknown expanse of creation Our ignorance of the actual density of the sun's atmosphere, of the density of the comet, and of the period of its revolution, renders it impossible to form any idea of the number of centuries which must elapse before this event takes place

But this is not the only comet threatened with such a catastrophe, Encke's, and that discovered by M Biela, are both slowly tending to the same fate. By the resistance of the ether, they will perform each revolution nearer and nearer to the sun, till at last they will be precipitated on his surface. The same cause may affect the motions of the planets, and ultimately be the means of destroying the solar system. But, as Sir John Herschel observes, they could hardly all revolve in the same direction round the sun for so many ages without impressing a corresponding motion on the ethereal fluid, which may preserve them from the accumulated effects of its resistance. Should this material fluid revolve about the sun like a vortex, it will accelerate the revolutions of such comets as have direct motions, and retard those that have retrograde motions

Though already so well acquainted with the motions of comets, we know nothing of their physical constitution. A vast number, especially of telescopic comets, are only like clouds or masses of vapour, often without tails. Such were the comets which appeared in the years 1795, 1797, and 1798 The head commonly consists of a mass of light, like a planet surrounded by a very transparent atmosphere, and the whole, viewed with a telescope, is so diaphanous, that the smallest

star may be seen even through the densest part of the nucleus; in general their masses, when they have any, are so minute, that they have no sensible diameter, like that of the comet of 1811, which appeared to Sir Wm. Herschel like a luminous point in the middle of the nebulous matter. The nuclei, which seem to be formed of the denser strata of that nebulous matter in successive coatings, are often of great magnitude. Those of the comets which came to the sun in the years 1799 and 1807 had nuclei whose diameters measured 180 and 275 leagues respectively, and the second comet of 1811 had a nucleus 1350 leagues in diameter.

The nebulosity immediately round the nucleus is so diaphonous that it gives little light, but at a small distance the nebulous matter becomes suddenly brilliant, so as to look like a bright ring round the body. Sometimes there are as many as two or three of these luminous concentric rings separated by dark intervals, but they are generally incomplete on the part next the tail. In the comet of 1811, the luminous ring was 12,400 leagues thick, and the distance between its interior surface and the centre of the nucleus was 14,880 leagues. The thickness of these bright diaphanous coatings in the comets of 1807 and 1799 were 14,880 and 9920 leagues respectively. The transit of a comet over the sun would afford the best information with regard to the nature of the nuclei. It was computed that such an event was to take place in the year 1827; unfortunately the sun was hid by clouds from the British astronomers, but it was examined at Viviers and at Marseilles, at the time the comet must have been projected on its disc, but no spot or cloud was to be seen.

The tails of comets proceed from the head in two streams of light, somewhat like that of the aurora

These in most cases unite at a greater or less distance from the nucleus, and are generally situate in the planes of their orbits They follow the comets in their descent towards the sun, but precede them in their return with a small degree of curvature, probably owing to the resistance of the ether, but their extent and form varies according to the positions of their orbits with regard to the ecliptic In some cases, the tail has been at right angles to the line joining the sun and comet They are generally of enormous lengths,—the comet of 1811 had a tail no less than 34 millions of leagues in length, and those which appeared in the years 1618, 1680, and 1769, had tails which extended respectively over 104, 90, and 97 degrees of space Consequently, when the heads of these comets were set, a portion of the extremity of their tails was still in the zenith. Sometimes the tail is divided into several branches, like the comet of 1744, which had six, separated by dark intervals, each of them about 4° broad, and from 30° to 44° long. The tails do not attain their full magnitude till the comet has left the sun. When these bodies first appear, they resemble round films of vapour with little or no tail. As they approach the sun, they increase in brilliancy, and their tail in length, till they are lost in his rays; and it is not till they emerge from the sun's more vivid light that they assume their full splendour. They then gradually decrease by the same degrees, their tails diminish and disappear nearly or altogether before the comet is beyond the sphere of telescopic vision Many comets have no tails, as, for example, Encke's comet and that discovered by M. Biela, both of which are small and insignificant objects The comets which appeared in the years 1585, 1763, and 1682, were also without tails, though the latter is

recorded to have been as bright as Jupiter. The matter of the tail must be extremely buoyant to precede a body moving with such velocity; indeed the rapidity of its ascent can only be accounted for by the fervent heat of the sun. Immediately after the great comet of 1680 had passed its perihelion, its tail was 20,000,000 leagues in length, and was projected from the comet's head in the short space of two days. A body of such extreme tenuity as a comet is most likely incapable of an attraction powerful enough to recall matter sent to such an enormous distance; it is, therefore, in all probability, scattered in space, which may account for the rapid decrease observed in the tails of comets every time they return to their perihelia.

It is remarkable that, although the tails of comets increase in length as they approach their perihelia, there is reason to believe that the real diameter of the nebulous matter, or nucleus, contracts on coming near the sun, and expands rapidly on leaving him. Hevelius first observed this phenomenon, which Encke's comet has exhibited in a very extraordinary degree. On the 28th of October, 1828, this comet was about three times as far from the sun as it was on the 24th of December, yet at the first date its apparent diameter was twenty-five times greater than at the second, the decrease being progressive. M. Valz attributes the circumstance to a real condensation of volume from the pressure of the ethereal medium, which increases most rapidly in density towards the surface of the sun, and forms an extensive atmosphere around him. Sir John Herschel, on the contrary, conjectures that it may be owing to the alternate conversion of evaporable materials in the upper regions of a transparent atmosphere into the states of visible cloud and invisible gas by the

effects of heat and cold. Not only the tails, but the nebulous part of comets diminishes every time they return to their perihelia; after frequent returns they ought to lose it altogether, and present the appearance of a fixed nucleus: this ought to happen sooner to comets of short periods. M. de la Place supposes that the comet of 1682 must be approaching rapidly to that state. Should the substances be altogether, or even to a great degree, evaporated, the comet would disappear for ever. Possibly comets may have vanished from our view sooner than they would otherwise have done from this cause.

In those positions of comets, where only half of their enlightened hemisphere could be seen if they shine by reflected light, they ought to exhibit phases; but even with high magnifying powers none have been detected, though some slight indications are said to have been once observed by Hevelius and La Hire in 1682. In general, the light of comets is dull,—that of the comet of 1811 was only equal to the tenth part of the light of the full moon; but some have been brilliant enough to be visible in full daylight, especially the comet of 1744, which was seen without a telescope at one o'clock in the afternoon, while the sun was shining. Hence it may be inferred that, although some comets may be altogether diaphanous, others seem to possess a solid mass resembling a planet. But whether they shine by their own or by reflected light has never been satisfactorily made out till now. Even if the light of a comet were polarised, it would not afford a decisive test, since a body is capable of reflecting light, though it shines by its own. M. Arago, however, has, with great ingenuity, discovered a method of ascertaining this point, independent both of phases and polarisation.

Since the rays of light diverge from a luminous point, they will be scattered over a greater space as the distance increases, so that the intensity of the light on a screen two feet from the object, is four times less than at the distance of one foot, three feet from the object it is nine times less, and so on, decreasing in intensity as the square of the distance increases. As a self-luminous surface consists of an infinite number of luminous points, it is clear that, the greater the extent of surface, the more intense will be the light; whence it may be concluded that the illuminating power of such a surface is proportional to its extent, and decreases inversely as the square of the distance. Notwithstanding this, a self-luminous surface, plane or curved, viewed through a hole in a plate of metal, is of the same brilliancy at all possible distances as long as it subtends a sensible angle, because, as the distance increases, a greater portion comes into view, and as the augmentation of surface is as the square of the diameter of the part seen through the hole, it increases as the square of the distance. Hence, though the number of rays from any one point of the surface which pass through the hole decrease inversely as the square of the distance, yet, as the extent of surface which comes into view increases also in that ratio, the brightness of the object is the same to the eye as long as it has a sensible diameter. For example — Uranus is about nineteen times farther from the sun than we are, so that the sun, seen from that planet, must appear like a star with a diameter of a hundred seconds, and must have the same brilliancy to the inhabitants, that he would have to us if viewed through a small circular hole having a diameter of a hundred seconds. For it is obvious, that light comes from every point of the sun's surface to Uranus, whereas a very

small portion of his disc is visible through the hole; so that extent of surface exactly compensates distance. Since, then, the visibility of a self-luminous object does not depend upon the angle it subtends as long as it is of sensible magnitude, if a comet shines by its own light, it should retain its brilliancy as long as its diameter is of a sensible magnitude; and even after it has lost an apparent diameter, it ought, like the fixed stars, to be visible, and should only vanish in consequence of extreme remoteness. That, however, is far from being the case — comets gradually become dim as their distance increases, and vanish merely from loss of light, while they still retain a sensible diameter, which is proved by observations made the evening before they disappear. It may, therefore, be concluded, that comets shine by reflecting the sun's light. The most brilliant comets have hitherto ceased to be visible when about five times as far from the sun as we are. Most of the comets that have been visible from the earth have their perihelia within the orbit of Mars, because they are invisible when as distant as the orbit of Saturn: on that account there is not one on record whose perihelion is situate beyond the orbit of Jupiter. Indeed, the comet of 1756, after its last appearance, remained five whole years within the ellipse described by Saturn without being once seen. A hundred and forty comets have appeared within the earth's orbit during the last century that have not again been seen. If a thousand years be allowed as the average period of each, it may be computed, by the theory of probabilities, that the whole number which range within the earth's orbit must be 1400; but Uranus being about nineteen times more distant, there may be no less than 11,200,000 comets that come within the known extent of our system. M.

Arago makes a different estimate: he considers that, as thirty comets are known to have their perihelion distance within the orbit of Mercury, if it be assumed that comets are uniformly distributed in space, the number having their perihelion within the orbit of Uranus must be to thirty as the cube of the radius of the orbit of Uranus to the cube of the radius of the orbit of Mercury, which makes the number of comets amount to 3,529,470. But that number may be doubled if it be considered that, in consequence of daylight, fogs, and great southern declination, one comet out of two must be hid from us. According to M. Arago, more than seven millions of comets frequent the planetary orbits.

SECTION XXXVI.

THE FIXED STARS.—THEIR NUMBERS.—ESTIMATION OF THEIR DISTANCES AND MAGNITUDES FROM THEIR LIGHT.—STARS THAT HAVE VANISHED.—NEW STARS.—DOUBLE STARS.—BINARY AND MULTIPLE SYSTEMS.—THEIR ORBITS AND PERIODS.—ORBITUAL AND PARALLACTIC MOTIONS.—COLOUR.—PROPER MOTIONS.—GENERAL MOTIONS OF ALL THE STARS.—CLUSTERS.—NEBULÆ.—THEIR NUMBER AND FORMS.—DOUBLE AND STELLAR NEBULÆ.—NEBULOUS STARS.—PLANETARY NEBULÆ.—CONSTITUTION OF THE NEBULÆ AND FORCES WHICH MAINTAIN THEM.—DISTRIBUTION.—METEORITES.

GREAT as the number of comets appears to be, it is absolutely nothing when compared to the number of the fixed stars. About 2000 only are visible to the naked eye; but when we view the heavens with a telescope, their number seems to be limited only by the imperfection of the instrument. In one hour Sir William Herschel estimated that 50,000 stars passed through the field of his telescope, in a zone of the heavens 2° in breadth. This, however, was stated as an instance of extraordinary crowding; but, on an average, the whole expanse of the heavens must exhibit about a hundred millions of fixed stars within the reach of telescopic vision.

The stars are classed according to their apparent brightness, and the places of the most remarkable of those visible to the naked eye are ascertained with great precision, and formed into a catalogue, not only for the determination of geographical positions by their occultations, but to serve as points of reference for marking the places of comets and other celestial phenomena.

The whole number of stars registered amounts to about 15,000 or 20,000. The distance of the fixed stars is too great to admit of their exhibiting a sensible disc; but, in all probability, they are spherical, and must certainly be so if gravitation pervades all space, which it may be presumed to do, since Sir John Herschel has shown that it extends to the binary systems of stars. With a fine telescope the stars appear like a point of light, their occultations by the moon are therefore instantaneous. Their twinkling arises from sudden changes in the refractive power of the air, which would not be sensible if they had discs like the planets. Thus we can learn nothing of the relative distances of the stars from us and from one another by their apparent diameters. Their annual parallax being insensible, shows that we must be one hundred millions of millions of miles at least from the nearest. Many of them, however, must be vastly more remote, for of two stars that appear close together, one may be far beyond the other in the depth of space. The light of Sirius, according to the observations of Sir John Herschel, is 324 times greater than that of a star of the sixth magnitude; if we suppose the two to be really of the same size, their distances from us must be in the ratio of 57·3 to 1, because light diminishes as the square of the distance of the luminous body increases.

Nothing is known of the absolute magnitude of the fixed stars, but the quantity of light emitted by many of them shows that they must be much larger than the sun. Dr. Wollaston determined the approximate ratio which the light of a wax candle bears to that of the sun, moon, and stars, by comparing their respective images, reflected from small glass globes filled with mercury, whence a comparison was established between the quan-

tities of light emitted by the celestial bodies themselves. By this method he found that the light of the sun is about twenty millions of millions of times greater than that of Sirius, the brightest, and supposed to be the nearest of the fixed stars If the parallax of Sirius were but half a second, its distance from the earth would be 525,481 times the distance of the sun from the earth, and therefore Sirius, placed where the sun is, would appear to us to be 3 7 times as large as the sun, and would give 13 8 times more light. Many of the fixed stars must be infinitely larger than Sirius.

Many stars have vanished from the heavens, the star 42 Virginis seems to be of this number, having been missed by Sir John Herschel on the 9th of May, 1828, and not again found, though he frequently had occasion to observe that part of the heavens. Sometimes stars have all at once appeared, shone with a bright light, and vanished. Several instances of these temporary stars are on record, a remarkable instance occurred in the year 125, which is said to have induced Hipparchus to form the first catalogue of stars. Another star appeared suddenly near α Aquilæ in the year 389, which vanished after remaining for three weeks as bright as Venus. On the 10th of October, 1604, a brilliant star burst forth in the constellation of Serpentarius, which continued visible for a year, and a more recent case occurred in the year 1670, when a new star was discovered in the head of the Swan, which, after becoming invisible, reappeared, and having undergone many variations in light vanished after two years, and has never since been seen In 1572, a star was discovered in Cassiopeia, which rapidly increased in brightness till it even surpassed that of Jupiter; it then gradually diminished in splendour, and having exhibited

all the variety of tints that indicate the changes of combustion, vanished sixteen months after its discovery without altering its position. It is impossible to imagine any thing more tremendous than a conflagration that could be visible at such a distance. It is, however, suspected that this star may be periodical and identical with the stars which appeared in the years 945 and 1264. There are probably many stars which alternately vanish and reappear among the innumerable multitudes that spangle the heavens, the periods of thirteen have already been pretty well ascertained. Of these the most remarkable is the star Omicron in the constellation Cetus. It appears about twelve times in eleven years, and is of variable brightness, sometimes appearing like a star of the second magnitude; but it does not always attain the same lustre, nor does it increase or diminish by the same degrees. According to Hevelius, it did not appear at all for four years. γ Hydræ also vanishes and reappears every 494 days, and a very singular instance of periodicity is given by Sir John Herschel in the star Algol or β Persei, which is described as retaining the size of a star of the second magnitude for two days and fourteen seconds; it then suddenly begins to diminish in splendour, and in about three hours and a half is reduced to the size of a star of the fourth magnitude; it then begins again to increase, and in three hours and a half more regains its usual brightness, going through all these vicissitudes in two days, twenty hours, and forty-eight minutes. The cause of the variations in most of the periodical stars is unknown, but, from the changes of Algol, M. Goodricke has conjectured that they may be occasioned by the revolution of some opaque body, coming between us and the star, and obstructing part of its light. Sir John Herschel is

struck with the high degree of activity evinced by these changes in regions where, "but for such evidences, we might conclude all to be lifeless." He observes that our own sun requires nine times the period of Algol to perform a revolution on its own axis; while, on the other hand, the periodic time of an opaque revolving body sufficiently large to produce a similar temporary obscuration of the sun, seen from a fixed star, would be less than fourteen hours.

Many thousands of stars that seem to be only brilliant points, when carefully examined are found to be in reality systems of two or more suns, some revolving about a common centre. These binary and multiple stars are extremely remote, requiring the most powerful telescopes to show them separately. The first catalogue of double stars, in which their places and relative positions are determined, was accomplished by the talents and industry of Sir William Herschel, to whom astronomy is indebted for so many brilliant discoveries, and with whom the idea of their combination in binary and multiple systems originated—an idea completely established by his own observations, and recently confirmed by those of his son. The motions of revolution of many of these stars round a common centre have been ascertained, and their periods determined with considerable accuracy. Some have, since their first discovery, already accomplished nearly a whole revolution, and one, η Coronæ, is actually considerably advanced in its second period. These interesting systems thus present a species of sidereal chronometer, by which the chronology of the heavens will be marked out to future ages by epochs of their own, liable to no fluctuations from such planetary disturbances as take place in our system.

In observing the relative position of the stars of a

binary system, the distance between them, and also the angle of position, that is, the angle which the meridian or a parallel to the equator makes with the line joining the two stars, are measured. The different values of the angle of position shows whether the revolving star moves from east to west or the contrary; whether the motion be uniform or variable, and at what points it is greatest or least. The measures of the distances show whether the two stars approach or recede from one another. From these the form and nature of the orbit are determined. Were observations perfectly accurate, four values of the angle of position and of the corresponding distances at given epochs would be sufficient to assign the form and position of the curve described by the revolving star; this, however, scarcely ever happens. The accuracy of each result depends upon taking the mean of a great number of the best observations, and eliminating error by mutual comparison. The distances between the stars are so minute that they cannot be measured with the same accuracy as the angles of position; therefore, to determine the orbit of a star independently of the distance, it is necessary to assume, as the most probable hypothesis, that the stars are subject to the law of gravitation, and consequently, that one of the two stars revolves in an ellipse about the other, supposed to be at rest, though not necessarily in the focus. A curve is thus constructed graphically by means of the angles of position and the corresponding times of observation. The angular velocities of the stars are obtained by drawing tangents to this curve at stated intervals, whence the apparent distances, or radii vectores, of the revolving star become known for each angle of position; because, by the laws of elliptical motion, they are equal to the square roots of the appa-

rent angular velocities. Now that the angles of position estimated from a given line, and the corresponding distances of the two stars, are known, another curve may be drawn, which will represent on paper the actual orbit of the star projected on the visible surface of the heavens, so that the elliptical elements of the true orbit and its position in space may be determined by a combined system of measurements and computation. But as this orbit has been obtained on the hypothesis that gravitation prevails in those distant regions, which could not be known *a priori*, it must be compared with as many observations as can be obtained, to ascertain how far the computed ellipse agrees with the curve actually described by the star

By this process Sir John Herschel has discovered that several of these systems of stars are subject to the same laws of motion with our system of planets he has determined the elements of their elliptical orbits, and computed the periods of their revolution. One of the stars of γ Virginis revolves about the other in 629 years, the periodic time of σ Coronæ is 287 years; that of Castor is 258 years, that of ϵ Bootes is 1600, that of 70 Ophiuchi is ascertained by Professor Encke to be 80 years, and M. Savary, who has the merit of having first determined the elliptical elements of the orbit of a binary star from observation, has shown that the revolution of ξ Ursæ is completed in 58 years. γ Virginis consists of two stars of nearly the same magnitude They were so far apart in the beginning and middle of the last century, that they were mentioned by Bradley and marked in Mayer's catalogue as two distinct stars. Now, they are so near to one another, that even with good telescopes they look like a single star somewhat elongated. A series of observ-

ations, since the beginning of the present century, has enabled Sir John Herschel to determine the form and position of the elliptical orbit of the revolving star with extraordinary truth. According to his computation, it must have arrived at its perihelion on the 18th of August of the present year, 1834. The actual proximity of the two stars must then have been extreme, and the apparent angular velocity so great that it may describe an angle of 68° in a single year. Observations made at the Cape of Good Hope, last May, by Sir John Herschel, as well as those of Captain Smyth, R. N., at home, correspond in proving an augmentation of velocity as the star was approaching its shortest distance from its primary. By the laws of elliptical motion, the angular velocity of the revolving star must now gradually diminish, till it comes to its aphelion some 314 years hence. The satellite star of σ Coronæ will attain its perihelion about 1835, and that of Castor some time in 1855.

It sometimes happens that the edge of the orbit of a revolving star is presented to the earth, as in ω Serpentarii. Then the star seems to move in a straight line, and to oscillate on each side of its primary. Five observations are requisite in this case for the determination of its orbit, provided they be accurate. At the time Sir William Herschel observed the system in question, the two stars were distinctly separate; at present, one is so completely projected on the other, that M. Struve, with his great telescope, cannot perceive the smallest separation. On the contrary, the two stars of ζ Orionis, which appeared to be one in the time of Sir William Herschel, are now separated. Were this libration owing to parallax, it would be annual, from the revolution of the earth; but as years elapse before it

amounts to a sensible quantity, it can only arise from a real orbitual motion seen obliquely. Among the triple stars, two of the stars of ζ Cancri revolve about the third. It is remarked that, in general, the ellipses in which the revolving stars of the binary systems move, are much more elongated than the orbits of the planets. Sir John Herschel, Sir James South, and Professor Struve of Dorpat, have increased Sir William Herschel's original catalogue of double stars to more than 3000, of which thirty or forty are known to form revolving or binary systems, and Mr. Dunlop has formed a catalogue of 253 double stars in the southern hemisphere. The motion of Mercury is more rapid than that of any other planet, being at the rate of 107,000 miles an hour; the perihelion velocity of the comet of 1680 was no less than 880,000 miles an hour; but if the two stars of ξ Ursæ be as remote from one another as the nearest fixed star is from the sun, the velocity of the revolving stars must exceed the powers of imagination. The discovery of the elliptical motion of the double stars excites the highest interest, since it shows that gravitation is not peculiar to our system of planets, but that systems of suns in the far distant regions of the universe are also obedient to its laws.

Possibly, among the multitudes of small stars, whether double or insulated, some may be found near enough to exhibit distinct parallactic motions, arising from the revolution of the earth in its orbit. Of two stars apparently in close approximation, one may be far behind the other in space. These may seem near to one another when viewed from the earth in one part of its orbit, but may separate widely when seen from the earth in another position, just as two terrestrial objects appear to be one when viewed in the same straight line,

but separate as the observer changes his position. In this case the stars would not have real, but only apparent, motion One of them would seem to oscillate annually to and fro in a straight line on each side of the other—a motion which could not be mistaken for that of a binary system, where one star describes an ellipse about the other, or if the edge of the orbit be turned towards the earth, where the oscillations require years for their accomplishment Such parallax does not yet appear to have been made out, so that the actual distance of the stars is still a matter of conjecture

The double stars are of various hues, but most frequently exhibit the contrasted colours. The large star is generally yellow, orange, or red, and the small star blue, purple, or green. Sometimes a white star is combined with a blue or purple, and more rarely a red and white are united. In many cases, these appearances are due to the influence of contrast on our judgment of colours For example, in observing a double star, where the large one is a full ruby red, or almost blood colour, and the small one a fine green, the latter loses its colour when the former is hid by the cross wires of the telescope But there are a vast number of instances where the colours are too strongly marked to be merely imaginary. Sir John Herschel observes, in one of his papers in the Philosophical Transactions, as a very remarkable fact, that, although red stars are common enough, no example of a solitary blue, green, or purple one has yet been produced.

Besides revolutions about one another, some of the binary systems are carried forward in space by a motion common to both stars, towards some unknown point in the firmament. The two stars of 61 Cygni, which are

nearly equal, and have remained at the distance of about $15''$ from each other for fifty years, have changed their place in the heavens during that period, by $4' 23''$, with a motion which for ages must appear uniform and rectilinear because, even if the path be curved, so small a portion of it, must appear a straight line to us. Multitudes of the single stars also have proper motions, yet so minute, that that of μ Cassiopeiæ, which is only $3''.74$ annually, is the greatest yet observed: the enormous distances of the stars make motions appear small to us, which are in reality very great. Sir William Herschel conceived that, among many irregularities, the motions of the stars have a general tendency towards a point diametrically opposite to that occupied by the star ζ Herculis, which he attributed to a motion of the solar system in the contrary direction. Should this really be the case, the stars, from the effects of perspective alone, would seem to diverge in the direction to which we are tending, and would apparently converge in the space we leave, and there would be a regularity in these apparent motions which would in time be detected; but if the solar system and the whole of the stars visible to us be carried forward in space by a motion common to all, like ships drifting in a current, it would be impossible for us, moving with the rest, to ascertain its direction. There can be no doubt of the progressive motion of the sun and many of the stars, but sidereal astronomy is not far enough advanced to determine what relations these bear to one another.

The stars are scattered very irregularly over the firmament. In some places they are crowded together, in others thinly dispersed. A few groups more closely condensed form very beautiful objects even to the naked eye, of which the Pleiades and the constellation Coma

Berenices are the most striking examples; but the greater number of these clusters of stars appear to unassisted vision like thin white clouds or vapours: such is the milky way, which, as Sir William Herschel has proved, derives its brightness from the diffused light of the myriads of stars that form it. Most of them are extremely small, on account of their enormous distances, and they are so numerous, that, according to his estimation, no fewer than 50,000 passed through the field of his telescope in the course of one hour in a zone 2° broad. This singular portion of the heavens, constituting part of our firmament, consists of an extensive stratum of stars, whose thickness is small compared with its length and breadth; the earth is placed about midway between its two surfaces, near the point where it diverges into two branches. Many clusters of stars appear like white clouds, or round comets without tails, either to unassisted vision or with ordinary telescopes; but, seen with powerful instruments, Sir John Herschel describes them as conveying the idea of a globular space filled full of stars insulated in the heavens, and constituting a family or society apart from the rest, subject only to its own internal laws. To attempt to count the stars in one of these globular clusters, he says, would be a vain task,—that they are not to be reckoned by hundreds,—and, on a rough computation, it appears that many clusters of this description must contain ten or twenty thousand stars compacted and wedged together in a round space, whose area is not more than a tenth part of that covered by the moon; so that its centre, where the stars are seen projected on each other, is one blaze of light.[1] If each of these stars be a sun, and if they be separated by intervals equal to that which sepa-

[1] Note 217.

rates our sun from the nearest fixed star, the distance which renders the whole cluster barely visible to the naked eye must be so great, that the existence of this splendid assemblage can only be known to us by light which must have left it at least a thousand years ago Occasionally these clusters are so irregular and so undefined in their outline, as merely to suggest the idea of a richer part of the heavens They contain fewer stars than the globular clusters, and sometimes a red star forms a conspicuous object among them These Sir William Herschel regarded as the rudiments of globular clusters in a less advanced state of condensation, but tending to that form by their mutual attraction

Multitudes of nebulous spots are to be seen on the clear vault of heaven which have every appearance of being clusters like those described, but are too distant to be resolved into stars by the most excellent telescopes This nebulous matter exists in vast abundance in space No fewer than 2000 nebulæ and clusters of stars were observed by Sir William Herschel, whose places have been computed from his observations, reduced to a common epoch, and arranged into a catalogue in order of right ascension by his sister, Miss Caroline Herschel, a lady so justly eminent for astronomical knowledge and discovery. Six or seven hundred nebulæ have already been ascertained in the southern hemisphere, of these the Magellanic clouds are the most remarkable. The nature and use of this matter, scattered over the heavens in such a variety of forms, is involved in the greatest obscurity That it is a self-luminous, phosphorescent, material substance, in a highly dilated or gaseous state, but gradually subsiding by the mutual gravitation of its particles into stars and sidereal systems, is the hypothesis most generally received. But the only way that

any real knowledge on this mysterious subject can be obtained, is by the determination of the form, place, and present state of each individual nebula; and a comparison of these with future observations will show generations to come, the changes that may now be going on in these supposed rudiments of future systems. With this view, Sir John Herschel began in the year 1825 the arduous and pious task of revising his illustrious father's observations, which he finished a short time before he sailed for the Cape of Good Hope, in order to disclose the mysteries of the southern hemisphere. Indeed, our firmament seems to be exhausted till farther improvements in the telescope shall enable astronomers to penetrate deeper into space. In a truly splendid paper read before the Royal Society on the 21st of November, 1833, he gives the places of 2500 nebulæ and clusters of stars. Of these 500 are new, the rest he mentions with peculiar pleasure as having been most accurately determined by his father. This work is the more extraordinary, as, from bad weather, fogs, twilight, and moonlight, these shadowy appearances are not visible, on an average, above thirty nights in the year.

The nebulæ have great variety of forms. Vast multitudes are so faint as to be with difficulty discerned at all till they have been for some time in the field of the telescope, or are just about to quit it. Many present a large ill-defined surface, in which it is difficult to say where the centre of the greatest brightness is. Some cling to stars like wisps of cloud; others exhibit the wonderful appearance of an enormous flat ring seen very obliquely, with a lenticular vacancy in the centre.[1] A very remarkable instance of an annular nebula is to

[1] Note 214.

be seen exactly half-way between β and γ Lyræ It is elliptical in the ratio of 4 to 5, is sharply defined, the internal opening occupying about half the diameter. This opening is not entirely dark, but filled up with a faint hazy light, aptly compared by Sir John Herschel to fine gauze stretched over a hoop.[1] Two are described as most amazing objects —One like a dumb-bell or hour-glass of bright matter, surrounded by a thin hazy atmosphere, so as to give the whole an oval form, or the appearance of an oblate spheroid This phenomenon bears no resemblance to any known object [2] The other consists of a bright round nucleus, surrounded at a distance by a nebulous ring split through half its circumference, and having the split portions separated at an angle of 45° each to the plane of the other. This nebula bears a strong similitude to the milky way, and suggested to Sir John Herschel the idea of a "brother system bearing a real physical resemblance and strong analogy of structure to our own."[3] It appears that double nebulæ are not unfrequent, exhibiting all the varieties of distance, position, and relative brightness with their counterparts the double stars. The rarity of single nebulæ as large, faint, and as little condensed in the centre as these, makes it extremely improbable that two such bodies should be accidentally so near as to touch, and often in part to overlap each other as these do. It is much more likely that they constitute systems; and if so, it will form an interesting subject of future enquiry to discover whether they possess orbitual motion.

Stellar nebulæ form another class. These have a round or oval shape, increasing in density towards the centre Sometimes the matter is so rapidly condensed

[1] Note 219 [2] Note 220 [3] Note 221

as to give the whole the appearance of a star with a blur, or like a candle shining through horn. In some instances the central matter is so highly and suddenly condensed, so vivid and sharply defined, that the nebula might be taken for a bright star surrounded by a thin atmosphere. Such are nebulous stars. The zodiacal light, or lenticular-shaped atmosphere of the sun, which may be seen extending beyond the orbits of Mercury and Venus soon after sunset in the months of April and May, is supposed to be a condensation of the ethereal medium by his attractive force, and seems to place our sun among the class of stellar nebulæ. The stellar nebulæ and nebulous stars assume all degrees of ellipticity. Not unfrequently they are long and narrow, like a spindle-shaped ray, with a bright nucleus in the centre.[1] The last class mentioned by Sir John Herschel are the planetary nebulæ. These bodies have exactly the appearance of planets, with sensibly round or oval discs, sometimes sharply terminated, at other times hazy and ill defined. Their surface, which is blue or bluish-white, is equable or slightly mottled, and their light occasionally rivals that of the planets in vividness. They are generally attended by minute stars, which give the idea of accompanying satellites. These nebulæ are of enormous dimensions. One of them, near ν Aquarii, has a sensible diameter of about 20″, and another presents a diameter of 12″. Sir John Herschel has computed that, if these objects be as far from us as the stars, their real magnitude, on the lowest estimation, must be such as would fill the orbit of Uranus. He concludes that, if they be solid bodies of a solar nature, their intrinsic splendour must be greatly inferior to that of the sun, because a circular portion of the sun's disc,

1 Note [illegible].

subtending an angle of 20″, would give a light equal to that of a hundred full moons, while, on the contrary, the objects in question are hardly, if at all, visible to the naked eye From the uniformity of the discs of the planetary nebulæ, and their want of apparent condensation, he presumes that they may be hollow shells, only emitting light from their surfaces.

The existence of every degree of ellipticity in the nebulæ—from long lenticular rays to the exact circular form,—and of every shade of central condensation—from the slighest increase of density to apparently a solid nucleus,—may be accounted for by supposing the general constitution of these nebulæ to be that of oblate spheroidal masses of every degree of flatness, from the sphere to the disc, and of every variety in their density and ellipticity towards the centre It would be erroneous however to imagine, that the forms of these systems are maintained by forces identical with those already described, which determine the form of a fluid mass in rotation; because, if the nebulæ be only clusters of separate stars, as in the greater number of cases there is every reason to believe them to be, no pressure can be propagated through them. Consequently, since no general rotation of such a system as one mass can be supposed, it may be conceived to be a quiescent form, comprising within its limits an indefinite multitude of stars, each of which may be moving in an orbit about the common centre of the whole, in virtue of a law of internal gravitation resulting from the compound gravitation of all its parts Sir John Herschel has proved that the existence of such a system is not inconsistent with the law of gravitation under certain conditions

The distribution of the nebulæ over the heavens is

even more irregular than that of the stars. In some places they are so crowded together as scarcely to allow one to pass through the field of the telescope before another appears, while in other parts hours elapse without a single nebula occurring. They are in general only to be seen with the very best telescopes, and are most abundant in a zone whose general direction is not far from the hour circles 0^h and 12^h, and which crosses the milky way nearly at right angles. Where that zone crosses the constellations Virgo, Coma Berenices, and the Great Bear, they are to be found in multitudes.

Such is a brief account of the discoveries contained in Sir John Herschel's paper, which, for sublimity of views and patient investigation, has not been surpassed. To him and to Sir William Herschel we owe almost all that is known of sidereal astronomy; and in the inimitable works of that highly gifted father and son, the reader will find this subject treated of in a style altogether worthy of it, and of them.

So numerous are the objects which meet our view in the heavens, that we cannot imagine a part of space where some light would not strike the eye;—innumerable stars, thousands of double and multiple systems, clusters in one blaze with their tens of thousands of stars, and the nebulæ amazing us by the strangeness of their forms and the incomprehensibility of their nature, till at last, from the limit of our senses, even these thin and airy phantoms vanish in the distance. If such remote bodies shone by reflected light, we should be unconscious of their existence. Each star must then be a sun, and may be presumed to have its system of planets, satellites, and comets, like our own; and, for aught we know, myriads of bodies may be wandering in

space unseen by us, of whose nature we can form no idea, and still less of the part they perform in the economy of the universe Nor is this an unwarranted presumption, many such do come within the sphere of the earth's attraction, are ignited by the velocity with which they pass through the atmosphere, and are precipitated with great violence on the earth The fall of meteoric stones is much more frequent than is generally believed Hardly a year passes without some instances occurring, and if it be considered that only a small part of the earth is inhabited, it may be presumed that numbers fall in the ocean, or on the uninhabited part of the land, unseen by man They are sometimes of great magnitude, the volume of several has exceeded that of the planet Ceres, which is about 70 miles in diameter One which passed within 25 miles of us was estimated to weigh about 600,000 tons, and to move with a velocity of about 20 miles in a second, — a fragment of it alone reached the earth. The obliquity of the descent of meteorites, the peculiar substances they are composed of, and the explosion accompanying their fall, show that they are foreign to our system Luminous spots, altogether independent of the phases, have occasionally appeared on the dark part of the moon, these have been ascribed to the light arising from the eruption of volcanos, whence it has been supposed that meteorites have been projected from the moon by the impetus of volcanic eruption It has even been computed, that if a stone were projected from the moon in a vertical line, with an initial velocity of 10,992 feet in a second, — more than four times the velocity of a ball when first discharged from a cannon, — instead of falling back to the moon by the attraction of gravity, it would come within the sphere of the earth's attraction, and revolve

about it like a satellite. These bodies, impelled either by the direction of the primitive impulse, or by the disturbing action of the sun, might ultimately penetrate the earth's atmosphere, and arrive at its surface. But from whatever source meteoric stones may come, it seems highly probable that they have a common origin, from the uniformity—we may almost say identity—of their chemical composition.

SECTION XXXVII.

DIFFUSION OF MATTER THROUGH SPACE. — GRAVITATION — ITS VELOCITY — SIMPLICITY OF ITS LAW — GRAVITATION INDEPENDENT OF THE MAGNITUDE AND DISTANCES OF THE BODIES. — NOT IMPEDED BY THE INTERVENTION OF ANY SUBSTANCE. — ITS INTENSITY INVARIABLE — GENERAL LAWS — RECAPITULATION AND CONCLUSION

THE known quantity of matter bears a very small proportion to the immensity of space. Large as the bodies are, the distances which separate them are immeasurably greater; but as design is manifest in every part of creation, it is probable, that if the various systems in the universe had been nearer to one another, their mutual disturbances would have been inconsistent with the harmony and stability of the whole. It is clear that space is not pervaded by atmospheric air, since its resistance would, long ere this, have destroyed the velocity of the planets, neither can we affirm it to be a void, since it seems to be replete with ether, and traversed in all directions by light, heat, gravitation, and possibly by influences whereof we can form no idea.

Whatever the laws may be that obtain in the more distant regions of creation, we are assured that one alone regulates the motions, not only of our own system, but also the binary systems of the fixed stars, and as general laws form the ultimate object of philosophical research, we cannot conclude these remarks without considering the nature of gravitation — that extraordinary power, whose effects we have been endeavouring to trace through some of their mazes. It was at one

time imagined that the acceleration in the moon's mean motion was occasioned by the successive transmission of the gravitating force. It has been proved, that in order to produce this effect, its velocity must be about fifty millions of times greater than that of light, which flies at the rate of 200,000 miles in a second. Its action, even at the distance of the sun, may therefore be regarded as instantaneous; yet so remote are the nearest of the fixed stars, that it may be doubted whether the sun has any sensible influence on them.

The curves in which the celestial bodies move by the force of gravitation are only lines of the second order. The attraction of spheroids, according to any other law of force than that of gravitation, would be much more complicated; and as it is easy to prove that matter might have been moved according to an infinite variety of laws, it may be concluded that gravitation must have been selected by Divine Wisdom out of an infinity of others, as being the most simple, and that which gives the greatest stability to the celestial motions.

It is a singular result of the simplicity of the laws of nature, which admit only of the observation and comparison of ratios, that the gravitation and theory of the motions of the celestial bodies are independent of their absolute magnitudes and distances. Consequently, if all the bodies of the solar system, their mutual distances, and their velocities, were to diminish proportionally, they would describe curves in all respects similar to those in which they now move; and the system might be successively reduced to the smallest sensible dimensions, and still exhibit the same appearances. We learn by experience that a very different law of attraction prevails when the particles of matter

are placed within inappreciable distances from each other, as in chemical and capillary attraction and the attraction of cohesion. Whether it be a modification of gravity, or that some new and unknown power comes into action, does not appear. But as a change in the law of the force takes place at one end of the scale, it is possible that gravitation may not remain the same throughout every part of space. Perhaps the day may come, when even gravitation, no longer regarded as an ultimate principle, may be resolved into a yet more general cause, embracing every law that regulates the material world.

The action of the gravitating force is not impeded by the intervention even of the densest substances. If the attraction of the sun for the centre of the earth, and of the hemisphere diametrically opposite to him, were diminished by a difficulty in penetrating the interposed matter, the tides would be more obviously affected. Its attraction is the same also, whatever the substances of the celestial bodies may be; for if the action of the sun upon the earth differed by a millionth part from his action upon the moon, the difference would occasion a periodical variation in the moon's parallax, whose maximum would be the $\frac{1}{15}$ of a second, and also a variation in her longitude amounting to several seconds; a supposition proved to be impossible, by the agreement of theory with observation. Thus all matter is pervious to gravitation, and is equally attracted by it.

As far as human knowledge extends, the intensity of gravitation has never varied within the limits of the solar system; nor does even analogy lead us to expect that it should; on the contrary, there is every reason to be assured that the great laws of the universe are

immutable, like their Author. Not only the sun and planets, but the minutest particles, in all the varieties of their attractions and repulsions,—nay, even the imponderable matter of the electric, galvanic, or magnetic fluid,—are all obedient to permanent laws, though we may not be able in every case to resolve their phenomena into general principles. Nor can we suppose the structure of the globe alone to be exempt from the universal fiat, though ages may pass before the changes it has undergone, or that are now in progress, can be referred to existing causes with the same certainty with which the motions of the planets, and all their periodic and secular variations, are referable to the law of gravitation. The traces of extreme antiquity perpetually occurring to the geologist, give that information as to the origin of things, in vain looked for in the other parts of the universe. They date the beginning of time with regard to our system, since there is ground to believe that the formation of the earth was contemporaneous with that of the rest of the planets; but they show that creation is the work of Him with whom "a thousand years are as one day, and one day as a thousand years."

In the work now brought to a conclusion, it has been necessary to select from the whole circle of the sciences a few of the most obvious of those proximate links which connect them together, and to pass over innumerable cases both of evident and occult alliance. Any one branch traced through its ramifications would have alone occupied a volume; it is hoped, nevertheless, that the view here given will suffice to show the extent, to which a consideration of the reciprocal influence of even a few of these subjects may ultimately lead. It thus appears that the theory of dynamics,

founded upon terrestrial phenomena, is indispensable for acquiring a knowledge of the revolutions of the celestial bodies and their reciprocal influences. The motions of the satellites are affected by the forms of their primaries, and the figures of the planets themselves depend upon their rotations. The symmetry of their internal structure proves the stability of these rotatory motions, and the immutability of the length of the day, which furnishes an invariable standard of time; and the actual size of the terrestrial spheroid affords the means of ascertaining the dimensions of the solar system, and provides an invariable foundation for a system of weights and measures. The mutual attraction of the celestial bodies disturbs the fluids at their surfaces, whence the theory of the tides and the oscillations of the atmosphere. The density and elasticity of the air, varying with every alternation of temperature, lead to the consideration of barometrical changes, the measurement of heights, and capillary attraction; and the doctrine of sound, including the theory of music, is to be referred to the small undulations of the aerial medium. A knowledge of the action of matter upon light is requisite for tracing the curved path of its rays through the atmosphere, by which the true places of distant objects are determined, whether in the heavens or on the earth. By this we learn the nature and properties of the sunbeam, the mode of its propagation through the ethereal fluid, or in the interior of material bodies, and the origin of colour. By the eclipses of Jupiter's satellites, the velocity of light is ascertained, and that velocity, in the aberration of the fixed stars, furnishes the only direct proof of the real motion of the earth. The effects of the invisible rays of light are immediately con-

nected with chemical action, and heat, forming a part of the solar ray, so essential to animated and inanimated existence, whether considered as invisible light or as a distinct quality, is too important an agent in the economy of creation, not to hold a principal place in the connection of physical sciences Whence follows its distribution in the interior, and over the surface of the globe, its power on the geological convulsions of our planet, its influence on the atmosphere and on climate, and its effects on vegetable and animal life, evinced in the localities of organised beings on the earth, in the waters, and in the air. The connection of heat with electrical phenomena, and the electricity of the atmosphere, together with all its energetic effects, its identity with magnetism and the phenomena of terrestrial polarity, can only be understood from the theories of these invisible agents, and are, probably, principal causes of chemical affinities Innumerable instances might be given in illustration of the immediate connection of the physical sciences, most of which are united still more closely by the common bond of analysis, which is daily extending its empire, and will ultimately embrace almost every subject in nature in its formulæ.

These formulæ, emblematic of Omniscience, condense into a few symbols the immutable laws of the universe This mighty instrument of human power, itself originates in the primitive constitution of the human mind, and rests upon a few fundamental axioms, which have eternally existed in Him who implanted them in the breast of man when he created him after His own image

SUPPLEMENT.

Since the preceding sheets were printed, M. Melloni has published an account of his discoveries in the instantaneous transmission of radiant heat, which are so important and interesting, as to justify a fuller statement of them than has been given in the text. Rays of heat dart in straight lines from flame and all hot bodies. Their transmission through solid and liquid substances is instantaneous, there being no appreciable difference in the time they take to pass through layers of any nature or thickness whatever. They pass also with the same facility, whether the media be agitated or at rest, and in these respects the analogy between light and heat is perfect. The transmission of this kind of heat through various bodies, forms the subject of M. Melloni's experiments. The instrument he employs for measuring the intensity of the caloric, is a thermo-electric pile, formed of slender rods of bismuth and antimony, soldered together. When heat is applied to this apparatus, electricity is evolved, whose intensity, and consequently that of the heat producing it, is marked by a galvanometer, to which the electricity is conveyed by wires. Radiant heat passes, in different quantities, through a certain class of solid and liquid substances; but the transmissive power is totally

independent of transparency, some substances which are nearly opaque giving a free passage to the calorific rays, whilst others, altogether limpid, exclude the greater part of them For example, thin and perfectly transparent plates of alum and citric acid sensibly transmit all the rays of light from an argand lamp, but stop eight or nine tenths of the concomitant heat, whilst a large piece of brown rock crystal gives a free passage to the radiant heat, but intercepts almost all the light M. Melloni has established the general law in uncrystallised substances, such as glass and liquids, that the property of instantaneously transmitting heat is in proportion to their refractive powers. The law, however, is entirely at fault in bodies of a crystalline texture Carbonate of lead, for instance, which is colourless, and possesses a very high refractive power with regard to light, transmits less radiant heat than Iceland spar, or rock crystal, which are very inferior to it in the order of refrangibility, whilst rock salt, which has the same transparency and refractive power with alum and citric acid, transmits six or eight times as much caloric This remarkable difference in the transmissive power of substances having the same appearance, is attributed by M Melloni to their crystalline form, and not to the chemical composition of their molecules, as the following experiments prove A block of common salt, cut into plates, entirely excludes calorific radiation, yet when dissolved in water it increases the transmissive power of that liquid moreover, the transmissive power of water is increased in nearly the same degree, whether salt or alum be dissolved in it, yet these two substances transmit very different quantities of heat in their solid state But, notwithstanding the influence of crystal-

lization on the transmissive power of bodies, no relation has been traced between that power and their crystalline form. The transmission of radiant heat is analogous to that of light through coloured media. When common white light, consisting of blue, yellow, and red rays, passes through a red liquid, almost all the blue and yellow rays, and a few of the red, are intercepted by the first layer of the fluid; fewer are intercepted by the second, still less by the third, and so on; till, at last, the losses become very small and invariable, and those rays alone are transmitted which give the red colour to the liquid. In a similar manner, when plates of the same thickness of any substance, such as glass, are exposed to an argand lamp, a considerable portion of the radiant heat is arrested by the first plate, a less portion by the second, still less by the third, and so on, the quantity of heat lost decreasing, till at last the loss becomes a constant quantity. The transmission of radiant heat through a solid mass, follows the same law. The losses are very considerable on first entering it, but they rapidly diminish in proportion as the heat penetrates deeper, and become constant at a certain depth. Indeed, the only difference between the transmission of radiant heat through a solid mass, or through the same mass when cut into plates of equal thickness, arises from the small quantity of heat that is reflected at the surfaces of the plates. It is evident, therefore, that the heat gradually lost, is not intercepted at the surface, but absorbed in the interior of the substance.

By experiments on caloric radiated from sources of different temperatures, M. Melloni has proved that the heat emanating from the sun or from a bright flame,

consists of rays which differ from each other as much as the red, yellow, and blue rays do, which constitute white light This explains the reason of the losses of heat in penetrating deeper and deeper into a solid mass, or in passing through a series of plates, for, of the different kinds of rays which dart from a vivid flame, all are successively extinguished by the absorbing nature of the substance through which they pass, till those homogeneous rays alone remain which have the greatest facility of passing through that particular substance, exactly as in a red liquid the blue and yellow rays are extinguished and the red are transmitted.

M. Melloni employed four sources of caloric, two of which were luminous and two obscure, namely, an oil lamp without a glass, incandescent platina, copper heated to 696 degrees, and a copper vessel filled with water at the temperature of 178½ degrees of Fahrenheit Rock salt transmitted heat in the proportion of 92 rays out of 100 from each of these sources, but all other substances, pervious to radiant heat, whether solid or liquid, transmit more caloric from sources of high temperature, than from such as are low. For instance, limpid and colourless fluate of lime transmitted in the proportion of 78 rays out of 100 from the lamp, 69 from the platina, 42 from the copper, and 33 from the hot water; while transparent rock crystal transmitted 38 rays in 100 from the lamp, 28 from the platina, 6 from the copper, and 9 from the hot water. Pure ice transmitted only in the proportion of 6 rays in the 100 from the lamp, and entirely excluded those from the other three sources. Out of 39 different substances, 34 were impervious to

the calorific rays from hot water, 14 excluded those from the hot copper, and 4 did not transmit those from the platina

Thus it appears, that the heat proceeding from these four sources are of different kinds this difference in the nature of the calorific rays, is also proved by another experiment, which will be more easily understood, from the analogy of light Red light, emanating from red glass, will pass in abundance through another piece of red glass, but it will be absorbed by green glass . green rays will more readily pass through a green medium, than through one of any other colour. This holds with regard to all colours · so in heat Rays of caloric, of the same intensity, which have passed through different substances, are transmitted in different quantities by the same piece of alum, and are sometimes stopped altogether , whence it is evident, that rays which emanate from different substances possess different qualities. It appears that a bright flame furnishes rays of heat of all kinds, in the same manner as it gives light of all colours ; and as coloured media transmit some coloured rays and absorb the rest, so bodies transmit some rays of caloric and exclude the others. Rock salt alone resembles colourless transparent media in transmitting all kinds of caloric, even the heat of the hand, just as they transmit white light, consisting of rays of all colours.

The colouring matter of coloured glasses exercises no peculiar action on the rays of heat, with the exception of black and green The heat which has already passed through a green or an opaque black glass, will not pass through alum, whilst that which has been

transmitted through glasses of other colours traverses it readily.

By reversing the experiment, and exposing different substances to caloric that had already passed through alum, M. Melloni found, that the heat emerging from alum is almost totally intercepted by opaque substances, and is abundantly transmitted by *all* such as are transparent and colourless, and that it suffers no appreciable loss when the thickness of the plate is varied within certain limits. The properties of the heat, therefore, which issues from alum nearly approach to those of light and solar heat.

Radiant heat, in traversing various media, is not only rendered more or less capable of being transmitted a second time, but, according to the experiments of Mr. Powell, it becomes more or less susceptible of being absorbed in different quantities by black and white surfaces.

M. Melloni has proved, that solar heat contains rays, which are affected by different substances, in the same manner as if the heat proceeded from a terrestrial source; whence he concludes that the differences observed between the transmission of terrestrial and solar heat, arise from the circumstance of solar heat containing all the kinds of caloric, whilst in other sources some of the kinds are wanting.

Some time since, M. Bérard published an account of having polarized heat by reflection, but his experiments have since been repeated by Mr. Powell and Mr. Loyd without success, though Mr. Powell thought he perceived a small effect in heat from a luminous source. M. Melloni has proved beyond a doubt, that such calorific rays as are capable of being transmitted

through tourmaline, are not polarized by that mineral, like rays of light It is clear, that if heat could be polarized by the method explained in page 213, it would be entirely excluded when the axes of the superposed slices of tourmaline cross each other at right angles, and transmitted when they are parallel. M Melloni found that the same quantity of heat was transmitted in both positions, so that heat does not appear to be capable of polarization

The property of transmitting all kinds of caloric, renders lenses and prisms of rock salt as valuable for experiments on heat, as those of glass are for optical purposes A prism of rock salt has afforded M Melloni the means, not only of proving that all the different kinds of caloric are susceptible of refraction, but that each kind has a refrangibility peculiar to itself

NOTES.

NOTE 1, page 2. *Diameter.* A straight line passing through the centre, and terminated both ways by the sides or surface of a figure. In fig. 1, QQ, NS, are diameters.

NOTE 2, p. 3. *Mathematical and mechanical sciences.* Mathematics teach the laws of number and quantity; mechanics treat of the equilibrium and motion of bodies.

NOTE 3, p. 3. *Analysis* is a series of reasoning conducted by signs or symbols of the quantities whose relations form the subject of enquiry.

NOTE 4, p. 4. *Oscillations* are movements to and fro, like the swinging of the pendulum of a clock, or waves in water. The tides are oscillations of the sea.

NOTE 5, p. 4. *Gravitation.* Sensible gravity or weight. It is the force which causes substances to fall to the surface of the earth, and which retains the celestial bodies in their orbits. Its intensity increases as the squares of the distance decrease.

NOTE 6, p. 5. *Particles of matter* are the indefinitely small or ultimate atoms into which matter is believed to be divisible. Their form is unknown; but though too small to be visible, they must have magnitude.

NOTE 7, p. 5. *A hollow sphere.* A hollow ball, like a bomb shell. A sphere is a ball or solid body, such, that all lines drawn from its centre to its surface

are equal They are called radii, and every line passing through the centre and terminated both ways by the surface is a diameter, which is consequently equal to twice the radius In fig 1 Q q or N S is a diameter, and C Q, C N, are radii A great circle of the sphere has the same centre with the sphere, as the circles Q L q d and Q N q S The circle A B is a lesser circle of the sphere

NOTE 8 p 5 *Concentric hollow spheres* Shells, or hollow spheres, having the same centre, like the coats of an onion

NOTE 9 p 5 *Spheroid* A solid body, which sometimes has the shape of an orange, as in fig 1; it is then called an oblate spheroid, because it is

Fig 1



flattened at the poles N and S Such is the form of the earth and planets When, on the contrary, it is drawn out at the poles like an egg, as in fig 2, it is called a prolate spheroid It is evident, that in both these solids the radii C q, C a, C N, &c are generally unequal, whereas in the sphere they are all equal

Fig 2



NOTE 10 p 5 *Centre of gravity* A point in every body, which if supported, the body will remain at rest in whatever position it may be placed About that point all the parts exactly balance one another

Fig 3



NOTE 11 pp 6 8 *Poles and equator* Let fig 1 or 3 represent the earth, C its centre, N C S the axis of rotation, or the imaginary line about which it performs its daily revolution Then N and S are the north and south poles, and the great circle q E Q, which divides the earth into two equal parts, is the equator The earth is flattened at the poles, fig 1, the equatorial diameter q Q exceeding the polar diameter N S by about 26½ miles Lesser circles, a A G B, which are parallel to the equator, are circles or parallels of latitude, which is estimated in degrees, minutes, and seconds, north and south of the equator, every place in the same parallel having the same latitude Greenwich is in the parallel of 51° 28′ 40″ Thus terrestrial latitude is the angular distance between the direction of a plumb line at any place and the plane of the equator Lines such as N Q S, N G L S, fig 3, are called meridians, all the places in any one of these lines have noon at the same instant The meridian of Greenwich has been chosen by the British as the origin of terrestrial longitude, which is estimated in degrees, minutes, and seconds, east and west of that line If N G L S be the meridian of Greenwich, the position of any place, B, is determined, when its latitude, Q C B, and its longitude, L C Q, are known

NOTE 12 p 6 *A certain mean latitude* The attraction of a sphere on an external body is the same as if its mass were collected into one heavy particle in its centre of gravity, and the intensity of its attraction diminishes as the square of its distance from the external body increases But the attraction of a spheroid, fig 1, on an external body at *m* in the plane of its equator, E Q, is greater, and its attraction on the same body when at *m*′ in the axis N S less, than if it were a sphere Therefore, in both cases, the force deviates from the exact law of gravity This deviation arises from the protuberant matter at the equator; and as it diminishes towards the poles, so does the attractive force of the spheroid But there is one mean latitude, where the attraction of a spheroid is the same as if it were a sphere It is that latitude the square of whose sine is equal to ⅓ of the equatorial radius

NOTE 13 p 6 *Mean distance* The mean distance of a planet from the centre of the sun, or of a satellite from the centre of its planet, is equal to half the major axis of its orbit For example, let P Q A D, fig 6, be the orbit or path of the moon or of a planet; then P A is the major axis When the body is at Q or D, it is at its mean distance from S, for S Q, S D are each equal to C P, half the major axis

NOTE 14 p 6 *Mean radius of the earth* The distance from the centre to the surface of the earth, regarded as a sphere

NOTE 15. p. 6. *Ratio.* The relation which one quantity bears to another.

NOTE 16. p. 6. *Square of moon's distance.* In order to avoid large numbers, the mean radius of the earth is taken for unity: then the mean distance of the moon is expressed by 60; and the square of that number is 3600, or 60 times 60.

NOTE 17. p. 6. *Centrifugal force.* The force with which a revolving body tends to fly from the centre of motion: a sling tends to fly from the hand in consequence of the centrifugal force. A tangent is a straight line touching a curved line in one point without cutting it, as *m* T, fig. 1. The direction of the centrifugal force is in the tangent to the curved line or path in which the body revolves, and its intensity increases with the angular swing of the body, and with its distance from the centre of motion. As the orbit of the moon does not differ much from a circle, let it be represented by *g d m h*, fig. 1, the earth being in C. The centrifugal force arising from the velocity of the moon in her orbit balances the attraction of the earth. By their joint action, the moon moves through the arc *m n* during the time that she would fly off in the tangent *m* T by the action of the centrifugal force alone, or fall through *m p* by the earth's attraction alone. T *n*, the deflection from the tangent, is parallel and equal to *m p*, the versed sine of the arc *m n*, supposed to be moved over by the moon in a second, and therefore so very small that it may be regarded as a straight line. T *n*, or *m p*, is the space the moon would fall through in the first second of her descent to the earth, were she not retained in her orbit by her centrifugal force.

Fig. 1.



NOTE 18. p. 6. *Action and reaction.* When motion is communicated by collision or pressure, the action of the body which strikes is returned with equal force by the body which receives the blow. The pressure of a hand on a table is resisted with an equal and contrary force. This necessarily follows from the impenetrability of matter; a property by which no two particles of matter can occupy the same identical portion of space at the same time. When motion is communicated without apparent contact, as in gravitation, attraction, and repulsion, the quantity of motion gained by the one body is exactly equal to that lost by the other, but in a contrary direction; a circumstance known by experience only.

NOTE 19. p. 6. *Projected.* A body is projected when it is thrown: a ball fired from a gun is projected; it is therefore called a projectile. But the word has also another meaning. A line, surface, or solid body, is said to be projected upon a plane, when parallel straight lines are drawn from every

point of it to the plane The figure so traced upon the plane is a projection The projection of a terrestrial object is therefore its daylight shadow, since the sun's rays are sensibly parallel

NOTE 20 p 6 *Space* The boundless region which contains all creation

NOTE 21 pp 6 16 *Conic sections* Lines formed by any plane cutting a cone A cone is a solid figure, like a sugar loaf, fig 5, of which A is

Fig 5



Fig 6



the apex, A D the axis, and the plane B E C the base The axis may or may not be perpendicular to the base, and the base may be a circle, or any other curved line When the axis is perpendicular to the base, the solid is a right cone If a right cone with a circular base be cut at right angles to the base by a plane passing through the apex, the section will be a triangle If the cone be cut through both sides by a plane parallel to the base, the section will be a circle If the cone be cut slanting quite through both sides, the section will be an ellipse, fig 6 If the cone be

Fig 7



Fig 8



cut parallel to one of the sloping sides, as A B, the section will be a parabola, fig 7 And if the plane cut only one side of the cone, and be not parallel to the other, the section will be a hyperbola, fig 8 Thus there are five conic sections

NOTE 22, p. 6. *Inverse square of distance.* The attraction of one body for another at the distance of two miles, is four times less than at the distance of one mile; at three miles, it is nine times less than at one; at four miles it is sixteen times less, and so on. That is, the gravitating force decreases in intensity as the squares of the distance increase.

NOTE 23, p. 7. *Ellipse.* One of the conic sections, fig. 6. An ellipse may be drawn by fixing the ends of a string to two points, S and F, in a sheet of paper, and then carrying the point of a pencil round in the loop of the string kept stretched, the length of the string being greater than the distance between the two points. The points S and F are called the foci, C the centre, S C or C F the excentricity, A P the major axis, Q D the minor axis, and P S the focal distance. It is evident, that the less the excentricity C S, the nearer does the ellipse approach to a circle; and from the construction it is clear that the length of the string S *m* F is equal to the major axis P A. If T *t* be a tangent to the ellipse at *m*, then the angle T *m* S is equal to the angle *t m* F; and as this is true for every point in the ellipse, it follows, that in an elliptical reflecting surface, rays of light or sound coming from one focus S will be reflected by the surface to the other focus F, since the angle of incidence is equal to the angle of reflection by the theories of light and sound.

NOTE 24, p. 7. *Periodic time.* The time in which a planet or comet performs a revolution round the sun, or a satellite about its planet.

NOTE 25, p. 7. Kepler discovered three laws in the planetary motions by which the principle of gravitation is established.—1st, That the radii vectores of the planets and comets describe areas proportional to the time.

Fig. 9.



Let fig. 9 be the orbit of a planet, then supposing the spaces or areas P S *p*, *p* S *a*, *a* S *b*, &c. equal to one another, the radius vector S P, which is the line joining the centres of the sun and planet, passes over these equal spaces in equal times, that is, if the line S P passes to S *p* in one day, it will come to S *a* in two days, to S *b* in three days, and so on. 2d, That the orbits or paths of the planets and comets are conic sections, having the sun in one of their foci. The orbits of the planets and satellites are curves like fig. 6 or 9 called ellipses, having the sun in the focus S. Three comets are known to move in ellipses, but the greater part seem to move in parabolas, fig. 7, having the sun in S; others appear to move in hyperbolas, like fig. 8. The third law is, that the squares of the periodic times of the planets are proportional to the cubes of their mean distances from the sun. The square of a number is that number multiplied by itself, and the cube of a number is that number twice multiplied by itself. For example, the squares of the numbers 2, 3, 4, &c. are 4, 9, 16, &c. but their cubes are 8, 27, 64, &c. Then the squares of the numbers representing the periodic times of two planets, are to one another as the cubes of the numbers representing their mean distances from the sun. So that three of these quantities being known, the other may be

found by the rule of three. The mean distances are measured in miles or terrestrial radii, and the periodic times are estimated in years, days, and parts of a day. Kepler's laws extend to the satellites.

NOTE 26, p. 7. *Mass.* The quantity of matter in a given bulk. It is proportional to the density and volume or bulk conjointly.

NOTE 27, p. 7. *Gravitation proportional to mass.* But for the resistance of the air, all bodies would fall to the ground in equal times. In fact, a hundred equal particles of matter at equal distances from the surface of the earth would fall to the ground in parallel straight lines with equal rapidity, and no change whatever would take place in the circumstances of their descent, if 99 of them were united in one solid mass; for the solid mass and the single particle would touch the ground at the same instant, were it not for the resistance of the air.

NOTE 28, p. 7. *Primary* signifies, in astronomy, the planet about which a satellite revolves. The earth is primary to the moon.

NOTE 29, p. 8. *Rotation.* Motion round an axis, real or imaginary.

NOTE 30, p. 9. *Compression of a spheroid.* The flattening at the poles. It is equal to the difference between the greatest and least diameters, divided by the greatest; these quantities being expressed in some standard measure, as miles.

NOTE 31, p. 9. *Satellites.* Small bodies revolving about some of the planets. The moon is a satellite to the earth.

NOTE 32, p. 9. *Nutation.* A nodding motion in the earth's axis while in rotation, similar to that observed in the spinning of a top. It is produced by the attraction of the sun and moon on the protuberant matter at the terrestrial equator.

NOTE 33, p. 9. *Axis of rotation.* The line, real or imaginary, about which a body revolves. The axis of the earth's rotation is that diameter, or imaginary line, passing through the centre and both poles. Fig. 1. being the earth, N S is the axis of rotation.

NOTE 34, p. 9. *Nutation of lunar orbit.* The action of the bulging matter at the earth's equator on the moon occasions a variation in the inclination of the lunar orbit to the plane of the ecliptic. Suppose the plane N p n, fig. 13., to be the orbit of the moon, and N m n the plane of the ecliptic, the earth's action on the moon causes the angle p N m to become less or greater than its mean state. The nutation in the lunar orbit is the reaction of the nutation in the earth's axis.

NOTE 35, p. 9. *Translated.* Carried forward in space.

NOTE 36, p. 10. *Force proportional to velocity.* Since a force is measured by its effect, the motions of the bodies of the solar system among

themselves would be the same whether the system be at rest or not The real motion of a person walking the deck of a ship at sea is compounded of his own motion and that of the ship, yet each takes place independently of the other We walk about as if the earth were at rest, though it has the double motion of rotation on its axis and revolution round the sun

NOTE 37 p 11 *Tangent* A straight line which touches a curved line in one point without cutting it In fig 4, m T is tangent to the curve in the point m In a circle the tangent is at right angles to the radius, C m

NOTE 38 p 11 *Motion in an elliptical orbit* A planet m, fig 6, moves round the sun at S in an ellipse P D A Q, in consequence of two forces, one urging it in the direction of the tangent m T, and another pulling it towards the sun in the direction m S Its velocity, which is greatest at P, decreases throughout the arc P D A to A, where it is least, and increases continually as it moves along the arc A Q P till it comes to P again The whole force producing the elliptical motion varies inversely as the square of the distance See note 22

NOTE 39 p 11 *Radii vectores* Imaginary lines joining the centre of the sun and the centre of a planet or comet, or the centres of a planet and its satellite In the circle, the radii are all equal, but in an ellipse, fig 6, the radius vector S A is greater, and S P less than all the others The radii vectores S Q, S D, are equal to C A or C P, half the major axis P A, and consequently equal to the mean distance A planet is at its mean distance from the sun when in the points Q and D

NOTE 40 p 11 *Equal areas in equal times* See Kepler's 1st law in note 25 p 7

NOTE 41 p 12 *Major axis* The line P A, fig 6 or 10

NOTE 42 p 12 *If the planet described a circle, &c* The motion of a planet about the sun, in a circle A B P, fig 10, whose radius C A is equal to the planet's mean distance from him, would be equable, that is, its velocity, or speed, would always be the same Whereas, if it moved in the ellipse A Q P, its speed would be continually varying, by note 38; but its motion is such, that the time elapsing between its departure from P, and its return to that point again, would be the same, whether it moved in the circle or in the ellipse; for these curves coincide in the points P and A

Fig 10



NOTE 13 p 19 *True motion* The motion of a body in its real orbit, P D A Q, fig 10.

NOTE 14 p 19 *Mean motion* Equable motion in a circle P E A B, fig 10, at the mean distance C P or C *m*, in the time that the body would accomplish a revolution in its elliptical orbit P D A Q.

Fig 11



NOTE 15 p 19 *The equinox* Fig 11 represents the celestial sphere, and C its centre where the earth is supposed to be. *q* ♈ Q ♎ is the equinoctial or great circle, traced in the starry heavens by an imaginary extension of the plane of the terrestrial equator, and E ♈ *e* ♎ is the ecliptic, or apparent path of the sun round the earth. ♈ ♎, the intersection of these two planes, is the line of the equinoxes, ♈ is the vernal equinox, and ♎ the autumnal. When the sun is in these points, the days and nights are equal. They are distant from one another by a semicircle, or two right angles. The points E and *e* are the solstices, where the sun is at his greatest distance from the equinoctial. The equinoctial is every where ninety degrees distant from its poles N and S, which are two points diametrically opposite to one another, where the axis of the earth's rotation, if prolonged, would meet the heavens. The northern celestial pole N is within 1° 24′ of the pole star. As the latitude of any place on the surface of the earth, is equal to the height of the pole above the horizon, it is easily determined by observation. The ecliptic E ♈ *e* ♎ is also every where ninety degrees distant from its poles P and *p*. The angle P C N, between the poles P and N of the equinoctial and ecliptic, is equal to the angle *e* C Q, called the obliquity of the ecliptic.

NOTE 16 p 19 *Longitude* The vernal equinox, ♈, fig 11, is the zero point in the heavens whence celestial longitudes, or the angular motions of the celestial bodies, are estimated from west to east, the direction in which they all revolve. The vernal equinox is generally called the first point of Aries, though these two points have not coincided since the early ages of astronomy, about 2233 years ago, on account of a motion in the equinoctial points, to be explained hereafter. If S ♈, fig 10, be the line of the equinoxes, and ♈ the vernal equinox, the true longitude of a planet *p* is the angle ♈ S *p*, and its mean longitude is the angle ♈ C *m*, the sun being in S. Celestial longitude is the angular distance of a heavenly body from the vernal equinox; whereas terrestrial longitude is the angular distance of a place on the surface of the earth from a meridian arbitrarily chosen, as that of Greenwich.

NOTE 47 p 12. *Equation of the centre.* The difference between ♈ C m and ♈ S P, fig 10, that is, the difference between the true and mean longitudes of a planet or satellite. The true and mean places only coincide in the points P and A; in every other point of the orbit, the true place is either before or behind the mean place. In moving from A through the arc A Q P, the true place p is behind the mean place m, and through the arc P D A the true place is before the mean place. At its maximum, the equation of the centre measures C S, the excentricity of the orbit, since it is the difference between the motion of a body in an ellipse and in a circle whose diameter A P is the major axis of the ellipse.

NOTE 48 p 12. *Apsides.* The points P and A, fig 10, at the extremities of the major axis of an orbit. P, is commonly called the perihelion, a Greek term signifying *round the sun*, and the point A is called the aphelion, a Greek term signifying *at a distance from the sun*.

NOTE 49 p 12. *Ninety degrees.* A circle is divided into 360 equal parts, or degrees, each degree into 60 equal parts, called minutes, and each minute into 60 equal parts, called seconds. It is usual to write these quantities thus, 15° 16′ 10″, which means fifteen degrees, sixteen minutes, and ten seconds. It is clear that an arc $m\ n$, fig 1, measures the angle m C n, hence we may say an arc of so many degrees, or an angle of so many degrees; for if there be ten degrees in the angle m C n, there will be ten degrees in the arc $m\ n$. It is evident that there are 90° in a right angle, m C d, or quadrant, since it is the fourth part of 360°.

NOTE 50 p 12. *Quadratures.* A celestial body is said to be in quadrature, when it is 90 degrees distant from the sun. For example, in fig 14 if d be the sun, S the earth, and p the moon, then the moon is said to be in quadrature when she is in either of the points Q or D, because the angles Q S d and D S d, which measure her apparent distance from the sun, are right angles.

NOTE 51 p 12. *Excentricity.* Deviation from circular form. In fig 6 C S is the excentricity of the orbit, P Q A D. The less C S, the more nearly does the orbit or ellipse approach the circular form, and when C S is zero, the ellipse becomes a circle.

Fig 12



Note 52 p 13. *Inclination of an orbit.* Let S, fig 12, be the centre of the sun, P N A n, the orbit of a planet moving from west to east in the direction N p. Let E N $m\ e\ n$ be the shadow or projection of the orbit on the plane of the ecliptic, then N S n is the intersection of these two planes, for the orbit rises above the plane of the ecliptic towards N p, and sinks below it at N P. The angle p N m, which these two planes make with one another, is the inclination of the orbit P N p A to the plane of the ecliptic.

NOTE 53. p. 13. *Latitude of a planet.* The angle pSm, fig. 12., or the height of the planet p above the ecliptic LNm. In this case the latitude is north. Thus, celestial latitude is the angular distance of a celestial body from the plane of the ecliptic, whereas terrestrial latitude is the angular distance of a place on the surface of the earth from the equator.

NOTE 54. p. 13. *Nodes.* The two points N and n, fig. 12., in which the orbit $NAnP$ of a planet or comet intersects the plane of the ecliptic $eNLn$. The part NAn of the orbit lies above the plane of the ecliptic, and the part nPN below it. The ascending node N is the point through which the body passes in rising above the plane of the ecliptic, and the descending node n is the point in which the body sinks below it. The nodes of a satellite's orbit are the points in which it intersects the plane of the orbit of the planet.

NOTE 55. p. 13. *Distance from the sun.* Sp in fig. 12. If ♈ be the vernal equinox, then ♈Sp is the longitude of the planet p, mSp is its latitude, and Sp its distance from the sun. When these three quantities are known, the place of the planet p in space is determined.

NOTE 56. pp. 13. 75. *Elements of an orbit.* Of these there are seven. Let $PNAn$, fig. 12., be the elliptical orbit of a planet, C its centre, S the sun in one of the foci, ♈ the first point of Aries, and $ENen$ the plane of the ecliptic. The elements are, the major axis AP; the excentricity CS; the periodic time, that is, the time of a complete revolution of the body in its orbit; and the fourth is the longitude of the body at any given instant, for example, that at which it passes through the perihelion, or P the point of its orbit nearest to the sun. That instant is assumed as the origin of time, whence all preceding and succeeding periods are estimated. These four quantities are sufficient to determine the form of the orbit, and the motion of the body in it. Three other elements are requisite for determining the position of the orbit in space. These are, the angle ♈SP, the longitude of the perihelion; the angle ANe, which is the inclination of the orbit to the plane of the ecliptic; and lastly, the angle ♈SN, the longitude of N the ascending node.

NOTE 57. p. 14. *Whose planes, &c.* The planes of the orbits, as $PNAn$, fig. 12., in which the planets move, are inclined, or make small angles eNA with the plane of the ecliptic $ENen$, and cut it in straight lines NSn, passing through S the centre of the sun.

NOTE 58. p. 15. *Momentum.* Force measured by the weight of a body and its speed, or simple velocity, conjointly. The primitive momentum of the planets is, therefore, the quantity of motion which was impressed upon them when they were first thrown into space.

NOTE 59. p. 16. *Unstable equilibrium.* A body is said to be in equilibrium, when it is so balanced as to remain at rest. But there are two kinds of equilibrium, *stable* and *unstable*. If a body balanced in stable equilibrium be slightly disturbed, it will endeavour to return to rest by a number of movements to and fro, which will continually decrease till they cease altogether, and then the body will be restored to its original state of repose. But if the equilibrium be unstable, these movements to and fro, or oscillations, will become greater and greater till the equilibrium is destroyed.

NOTE 60 p 18 *Retrograde* Going backwards, as from east to west, contrary to the motion of the planets

NOTE 61 p 19 *Parallel directions* Such as never meet, though prolonged ever so far

Fig 13



NOTE 62 pp 19 21 *The whole force, &c* Let S, fig 13, be the sun, N m n the plane of the ecliptic, p the disturbed planet moving in its orbit n p N, and d the disturbing planet Now, d attracts the sun and the planet p with different intensities in the directions d S, d p the difference only of these forces disturbs the motion of p; it is therefore called the disturbing force. But this whole disturbing force may be regarded as equivalent to three forces, acting in the directions p S, p T, and p m The force acting in the radius vector p S, joining the centres of the sun and planet, is called the *radial force* It sometimes draws the disturbed planet p from the sun, and sometimes brings it nearer to him The force which acts in the direction of the tangent p T is called the *tangential force* It disturbs the motion of p in longitude, that is, it accelerates its motion in some parts of its orbit and retards it in others, so that the radius vector S p does not move over equal areas in equal times (See Note 25) For example, in the position of the bodies in fig 14 it is evident that, in consequence of the attraction of d, the planet p will have its motion accelerated from Q to C, retarded from C to D, again accelerated from D to O, and lastly retarded from O to Q The disturbing body is here supposed to be at rest, and the orbit circular, but as both bodies are perpetually moving with different velocities in ellipses, the perturbations or changes in the motions of p are very numerous Lastly, that part of the disturbing force which acts in the direction of a line p m, fig 13, at right angles to the plane of the orbit N p n, may be called the perpendicular force It sometimes causes the body to approach nearer, and sometimes to recede farther from, the plane of the ecliptic N m n, than it would otherwise do The action of the disturbing forces is admirably explained in a work on gravitation by Professor Airy of Cambridge

Fig 14



NOTE 63. pp. 21, 89. *Perihelion*. Fig. 10, P, the point of an orbit, nearest to the sun.

NOTE 64. p. 21. *Aphelion*. Fig. 10, A, the point of an orbit, farthest from the sun.

NOTE 65. pp. 21, 22, 23. In fig. 15 the central force is greater than the exact law of gravity, therefore the curvature P p a is greater than P p A the real ellipse, hence the planet p comes to the point a, called the aphelion, sooner than if it moved in the orbit P p A, which makes the line P S A advance to a. In fig. 16, on the contrary, the curvature P p a is less than in the true ellipse, so that the planet p must move through more than the arc P p A, or 180°, before it comes to the aphelion a, which causes the greater axis P S A to recede to a.

Fig. 15



Fig. 16



NOTE 66. pp. 22, 23. *Motion of apsides*. Let P S A, fig. 17, be the position of the elliptical orbit of a planet at any time, then, by the action of the disturbing forces, it successively takes the positions P′ S A′, P″ S A″, &c. till by this direct motion it has accomplished a revolution, and then it begins again, so that the motion is perpetual.

Fig. 17



NOTE 67. p. 22. *Siderial revolution*. The consecutive return of an object to the same star.

NOTE 68. p. 23. *Tropical revolution*. The consecutive return of an object to the same tropic or equinox.

NOTE 69. p. 23. *The orbit only bulges, &c.* In fig. 18 the effects of the variation in the excentricity is shown, where P p A is the elliptical orbit at any given instant; after a time it will take the form P p' A, in consequence of the decrease in the excentricity C S; then the forms P p'' A, P p''' A, &c. Consecutively from the same cause, and as the major axis P A always retains the same length, the orbit approaches more and more nearly to the circular form. But

Fig. 18



after this has gone on for some thousands of years, the orbit contracts again, and becomes more and more elliptical

NOTE 70 pp 23 25 *The ecliptic* is the apparent path of the sun in the heavens See Note 45

NOTE 71 p 23 *This force tends to pull, &c* The force in question, acting in the direction $p\,m$, fig 19, pulls the planet p towards the plane N m n, or pushes it farther above it, giving the planet a tendency to move in an orbit above or below its undisturbed orbit N p n, which alters the angle p N m, and makes the node N and the line of nodes N n change their positions.

NOTE 72 p 24 *Motion of the nodes* Let S, fig 19, be the sun; S N n the plane of the ecliptic, P the disturbing body; and p a planet moving in its

Fig 19



orbit $p\,n$, of which $p\,n$ is so small a part that it is represented as a straight line The plane S n p of this orbit cuts the plane of the ecliptic in the straight line S n Suppose the disturbing force begins to act on p so as to draw the planet into the arc $p\,p'$, then, instead of moving in the orbit $p\,n$, it will tend to move in the orbit $p\,p'\,n'$, whose plane cuts the ecliptic in the straight line S n' If the disturbing force acts again upon the body when at p', so as to draw it into the arc $p'\,p''$, the planet will now tend to move in the orbit $p\,p''\,n''$, whose plane cuts the ecliptic in the straight line S n'' The action of the disturbing force on the planet, when at p'', will bring the node to n''', and so on In this manner the node goes backwards through the successive points n, n', n'', n''', &c, and the line of nodes S n has a perpetual retrograde motion about S the centre of the sun The disturbing force has been represented as acting at intervals, for the sake of illustration In nature it is continuous, so that the motion of the node is continuous also; though it is sometimes rapid and sometimes slow, now retrograde and now direct; but, on the whole, the motion is slowly retrograde

NOTE 73 p 24 *When the disturbing planet* is any where in the line S N, fig 19, or in its prolongation, it is in the same plane with the disturbed

planet, and however much it may affect its motions in that plane, it can have no tendency to draw it out of it. But when the disturbing planet is in P, at right angles to the line S N, and not in the plane of the orbit, it has a powerful effect on the motion of the nodes; between these two positions there is a great variety of action.

NOTE 74. p. 25. *The changes in the inclination* are extremely minute when compared with the motion of the node, as evidently appears from fig. 10, where the angles $n\,p\,n'$, $n'\,p'\,n''$, &c. are much smaller than the corresponding angles $n\,S\,n'$, $n'\,S\,n''$, &c.

NOTE 75. p. 27. *Sines and cosines.* Figure 1 is a circle; $n\,p$ is the sine, and $C\,p$ is the cosine, of an arc $m\,n$. Suppose the radius $C\,m$ to begin to revolve at m, in the direction $m\,n\,a$; then at the point m, the sign is zero, and the cosine is equal to the radius $C\,m$. As the line $C\,m$ revolves and takes the successive positions $C\,n$, $C\,a$, $C\,b$, &c. the sines $n\,p$, $a\,q$, $b\,r$, &c. of the arcs $m\,n$, $m\,a$, $m\,b$, &c. increase, while the corresponding cosines $C\,p$, $C\,q$, $C\,r$, &c. decrease; and when the revolving radius takes the position $C\,d$ at right angles to the diameter $g\,m$, the sine becomes equal to the radius $C\,d$, and the cosine is zero. After passing the point d, the contrary happens, for the sines $e\,k$, $f\,v$, &c. diminish, and the cosines $C\,k$, $C\,v$, &c. go on increasing till at g the sine is zero, and the cosine is equal to the radius $C\,g$. The same alternation takes place through the remaining parts $g\,h$, $h\,m$, of the circle, so that a sine or cosine never can exceed the radius. As the rotation of the earth is invariable, each point on its surface passes through a complete circle, or 360 degrees, in twenty-four hours, at the rate of 15 degrees in an hour. Time, therefore, becomes a measure of angular motion, and, *vice versâ*, the arcs of a circle a measure of time, since these two quantities vary simultaneously and equably; and as the sines and cosines of the arcs are expressed in terms of the time, they vary with it. Therefore, however long the time may be, and how often soever the radius may revolve round the circle, the sines and cosines never can exceed the radius; and as the radius is assumed to be equal to unity, their values oscillate between unity and zero.

NOTE 76. p. 27. *Resisting medium.* A fluid which resists the motions of bodies, such as atmospheric air, or the highly elastic fluid called ether, with which it is presumed that space is filled.

NOTE 77. p. 28. *Obliquity of the ecliptic.* The angle $e\,♈\,Q$, fig. 11, between the plane of the terrestrial equator, $q\,♈\,Q$, and the plane of the ecliptic, $E\,♈\,e$. The obliquity is variable.

NOTE 78. p. 29. *Invariable plane.* In the earth the equator is the invariable plane which nearly maintains a parallel position with regard to itself while revolving about the sun, as in fig. 20, where E Q represents it. The two hemispheres balance one another on each side of this plane, and would still do so if all the particles of which they consist were movable among themselves, provided the earth were not disturbed by the action of the sun and moon, which alters the parallelism of the equator by the small variation called nutation, to be explained hereafter.

Fig 20



NOTE 79 p 30 *If each particle*, &c Let P, P', P'', &c, fig 21, be planets moving in their orbits about the centre of gravity of the system Let

Fig 21



P S M, P' S M', &c be portions of these orbits moved over by the radii vectores, S P, S P', &c in a given time, and let p S m, p' S m', &c be their shadows or projections on the invariable plane Then, if the numbers which represent the masses of the planets, P, P', &c be respectively multiplied by the numbers representing the areas or spaces p S m, p' S m', &c the sum of the whole will be greater for the invariable plane than it would be for any plane that could pass through S, the centre of gravity of the system

NOTE 80 p 30 *The centre of gravity* of the solar system lies within the body of the sun, because his mass is much greater than the masses of all the planets and satellites added together

NOTE 81 pp 32 46 *Conjunction* A planet is said to be in conjunction when it has the same longitude with the sun In fig 11, let d be the earth,

and S the sun, then a planet in C would be in conjunction, at O it would be in opposition

NOTE 82 p 92 *The periodic inequalities* are computed for a given time, and consequently for a given form and position of the orbits, of the disturbed and disturbing bodies Although the elements of the orbits vary so slowly that no sensible effect is produced on inequalities of a short period, yet, in the course of time, the secular variations of the elements change the forms and relative positions of the orbits so much, that Jupiter and Saturn which would have come to the same relative positions with regard to the sun and to one another, after 850 years, do not arrive at the same relative positions till after 918 years

NOTE 83 p 93 *Configuration* The relative position of the planets with regard to one another, to the sun, and to the plane of the ecliptic

NOTE 84 p 95 In the same manner that the excentricity of an elliptical orbit may be increased or diminished by the action of the disturbing forces, so a circular orbit may acquire less or more ellipticity from the same cause It is thus that the forms of the orbits of the first and second satellites of Jupiter oscillate between circles and ellipses differing very little from circles

NOTE 85 p 95 *The plane of Jupiter's equator* is the imaginary plane passing through his centre at right angles to his axis of rotation, and corresponds to the plane q E Q e, in fig 1 The satellites move very nearly in the plane of Jupiter's equator, for if J be Jupiter, fig 24, P p his axis of

Fig 24



rotation, e Q his equatorial diameter, which is 6000 miles longer than P p, and if J O and J E be the planes of his orbit and equator seen edgewise, then the orbits of his four satellites seen edgewise will have the positions J 1, J 2, J 3, J 4 These are extremely near to one another, for the angle E J O is only 3° 5′ 30″

NOTE 86 p 85 In consequence of the satellites moving so nearly in the plane of Jupiter's equator, when seen from the earth, they appear to be always very nearly in a straight line, however much they may change their positions with regard to one another and to their primary For example, on the evenings of the 3d, 4th, 5th, and 6th of January, 1835, the satellites will have the configurations given in fig 25, where O is Jupiter, and 1 2 3 4 are the first, second, third, and fourth satellites The satellite is

Fig 23.



supposed to be moving in a direction from the figure towards the point On the sixth evening the second satellite will be seen on the disc of the planet

NOTE 87 p 36 *Angular motion or velocity* is the swiftness with which a body revolves—a sling, for example, or the speed with which a point on the surface of the earth performs its daily rotation about its axis

NOTE 88 p 37 *Displacement of Jupiter's orbit* The action of the planets occasions secular variations in the position of Jupiter's orbit, J O, fig 22, without affecting the plane of his equator J E Again, the sun and satellites themselves, by attracting the protuberant matter at his equator, change the position of the plane J E without affecting J O Both of these cause perturbations in the motions of the satellites

NOTE 89 p 37 *Precession*, with regard to Jupiter, is a retrograde motion of the point where the lines J O, J E, intersect, fig 22

NOTE 90 p 38 *Synodic motion of a satellite* Its motion during the interval between two of its consecutive eclipses

NOTE 91 p 38 *Opposition* A body is said to be in opposition when its longitude differs from that of the sun by 180° If S, fig 24, be the sun,

Fig 24



and E the earth, then Jupiter is in opposition when at O, and in conjunction when at C In these positions the three bodies are in the same straight line

Fig 25



Note 92 p 39 *Eclipses of the satellites* Let S, fig 25, be the sun, J Jupiter, and *a* B *b* his shadow Let the earth be moving in its orbit, in the direction E A R T H, and the third satellite in the direction *a b m n* When the earth is at E, the satellite, in moving through the arc *a b*, will vanish at *a*, and re-appear at *b*, on the same side of Jupiter If the earth be in R, Jupiter will be in opposition, and then the satellite, in moving through the arc *a b*, will vanish close to the disc of the planet, and will reappear on the other side of it But if the satellite be moving through the arc *m n*, it will appear to pass over the disc and eclipse the planet

Note 93 pp 39 51 *Meridian* A terrestrial meridian is a line passing round the earth and through both poles In every part of it noon happens at the same instant In figures 1 and 3, the lines N Q S and N G S are meridians, C being the centre of the earth, and N S its axis of rotation The meridian passing through the Observatory at Greenwich is assumed by the British as a fixed origin, from whence terrestrial longitudes are measured And as each point on the surface of the earth passes through 360°, or a complete circle, in twenty four hours, at the rate of 15° in an hour, time becomes a representative of angular motion Hence, if the eclipse of a satellite happens at any place at eight o'clock in the evening, and the Nautical Almanac shows that the same phenomenon will take place at Greenwich at nine, the place of observation will be in 15° of west longitude

Note 94 p 39 *Conjunction* Let S be the sun, fig 24, E the earth, and J O P C the orbit of Jupiter Then the eclipses which happen when Jupiter is in O, are seen 16m 26s sooner than those which take place when the planet is in C Jupiter is in conjunction when at C and in opposition when in O

Fig 20



NOTE 95 p 40 In the diagonal, &c were the line A S, fig 20, 100,000 times longer than A B, Jupiter's true place would be in the direction A S′, the diagonal of the figure A B S′ S, which is, of course, out of proportion

NOTE 96 p 40 *Aberration of light* The celestial bodies are so distant, that the rays of light coming from them may be reckoned parallel Therefore, let S A, S′ B, fig 20, be two rays of light coming from the sun, or a planet, to the earth moving in its orbit in the direction A B If a telescope be held in the direction A S the ray S A, instead of going down the tube, will impinge on its side, and be lost in consequence of the telescope being carried with the earth in the direction A B But if the tube be held in the position A P, so that A B is to A S, as the velocity of the earth to the velocity of light, the ray will pass through S′ A The star appears to be in the direction A S′, when it really is in the direction A S, hence the angle S A S′ is the angle of aberration

NOTE 97 p 41 *Density proportional to elasticity* The more a fluid, such as atmospheric air, is reduced in dimensions by pressure, the more it resists the pressure

NOTE 98 p 41 *Oscillations of pendulum retarded* If a clock be carried from the pole to the equator its rate will be gradually diminished, that is, it will go slower and slower, because the centrifugal force which increases from the pole to the equator diminishes the force of gravity

NOTE 99 p 44 *Disturbing action* The disturbing force acts here in the very same manner as in note 62, only that the disturbing body *d*, fig 14, is the sun, S the earth, and *p* the moon

NOTE 100 pp 45 47 105 *Perigee* A Greek word, signifying round the earth The perigee of the lunar orbit is the point P, fig 6, where the moon is nearest to the earth It corresponds to the perihelion of a planet Sometimes the word is used to denote the point where the sun is nearest to the earth

NOTE 101 p 45 *Evection* The evection is produced by the action of the radial force in the direction S *p*, fig 14, which sometimes increases and sometimes diminishes the earth's attraction to the moon It produces a corresponding temporary change on the eccentricity, which varies with the position of the major axis of the lunar orbit in respect of the line S *d*, joining the centres of the earth and sun

NOTE 102 p 45 *Variation* The lunar perturbation called the variation is the alternate acceleration and retardation of the moon in longitude, from the action of the tangential force She is accelerated in going from qua

dratures in Q and D, fig 14, to the points C and O, called syzygies, and is retarded in going from the syzygies C and O to Q and D again

Note 103 p 46 *Square of time* If the times increase at the rate of 1, 2, 3, 4, &c years, or hundreds of years, the squares of the times will be 1, 4, 9, 16, &c years, or hundreds of years

Note 104 p 49 *Mean anomaly* The mean anomaly of a planet is its angular distance from the perihelion, supposing it to move in a circle The true anomaly is its angular distance from the perihelion in its elliptical orbit For example, in fig 10, the mean anomaly is P C m, and the true anomaly is P S p

Note 105 pp 49 81 *Many circumferences* There are 360 degrees, or 1,296,000 seconds, in a circumference; and as the acceleration of the moon only increases at the rate of 11″ in a century, it must be a prodigious number of ages before it accumulates to many circumferences

Note 106 p 50 *Phases of the moon* The periodical changes in the enlightened part of her disc from a crescent to a circle, depending upon her position with regard to the sun and earth

Note 107 p 50 *Lunar eclipse* Let S, fig 27, be the sun, E the earth, and m the moon The space a A b is a section of the shadow, which

Fig 27



has the form of a cone or sugar loaf, and the spaces A a c, A b d, are the penumbra The axis of the cone passes through A and through E and S, the centres of the sun and earth; and n m n' is the path of the moon through the shadow

Note 108 p 50 *Apparent diameter* The diameter of a celestial body, as seen from the earth

Note 109 p 51 *Penumbra* The shadow, or imperfect darkness, which precedes and follows an eclipse

Note 110 p 51 *Synodic revolution of the moon* The time between two consecutive new or full moons

Note 111 p. 51 *Horizontal refraction* The light, in coming from a

celestial object, is bent into a curve as soon as it enters our atmosphere, and that bending is greatest when the object is in the horizon

NOTE 112 p 52 *Solar eclipse* Let S, fig 28, be the sun, *m* the moon, and E the earth Then *a* E *b* is the moon's shadow, which sometimes

Fig 28



eclipses a small portion of the earth's surface at *e*, and sometimes falls short of it To a person at *e*, in the centre of the shadow, the eclipse may be total or annular To a person not in the centre of the shadow a part of the sun will be eclipsed, and to one at the edge of the shadow there will be no eclipse at all The spaces P *b* E, P' *a* E are the penumbra

Fig 29



NOTE 113 p 54 *From the extremities, &c* If the length of the line *a b*, fig 29, be measured, in feet or fathoms, the angles S *b a*, S *a b*, can be measured, and then the angle *a* S *b* is known, whence the length of the line S C may be computed *a* S *b* is the parallax of the object S, and it is clear that the greater the distance of S, the less the base *a b* will appear, because the angle *a* S' *b* is less than *a* S *b*

NOTE 114 p 56 *Every particle will describe a circle, &c* If N S, fig 3, be the axis about which the body revolves, then particles at B, Q, &c will whirl in the circles B G A *a*, Q E *q* D, whose centres are in the axis N S, and their planes parallel to one another They are, in fact, parallels of latitude, Q E *q* D being the equator

NOTE 115 p 56 *The force of gravity, &c* Gravity, at the equator

acts in the direction Q C, fig 30. Whereas the direction of the cen-

Fig 30



trifugal force is exactly contrary, being in the direction C Q, hence the difference of the two is the force called gravitation, which makes bodies fall to the surface of the earth At any point, *m*, not at the equator, the direction of gravity is *m b*, perpendicular to the surface, but the centrifugal force acts perpendicularly to N S, the axis of rotation Now the effect of the centrifugal force is the same as if it were two forces, one of which, acting in the direction *b m*, diminishes the force of gravity, and another which, acting in the direction *m t*, tangent to the surface at *m*, urges the particles towards Q, and tends to swell out the earth at the equator

Note 116 p 57 *Homogeneous mass* A quantity of matter, every where of the same density

Note 117 p 58 *Ellipsoid of revolution* A solid formed by the revolution of an ellipse about its axis If the ellipse revolve about its minor axis Q D, fig 6, the ellipsoid will be *oblate*, or flattened, at the poles, like an orange If the revolution be about the greater axis A P, the ellipsoid will be prolate, like an egg

Note 118 p 58 *Concentric elliptical strata* Strata, or layers, having an elliptical form and the same centre

Note 119 p 58 *On the whole, &c* The line N Q S *q*, fig 1, represents the ellipse in question, its major axis being Q *q*, its minor N S

Note 120 p 59 *Increase in the length of the radii, &c* The radii gradually increase from the polar radius C N, fig 30, which is least, to the equatorial radius C Q, which is greatest There is also an increase in the lengths of the arcs corresponding to the same number of degrees from the equator to the poles; for the angle N C *r* being equal to *q* C *d*, the elliptical arc N *r* is greater than *q d*

NOTE 121 p 59 *Cosine of latitude* The angles m C a, m C b, fig 1, being the latitudes of the points a, b, &c the cosines are C q, C r, &c

NOTE 122 p 60 *An arc of the meridian* Let N Q S q, fig 30, be the meridian, and m n the arc to be measured Then if Z' m, Z n, be verticals, or lines perpendicular to the surface of the earth, at the extremities of the arc m n, they will meet in p Q a n, Q b m, are the latitudes of the points m and n, and their difference is the angle m p n Since the latitudes are equal to the height of the pole of the equinoctial above the horizon of the places m and n, the angle m p n may be found by observation When the distance m n is measured in feet or fathoms, and divided by the number of degrees and parts of a degree contained in the angle m p n, the length of an arc of one degree is obtained

NOTE 123 p 60 *A series of triangles* Let M M', fig 31, be the meri-

Fig 31



dian of any place A line, A B, is measured with rods, on level ground, of any number of fathoms, C being some point seen from both ends of it As two of the angles of the triangle A B C can be measured, the lengths of the sides A C, B C, can be computed, and if the angle m A B, which the base A B makes with the meridian be measured, the length of the sides B m, A m, may be obtained by computation, so that A m, a small part of the meridian, is determined Again, if D be a point visible from the extremities of the known line B C, two of the angles of the triangle B C D may be measured, and the length of the sides C D, B D, computed Then if the angle B m m' be measured, all the angles and the side B m of the triangle B m m' are known, whence the length of the line m m' may be computed, so that the portion A m' of the meridian is determined, and in the same manner it may be prolonged indefinitely

NOTE 124 pp 61 63 *The square of the sine of the latitude* Q b m, fig 30, being the latitude of m, e m is the sine and b e the cosine Then the number expressing the length of e m, multiplied by itself, is the square of the sine of the latitude, and the number expressing the length of b e, multiplied by itself, is the square of the cosine of the latitude

NOTE 125 p 64 *A pendulum* is that part of a clock which swings to and fro

NOTE 126. p. 67. *Parallax.* The angle $a S b$, fig. 29., under which we view an object $a b$. It therefore diminishes as the distance increases. The parallax of a celestial object is the angle which the radius of the earth would be seen under, if viewed from that object. Let E, fig. 32., be the

Fig. 32.



centre of the earth, E H, its radius, and m H O, the horizon of an observer at H. Then, H m E is the parallax of a body m, the moon for example. In measure, as m rises higher and higher in the heavens, to the points m', m'', &c. the parallax H m' E, H m'' E, &c. decreases. At Z, the zenith, or point immediately above the head of the observer, it is zero, and at m, where the body is in the horizon, the angle H m E is the greatest possible, and is called the horizontal parallax. It is clear that, with regard to celestial bodies, the whole effect of parallax is in the vertical or in the direction m m' Z, and as a person at H sees m' in the direction H m' A, when it really is in the direction E m' B, it makes celestial objects appear to be lower than they really are. The distance of the moon from the earth has been determined from her horizontal parallax. The angle E m H can be measured. E H m is a right angle, and E H, the radius of the earth, is known in miles, whence the distance of the moon E m is easily found. Annual parallax is the angle under which the diameter of the earth's orbit would be seen, if viewed from a star.

NOTE 127. p. 68. *The radii n B, n G, &c.* fig. 3., are equal in any one parallel of latitude, A a B G, therefore a change in the parallax observed in that parallel can only arise from a change in the moon's distance from the earth; and when the moon is at her mean distance, which is a constant quantity equal to half the major axis of her orbit, a change in the parallax observed in different latitudes, G and E, must arise from the difference in the lengths of the radii n G and C E.

NOTE 128. p. 68. *When Venus is in her nodes.* She must be in the line N S n, where her orbit P N A n cuts the plane of the ecliptic L N e n, fig. 12.

NOTE 129 p 68 *The line described, &c* Let E, fig 33, be the earth

Fig 33



S the centre of the sun, and V the planet Venus The real transit of the planet, seen from E the centre of the earth, would be in the direction A B A person at W would see it pass over the sun in the line $v\,a$, and a person at O would see it move across him in the direction $v'\,a'$

NOTE 130 p 61 *Kepler's second law* Suppose it were required to find the distance of Jupiter from the sun The periodic times of Jupiter and Venus are given by observation, and the mean distance of Venus from the centre of the sun is known in miles or terrestrial radii; therefore, by the rule of three, the square root of the periodic time of Venus is to the square root of the periodic time of Jupiter, as the cube root of the mean distance of Venus from the sun to the cube root of the mean distance of Jupiter from the sun, which is thus obtained in miles or terrestrial radii The root of a number is that number which, once multiplied by itself, gives its square; twice multiplied by itself, gives its cube, &c For example, twice 2 are 4, and twice 4 are 8 2 is therefore the square root of 4, and the cube root of 8 In the same manner 3 times 3 are 9, and 3 times 9 are 27, 3 is therefore the square root of 9 and the cube root of 27

NOTE 131 p 71 *Inversely, &c* The quantities of matter in any two primary planets, are greater in proportion as the cubes of the numbers representing the mean distances of their satellites are greater, and also in proportion as the squares of their periodic times are less

NOTE 132 p 75 The sum of the greatest and least distances, S P, S A, fig 12, is equal to P A, the major axis; and their difference is equal to twice the excentricity C S The longitude ♈ S P of the planet, when in the point P, at its least distance from the sun, is the longitude of the perihelion The greatest height of the planet above the plane of the ecliptic 1 N *e n*, is equal to the inclination of the orbit P N A *n* to that plane The longitude of the planet, when in the plane of the ecliptic, can only be the longitude of one of the points N or *n*, and when one of these points is known, the other is given, being 180° distant from it Lastly, the time included between two consecutive passages of the planet, through the same node N or *n*, is its periodic time, allowance being made for the recess of the node in the interval

NOTE 133, p 76 Suppose that it were required to find the position of a

point in space, as of a planet, and that one observation places it in n, fig 34, another observation places it in n', another in n'', and so on, all the points n, n', n'', n''', &c, being very near to one another. The true place of the planet P will not differ much from any of these positions. It is evident, from this view of the subject, that P n, P n', P n'', &c are the errors of observation. The true position of the planet P is found by this property, that the squares of the numbers representing the lines P n, P n', &c, when added together, is the least possible. Each line P n, P n', &c being the whole error in the place of the planet, is made up of the errors of all the elements, and when compared with the errors obtained from theory, it affords the means of finding each. The principle of least squares is of very general application; its demonstration cannot find a place here, but the reader is referred to Biot's Astronomy, vol ii p 203

Fig 34



NOTE 134 p 78 *An axis that, &c* Fig 20 represents the earth revolving in its orbit about the sun in S, the axis of rotation, P p being every where parallel to itself

NOTE 135 p 78 *Angular velocities that are sensibly uniform* The earth and planets revolve about their axes, with an equable motion, which is never either faster or slower. For example, the length of the day is never more nor less than twenty four hours

NOTE 136 p 80 Some astronomers affirm that there are several divisions in the ring, a statement that requires confirmation

NOTE 137 p 82 If fig 1 be the moon, her polar diameter N S is the shortest; and of those in the plane of the equator, Q E q, that which points to the earth is greater than all the others

NOTE 138 p 88 *Inversely proportional, &c* That is, the total amount of solar radiation becomes less as the minor axis C C', fig 20, of the earth's orbit becomes greater

NOTE 139 p 90 Fig 35 represents the position of the apparent orbit of the sun as it is at present, the earth being in E. The sun is nearer to the earth in moving through ♎ P ♈, than in moving through ♈ A ♎, but its motion through ♎ P ♈ is more rapid than its motion through ♈ A ♎, and as the swiftness of the motion and the quantity of heat received, vary in the same proportion, a compensation takes place

Fig 35



NOTE 140 p 92 *In an ellipsoid of revolution*, fig 1, the polar diameter N S, and every diameter in the equator, q E Q e are permanent axes of rotation, but the rotation would be unstable about any other Were the earth to begin to rotate about C a, the angular distance from a to the equator at q, would no longer be ninety degrees, which would be immediately detected by the change it would occasion in the latitudes

NOTE 141 pp 65 97 *Let* q ♈ Q, and E ♈ e, fig 11, be the planes of the equator and ecliptic The angle e ♈ Q, which separates them, called the obliquity of the ecliptic, varies in consequence of the action of the sun and moon upon the protuberant matter at the earth's equator That action brings the point Q towards e, and tends to make the plane q ♈ Q coincide with the ecliptic E ♈ e, which causes the equinoctial points, ♈ and ♎, to move slowly backwards on the plane e ♈ E at the rate of 50″ 41 annually This part of the motion, which depends upon the form of the earth, is called lunisolar precession Another part, totally independent of the form of the earth, arises from the mutual action of the earth, planets, and sun, which, altering the position of the plane of the ecliptic e ♈ E, causes the equinoctial points ♈ and ♎ to advance at the rate of 0″ 31 annually; but as this motion is much less than the former, the equinoctial points recede on the plane of the ecliptic at the rate of 50″ 1 annually. This motion is called the precession of the equinoxes

NOTE 142 pp 70 99 *Let* q ♈ Q, e ♈ E, fig 86, be the planes of the equinoctial or celestial equator and ecliptic, and p, P, their poles Then suppose p, the pole of the equator, to revolve with a tremulous or wavy motion in the little ellipse $p\,a\,d\,b$ in about 19 years, while the point a is carried round in the circle a A B in 25,868 years, both motions being very small The tremulous motion may represent the half yearly variation, the motion in the ellipse gives an idea of the nutation discovered by Bradley, and the motion in the circle a A B arises from the precession of the equinoxes The greater axis $p\,d$ of the small ellipse is 18″ 5, its minor axis $b\,a$ is 13″74 These motions are so small, that they have very little effect on the parallelism of the axis of the earth's rotation during its revolution round the sun, as represented in fig 20 As the stars are fixed, this real motion in the pole of the earth must cause an apparent change in their places

Fig 86



NOTE 143 p 102 *Let* N be the pole, fig 11 e E the ecliptic, and Q q

[illegible] meridian, and at right angles to the [illegible] the arc ♈ [illegible]

[illegible] When the star appears in [illegible] horizon, a little before the rising of the sun

[illegible], fig. [illegible], be the apparent orbit or path [illegible] Its major axis, A P, is at present situate [illegible] the solar perigee P is between the solstice of [illegible] of spring. So that the time of the sun's passage [illegible] is greater than the time he takes to go through [illegible] axis A P coincided with [illegible] ♈, the line of the [illegible] years before the Christian era; at that time P was in the [illegible] of the Christian era, the perigee P will coincide with [illegible] axis was perpendicular to ♈ [illegible], and then P [illegible]

[illegible] Since the declination of a celestial [illegible] distance from the equinoctial, the declination of the [illegible] is equal to the arc Q [illegible], fig. 11, which measures the ob[illegible] or angular distance of the plane ♈ [illegible] from the [illegible]

[illegible] is the angular distance of a celestial [illegible] the point [illegible] over the head of an observer

[illegible] The force of gravita[illegible] the height above the surface of the earth [illegible] vibrates slower on high ground; and in order [illegible] independent of local circumstances, it is necessary to [illegible] that would exactly make 86,400 vibrations in a mean [illegible] at the level of the sea.

[illegible] *A quadrant of the meridian* is a fourth part of a [illegible] or an arc of a meridian containing 90°, as N Q, fig. 11

[illegible] *The angular velocity of the earth* is at the rate of 180° [illegible] which is the time included between the passages of the [illegible] under meridian

[illegible] If [illegible] be the earth, fig. 11, *d* the sun, and C Q O D the [illegible] of the moon, then C and O are the syzygies. When the moon is new [illegible] full she is at O; and as both sun and moon are then [illegible] the spring tides, it being high water [illegible] C and O, while it is low water at those under Q and D. [illegible] happen when the moon is in quadrature at Q or D, for [illegible] distant from the sun by the angle *d* B Q, or *d* B D, each of which is 90°.

[illegible] *Declination.* If the earth be in C, fig. 11, and

If q ♈ Q be the equinoctial, and N m S a meridian, then m C n is the declination of a body at n. Therefore the cosine of that angle is the cosine of the declination.

Note 153. p. 118. *Moon's southing.* The time when the moon is on the meridian of any place, which happens about forty eight minutes later every day.

Note 154. pp. 120, 150. fig. 37. Shows the propagation of waves from two points C and C', where stones are supposed to have fallen. Those points in

Fig. 37.



which the waves cross each other are the places where they counteract each other's effects, so that the water is smooth there, while it is agitated in the intermediate spaces.

Note 155. p. 121. *The centrifugal force may, &c.* The centrifugal force acts in a direction at right angles to N S, the axis of rotation, fig. 30. Its effects are equivalent to two forces, one of which is in the direction $b\,m$ perpendicular to the surface Q m n of the earth, and diminishes the force of gravity at m. The other acts in the direction of the tangent m T, which makes the fluid particles tend towards the equator.

Note 156. p. 127. *Analytical formula, or expression.* A combination of symbols, or signs, expressing or representing a series of calculation, and including every particular case that can arise from a general law.

Note 157. p. 131. *Platina.* The heaviest of metals; its colour is between that of silver and lead.

Note 158. p. 139. *Fig. 38 is a perfect octahedron.* Sometimes its angles, A, X, a, a, &c. are truncated, or cut off. Sometimes a slice is cut off its edges A a, X a, a a, &c. Occasionally both these modifications take place,

Fig 38.



NOTE 159 p 133 Prismatic crystals of sulphate of nickel are somewhat like fig 32, only that they are thin, like a hair

NOTE 160 p 134 *Zinc*, a metal either found as an ore, or mixed with other metals It is used in making brass

NOTE 161 p 135 *A cube* is a solid contained by six plane square surfaces, as fig 39

Fig 39



Fig 40



NOTE 162 p 135 *A tetrahedron* is a solid contained by four triangular surfaces, as fig 40 of this solid there are many varieties

NOTE 163 p 135 There are many varieties of the octahedron In that mentioned in the text, the base *a a a a*, fig 38, is a square, but the base may be a rhomb, this solid may also be elongated in the direction of its axis A X, or it may be depressed

NOTE 164 pp 136 229 *A rhombohedron* is a solid contained by six plane surfaces, as in fig 63, the opposite planes being equal and similar rhombs parallel to one another; but all the planes are not necessarily equal

or similar, nor are its angles right angles In carbonate of lime the angle C A B is 105° 55, and the angle B or C is 75° 05

NOTE 165 p 135 *Sublimation* Bodies raised into vapour which is again condensed into a solid state

Fig 41



NOTE 166 p 137 The surface of a column of water, or spirit of wine in a capillary tube is hollow, and that of a column of quicksilver is convex, or rounded, as in fig 41

NOTE 167 p 137 *Inverse ratio, &c* The elevation of the liquid is greater, in proportion as the internal diameter of the tube is less

NOTE 168 p 139 In fig 41, the line *c d* shows the direction of the resulting force in the two cases

NOTE 169 p 139 When two plates of glass are brought near to one another in water, the liquid rises between them, and if the plates touch each other at one of their upright edges, the outline of the water will become an hyperbola

NOTE 170 p 140 Let A A′, fig 42, be two plates, both of which are wet, and B B′, two that are dry When partly immersed in a liquid, its

Fig 42



surface will be curved close to them, but will be of its usual level for the rest of the distance At such a distance, they will neither attract nor repel one another But as soon as they are brought near enough to have the whole of the liquid surface between them curved, as in *a a*, *b b*, they will rush together If one be wet and another dry, as C C, they will repel one another at a certain distance, but as soon as they are brought very near, they will rush together, as in the former cases

NOTE 171 p 155 *Latent heat* There is a certain quantity of heat in all bodies, which cannot be detected by the thermometer, but which may become sensible by compression.

NOTE 172 p 159 *Reflected waves* A series of waves of light, sound, or water, diverge in all directions from their origin I, fig 43, as from a centre

Fig 43



When they meet with an obstacle S S, they strike against it, and are reflected or turned back by it in the same form, as if they had proceeded, from the centre C, at an equal distance on the other side of the surface S S

NOTE 173 p 160 *Elliptical shell* If fig 6 be a section of an elliptical shell, then all sounds coming from the focus S to different points on the surface, as *m*, are reflected back to F, because the angle T*m*S is equal to *t m* F In a spherical hollow shell, a sound diverging from the centre is reflected back to the centre again

NOTE 174 p 165 Fig 44 represents musical strings in vibration, the

Fig 44



straight lines are the strings when at rest The first figure of the four would give the fundamental note, as, for example, the low C The second and third figures would give the first and second harmonics, that is, the

octave and the 12th above C, $n\,n\,n$ being the points of rest; and the fourth figure shows the real motion when compounded of all three

NOTE 175 p 167 Fig 15 represents sections of an open and of a

Fig 15



shut pipe, and of a pipe open at one end. When sounded, the air spontaneously divides itself into segments It remains at rest in the divisions or nodes $n\,n$, &c, but vibrates between them in the direction of the arrow heads The undulations of the whole column of air give the fundamental note, while the vibrations of the divisions give the harmonics

NOTE 176 p 169 Fig 1 plate 1 shows the vibrating surface when the sand divides it into squares, and fig 2 represents the same when the nodal lines divide it into triangles The portions marked a, a are in different states of vibration from those marked $b\,b$

NOTE 177 p 170 Plates 1 and 2 contain a few of Chladni's figures The white lines are the forms assumed by the sand, from different modes of vibration, corresponding to musical notes of different degrees of pitch Plate 3 contains six of Chladni's circular figures

NOTE 178 p 171 Mr Wheatstone's principle is, that when vibrations producing the forms of figs 1 and 2 plate 3 are united in the same surface, they make the sand assume the form of fig 3. In the same manner, the vibrations which would separately cause the sand to take the forms of figs 4 and 5, would make it assume the form in fig 6 when united The fig 9 results from the modes of vibration of 7 and 8 combined The parts marked a, a, are in different states of vibration from those marked b, b Figs 1, 2 and 3 plate 4 represent forms which the sand takes, in consequence of simple modes of vibration; 4 and 5 are those arising from two combined modes of vibration; and the last six figures arise from four superposed simple modes of vibration Those complicated figures are determined by computation independent of experiment.

NOTE 179 p 171 The long cross lines of fig 46, show the two systems of nodal lines given by M. Savart's lamina

Fig. 46.



NOTE 180, p. 171. The short lines on fig. 46 show the positions of the nodal lines on the other sides of the same laminæ.

NOTE 181, p. 172. Fig. 47 gives the nodal lines on a cylinder, with the

Fig. 47.



paper rings that mark the quiescent points.

NOTE 182, pp. 180, 181, 185. *Reflection and refraction.* Let P C *p*, fig. 48, be perpendicular to a surface of glass or water A B. When a ray of light, passing through the air, falls on this surface in any direction I C, part of it is reflected in the direction C S, and the other part is bent at C, and passes through the glass or water in the direction C R. I C is called the incident ray, and I C P the angle of incidence; C S is the reflected ray, and P C S the angle of reflection. C R is the refracted ray, and *p* C R the angle of refraction. The plane passing through S C and I C is the plane of reflection, and the plane passing through I C and C R is the plane of refraction. In ordinary cases, C S, C R, C I, are all in the same plane. We see the surface by means of the reflected light, which would otherwise be invisible. Whatever the reflecting surface may be, and however obliquely the light may fall upon it, the angle of reflection is always equal to the angle of incidence. Thus, I C, I′ C, being rays incident on the surface at C, they will be reflected into C S, C S′, so that the angle S C P will be equal to the angle I C P, and S′ C P equal to I′ C P. That is by no means the case with the refracted rays. The incident rays I C, I′ C, are bent at C, towards the perpendicular, in the direction C R, C R′, and the law of refraction is such, that the sine of the angle of incidence has a constant ratio to the sine of the angle of refraction; that is to say, the number expressing the length of I *m*, the sine of I C P, divided by

Fig. 48.



the number expressing the length of R n, the sine of R C p is the same for all the rays of light that can fall upon the surface of any one substance, and is called its Index of refraction. Though the index of refraction be the same for any one substance, it is not the same for all substances. For water it is 1.336, for crown glass it is 1.535, for flint glass, 1.6, for diamond, 2.187, and for chromate of lead it is 3, which substance has a higher refractive power than any other known. Light falling perpendicularly on a surface, passes through it without being refracted. If the light be now supposed to pass from a dense into a rare medium, as from glass or water into air, then R C, R′ C, become the incident rays, and in this case the refracted rays, C I, C I′, are bent from the perpendicular instead of towards it. When the incidence is very oblique, as r C, the light never passes into the air at all, but is *totally* reflected in the direction C r′, so that the angle p C r is equal to p C r′. That frequently happens at the second surface of a piece of glass. When a ray I S falls from air upon a piece of glass A B, it is in general refracted at each surface. At C it is bent towards the perpendicular, and at R from it, and the ray emerges parallel to I C; but when the ray is very oblique to the second surface, it is totally reflected. An object seen by total reflection, is nearly as vivid as when seen by direct vision, because no part of the light is refracted.

NOTE 183. p. 181. *Atmospheric refraction.* Let a b, a b, &c., fig. 49, be

Fig. 49.



strata, or extremely thin layers, of the atmosphere, which increase in density towards m n, the surface of the earth. A ray coming from a star meeting the surface of the atmosphere at S, would be refracted at the surface of each layer, and would consequently move in the curved line S r r r A; and as an object is seen in the direction of the ray that meets the eye, the star, which really is in the direction A S, would seem to a person at A to be in s. So that refraction, which always acts in a vertical direction, raises objects above their true place. For that reason, a body at S′, below the horizon H A O, would be raised, and would be seen in s′. The sun is frequently visible by refraction after he is set, or before he is risen. There is no refrac-

tion in the zenith at Z It increases all the way to the horizon, where it is greatest, the variation being proportional to the tangent of the angles Z A S, Z A S', the distances of the bodies S, S', from the zenith The more obliquely the rays fall, the greater the refraction

NOTE 184 p 182 *Bradley's method of ascertaining the amount of refraction* Let Z, fig 50, be the zenith, or point immediately above an observer

Fig 50



at A; let H O be his horizon, and P the pole of the equinoctial A Q Hence P A Q is a right angle A star as near to the pole as *s*, would appear to revolve about it, in consequence of the rotation of the earth At noon, for example, it would be at *s* above the pole, and at midnight it would be in *s'* below it The sum of the true zenith distances, Z A *s*, Z A *s'*, is equal to twice the angle Z A P Again, S and S' being the sun at his greatest distances from the equinoctial A Q when in the solstices, the sum of his true zenith distances, Z A S, Z A S', is equal to twice the angle Z A Q Consequently, the four true zenith distances, when added together, are equal to twice the right angle Q A P, that is, they are equal to 180° But the observed or apparent zenith distances are less than the true, on account of refraction; therefore the sum of the four apparent zenith distances are less than 180° by the whole amount of the four refractions

NOTE 185 p 183 *Terrestrial refraction* Let C, fig 51, be the centre of the earth, A an observer at its surface, A H his horizon, and B some distant point, as the top of a hill Let the arc B A be the path of a ray coming from B to A, E B, E A, tangents to its extremities; and A G, B I, perpendiculars to C A and C B However high the hill B may be, it is nothing when compared with C A, the radius of the earth, consequently, A B differs so little from A D, that the angles A E B and A C B are supplementary to one another; that is, the two taken together are equal to 180° Now B A H is the real height of B, and E A H its apparent height; hence refraction raises the object B, by the angle E A B, above its real place Again, the real depression of A, when viewed

from E, is F B A, whereas its apparent depression is I B E, so F B A is due to refraction The angle F B A is equal to the sum of the angles B A H and A C B, that is, the true elevation is equal to the sum of the true depression and the horizontal angle But the true elevation is equal to the apparent elevation diminished by the refraction; and the true depression is equal to the apparent depression, increased by refraction Hence twice the refraction is equal to the horizontal angle augmented by the difference between the apparent elevation and the apparent depression

Fig 51



NOTE 186 p 184 Fig 52 represents the phenomenon in question S P is the real ship, with its inverted and direct images seen in the air Were there no refraction, the rays would come from the ship S P to the

Fig 52



eye E in the direction of the straight lines; but, on account of the variable density of the inferior strata of the atmosphere, the rays are bent in the curved lines P c E, P d E, S m E, S n E Since an object is seen in the direction of the tangent to that point of the ray which meets the eye, the point P of the real ship is seen at p and p', and the point S seems to be in s and s'; and as all the other points are transferred in the same manner, direct and inverted images of the ship are formed in the air above it.

Fig 53



NOTE 187 p 184 Fig 53 represents the section of a poker, with the refraction produced by the hot air surrounding it

NOTE 188 p 188 *The solar spectrum* A ray from the sun at S, fig 54,

Fig 54



admitted into a dark room through a small round hole H in a window shutter, proceeds in a straight line to a screen D, on which it forms a bright circular spot of white light of nearly the same diameter with the hole H But when the refracting angle B A C of a glass prism is interposed, so that the sun beam falls on A C the first surface of the prism, and emerges from the second surface A B at equal angles, it causes the rays to deviate from the straight path S D, and bends them to the screen M N, where they form a coloured image V R of the sun, of the same breadth with the diameter of the hole H, but much longer The space V R consists of seven colours,—violet, indigo, blue, green, yellow, orange, and red The violet and red, being the most and least refrangible rays, are at the extremities, and the green occupy the middle part at G The angle D *g* G is called the mean deviation, and the spreading of the coloured rays over the angle V *g* R the dispersion The deviation and dispersion vary with the refracting angle B A C of the prism, and with the substance of which it is made

NOTE 189 p 191 Under the same circumstances, and where the refracting angles of the two prisms are equal, the angles D *g* G and V *g* R, fig 54,

are greater for flint glass than for crown glass. But as they vary with the angle of the prism, it is only necessary to augment the refracting angle of the crown glass prism by a certain quantity, to produce nearly the same deviation and dispersion with the flint glass prism. Hence, when the two prisms are placed with their refracting angles in opposite directions, as in fig. 54, they nearly neutralise each other's effects, and refract a ray of light without resolving it into its elementary coloured rays. Sir David Brewster has come to the conclusion, that there may be refraction without colour by means of two prisms, or two lenses, when properly adjusted, even though they be made of the same kind of glass.

Fig. 55.

NOTE 190, p. 194. The object glass of the achromatic telescope consists of a convex lens A B, fig. 55, of crown glass placed on the outside towards the object, and of a concavo convex lens C D of flint glass placed towards the eye. The focal length of a lens is the distance of its centre from the point in which the rays converge, as F, fig. 60. If, then, the lenses A B and C D be so constructed that their focal lengths are in the same proportion as their dispersive powers, they will refract rays of light without colour.

NOTE 191, p. 198. When a sun beam, after having passed through a coloured glass V V', fig. 56, enters a dark room by two small slits O O' in a card, or piece of tin, they produce alternate bright and black bands on a screen S S' at a little distance. When either one or other of the slits O or O' is stopped, the dark bands vanish, and the screen is illuminated by a uniform light, proving that the dark bands are produced by the interference of the two sets of rays. Again, let H *m*, fig. 57, be a beam of white light passing through a hole at H, made with a fine needle in a piece of lead or a card, and received on a screen S S'. When a hair, or a small slip of card *h h'* about the 30th of an inch in breadth, is held in the beam, the rays bend round on each side of it, and, arriving at the screen in different states of vibration, interfere and form a series of coloured fringes on each side of a central white band *m*. When a piece of card is interposed at C, so as to intercept the light which passes on one side of the hair, the coloured fringes vanish. When homogeneous light is used, the fringes are broadest in red, and become narrower for each colour of the spectrum progressively to the violet, which gives the narrowest and most crowded fringes. These very elegant experiments are due to Dr. Thomas Young.

Fig 56



Fig 57



NOTE 109 pp 202 237 Fig 58 shows Newton's rings, of which there are seven, formed by screwing two lenses of glass together Provided the incident light be white, they always succeed each other in the following order —

Fig 58



1st ring, or 1st order of colours Black, very faint blue, brilliant white, yellow, orange, red

2d ring Dark purple, or rather violet, blue, a very imperfect yellow green, vivid yellow, crimson red

3d ring Purple, blue, rich grass green, fine yellow, pink, crimson

4th ring Dull bluish green, pale yellowish pink, red

5th ring Pale bluish green, white, pink

6th ring Pale blue green, pale pink

7th ring: Very pale bluish green, very pale pink

After the seventh order, the colours became too faint to be distinguished The rings decrease in breadth, and the colours become more crowded together, as they recede from the centre When the light is homogeneous, the rings are broadest in the red, and decrease in breadth with every successive colour of the spectrum to the violet

NOTE 193, p 204 The absolute thickness of the film of air between the glasses is found as follows:—Let A F B C, fig 59, be the section of a lens lying on a plane surface or plate of glass P P', seen edgewise, and let E C be the diameter of the sphere of which the lens is a segment. If A B be the diameter of any one of Newton's rings, and B D parallel to C E, then B D or C F is the thickness of the air producing it. E C is a known quantity, and when A B the diameter is measured with compasses, B D or F C can be computed. Newton found that the length of B D, corresponding to the darkest part of the first ring, is the 98000th part of an inch when the rays fall perpendicularly on the lens, and from this he deduced the thickness corresponding to each colour in the system of rings. By passing each colour of the solar spectrum in succession over the lenses, Newton also determined the thickness of the film of air corresponding to each colour from the breadth of the rings, which are always of the same colour with the homogeneous light.

Fig 59



NOTE 194, p 206 There are seven rings, and not three, as stated in the text. Let L L', fig 60, be a lens of very short focus fixed in the window shutter of a dark room. A sunbeam S L L' passing through the lens, will be brought to a focus in F, whence it will diverge in lines F C, F D, and will form a circular image of light on the opposite wall. Suppose a sheet of lead, having a small pin hole pierced through it, to be placed in this beam; when the pin hole is viewed from behind with a lens at L, it is surrounded with a series of coloured rings, which vary in appearance with the relative positions of the pin hole and eye with regard to the point F. When the hole is the 30th of an inch in diameter and at the distance of 6½ feet from F, when viewed at the distance of 24 inches, there are seven rings of the following colours:—

1st order. White, pale yellow, yellow, orange, dull red.

2d order. Violet, blue, whitish, greenish yellow, fine yellow, orange red.

3d order. Purple, indigo blue, greenish blue, brilliant green, yellow green, red.

4th order. Good green, bluish white, red.

5th order. Dull green, faint bluish white, faint red.

Fig 60



6th order. Very faint green, very faint red.
7th order. A trace of green and red.

Fig. 61.



Note 195, p. 207. Let L L', fig. 61, be the section of a lens placed in a window shutter, through which a very small beam of light S L L' passes into a dark room, and comes to a focus in F. If the edge of a knife K N be held in the beam, the rays bend away from it in hyperbolic curves K r, K r', &c. instead of coming directly to the screen in the straight line K E, which is the boundary of the shadow. As these bending rays arrive at the screen in different states of undulation, they interfere, and form a series of coloured fringes, r r', &c. along the edge of the shadow K E S N of the knife. The fringes vary in breadth with the relative distances of the knife edge and screen from F.

Note 196, p. 210. Fig. 13 represents the phenomenon in question, where S S is the surface, and I the centre of incident waves. The reflected waves are the dark lines returning towards I, which are the same as if they had originated in C on the other side of the surface.

Fig. 62.

Note 197, p. 213. Fig. 62 represents a prismatic piece of tourmaline, whose axis is A X. The slices that are used for polarising light are cut parallel to A X.

Note 198, p. 215. *Double refraction.* If a pencil of light R r, fig. 63, falls upon a rhombohedron of Iceland spar A B X C, it is separated into two equal pencils of light at r, which are refracted in the directions r O, r E: when these arrive at O and E they are again refracted, and pass into

the air in the directions O o, E o, parallel to one another and to the incident ray R r. The ray r O is refracted according to the ordinary law, which is,

Fig 63



that the sines of the angles of incidence and refraction bear a constant ratio to one another (see Note 182), and the rays R r, r O, O o, are all in the same plane The pencil r E, on the contrary, is bent aside out of that plane, and its refraction does not follow the constant ratio of the sines r E is therefore called the extraordinary ray, and r O the ordinary ray In consequence of this bisection of the light, a spot of ink at O is seen double at O and E, when viewed from r, and when the crystal is turned round, the image E revolves about O, which remains stationary

NOTE 199 p 216 Both of the parallel rays O o and E o, fig 63, are polarised on leaving the doubly refracting crystal, and in both the particles of light make their vibrations at right angles to the lines O o, E o In the one, however, these vibrations lie, for example, in the plane of the horizon, while the vibrations of the other lie in the vertical plane perpendicular to the horizon

NOTE 200 p 217 If light be made to fall in various directions on the natural faces of a crystal of Iceland spar, or on faces cut and polished artificially, one direction A X, fig 60, will be found, along which the light passes without being separated into two pencils A X is the optic axis In some substances there are two optic axes forming an angle with each other The optic axis is not a fixed line, it only has a fixed direction; for if a crystal of Iceland spar be divided into smaller crystals, each will have its optic axis; but if all these pieces be put together again, their optic axes will be parallel to A X Every line, therefore, within the crystal parallel to A X is an optic axis, but as these lines have all the same direction, the crystal is still said to have but one optic axis

NOTE 201 p 219 If I C, fig 48, be the incident, and C S, the reflected rays, then the particles of polarised light make their vibrations at right angles to the plane of the paper

NOTE 202, p. 219. Let A B, fig 48, be the surface of the reflector, I C

the incident, and C S the reflected rays; then, when the angle S C B is 57°, and consequently the angle P C S equal to 33°, the black spot will be seen at C by an eye at S.

NOTE 203. p. 220. Let A B, fig. 48., be a reflecting surface, I C the incident, and C S the reflected rays; then, if the surface be plate glass, the angle S C B must be 57°, in order that C S may be polarised. If the surface be crown glass or water, the angle S C B must be 56° 55′ for the first, and 53° 11′ for the second, in order to give a polarised ray.

NOTE 204. p. 222. A polarising apparatus is represented in fig. 64.,

Fig. 64.



where R r is a ray of light falling on a piece of glass r at an angle of 57°. The reflected ray r s is then polarised, and may be viewed through a piece of tourmaline in s, or it may be received on another plate of glass, B, whose surface is at right angles to the surface of r. The ray r s is again reflected in s, and comes to the eye in the direction s E. The plate of mica, M I, or of any substance that is to be examined, is placed between the points r and s.

NOTE 205. p. 224. In order to see these figures, the polarised ray r s, fig. 64., must pass through the optic axis of the crystal, which must be held as near as possible to s on one side, and the eye placed as near as possible to s on the other. Fig. 65. shows the image formed by a crystal of Ice

Fig. 65.



Fig. 66.

land spar which has one optic axis The colours in the rings are exactly the same with those of Newton's rings given in Note 192, and the cross is black If the spar be turned round its axis, the rings suffer no change, but if the tourmaline through which it is viewed, or the plate of glass D, be turned round, this figure will be seen at the angles 0°, 90°, 180°, and 270° of its revolution But in the intermediate points, that is, at the angles 45°, 135°, 225°, and 315°, another system will appear, such as represented in fig 66, where all the colours of the rings are complementary to those of fig 65, and the black cross is white The two systems of rings, if superposed, would produce white light

Note 206 p 224 Saltpetre, or nitre, crystallises in six sided prisms having two optic axes inclined to one another at an angle of 5° A slice of this substance about the 6th or 8th of an inch thick, cut perpendicularly to the axis of the prism, and placed very near to *s*, fig 64, so that the polarised ray *r s* may pass through it, exhibits the system of rings represented in fig 67, where the points C and C mark the position of the optic axes When the plate D, fig 64, is turned round, the image changes

Fig 67

Fig 68



successively to those given in figs 68, 69, and 70 The colours of the rings are the same with those of thin plates, but they vary with the thickness of the nitre Their breadth enlarges or diminishes also with the colour, when homogeneous light is used.

Fig. 69

Fig. 70

NOTE 207, p. 228. Fig. 71 represents the appearance produced by placing a slice of rock crystal in the polarised ray $r\,s$, fig. 64. The uniform colour in the interior of the image depends upon the thickness of the slice; but whatever that colour may be, it will alternately attain a maximum brightness and vanish with the revolution of the glass B. It may be observed, that the two kinds of quartz, or rock crystal, mentioned in the text, are combined in the amethyst, which consists of alternate layers of right-handed and left-handed quartz, whose planes are parallel to the axis of the crystal.

Fig. 71

NOTE 208, p. 230. Suppose the major axis A P of an ellipse, fig. 81, to be invariable, but the excentricity C S continually to diminish, the ellipse would bulge more and more; and when C S vanished, it would become a circle whose diameter is A P. Again, if the excentricity were continually to increase, the ellipse would be more and more flattened till C S was equal to C P, when it would become a straight line A P. The circle and straight line are therefore the limits of the ellipse.

NOTE 209, p. 231. The coloured rings are produced by the interference of two polarised rays in different states of undulation, on the principle explained for common light.

NOTE 210, p. 264. A *mirror* is a polished metallic surface, which may be plane, convex, or concave.

NOTE 211 p 291 The class *Cryptogamia* contains the ferns, mosses, funguses, and sea weeds In all of which the parts of the flowers are either little known, or too minute to be evident

NOTE 212 p 297 *Zoophites* are the animals which form madrepores, corals, sponges, &c

NOTE 213 p 297 The *Saurian tribes* are creatures of the lizard or croco dile kind Some of those found in a fossil state are of enormous size

Fig 72



NOTE 214 p 341 When a stream of positive electricity descends from P to *n*, fig 72, in a vertical wire at right angles to the plane of the horizontal circle A B, the negative electricity as cends from *n* to P, and the force ex erted by the current makes the north pole of a magnet revolve about the wire in the direction of the arrow heads in the circumference, and it makes the south pole revolve in the opposite di rection When the current of posi tive electricity flows upwards from *n* to P, these effects are reversed

NOTE 215 p 346 Fig 73 represents a helix or coil of coppe wire, ter minated by two cups con taining a little quicksil ver When the positive wire of a Voltaic battery is immersed in the cup P, and the negative in the cup *n*, the circuit is completed The quick silver insures the connec tion between the battery and the helix, by convey ing the electricity from the one to the other While the electricity flows through the helix, the magnet S N remains suspended within it, but falls down the moment it ceases The magnet always turns its south pole S towards P the positive wire of the battery, and its north pole towards the negative wire

Fig 73



NOTE 216 p 351 A copper wire coiled in the form represented in fig 73, is an electro-dynamic cylinder When its extremities P and *n* are connected with the positive and negative poles of a Voltaic battery, it be comes a perfect magnet during the time that a current of electricity is flowing through it, P and *n* being its north and south poles There are a variety of forms of this apparatus

NOTE 217 p 404 One of the globular clusters mentioned in the text, is represented in fig 1 plate 5 The stars are gradually condensed towards the centre, where they run together into a blaze somewhat like a snowball The more condensed part is projected on a ground of irregularly scattered stars, which fills the whole field of the telescope There are few stars in the neighbourhood of this cluster

NOTE 218 p 406 Fig 2 plate 5 represents one of those enormous rings in its oblique position It has a dark space in the centre, with a small star at each extremity

NOTE 219 p 407 Fig 3 plate 5 may convey some idea of the ring in the constellation of the Lyre mentioned in the text

NOTE 220 p 407 This most wonderful object has the appearance of fig 4 plate 5 The southern head is denser than the northern The light of this object is perfectly milky There are one or two stars in it

NOTE 221 p 407 Fig 5 plate 5 represents this brother system

NOTE 222. p 408 Fig 6 plate 5 represents one of the spindle shaped nebulæ

PLATE 1







1



2

3



4

5

6

7



8



9



PLATE IX



INDEX.

C

I

M

[illegible]

W

Y

THE END.

[illegible]

Lately were published

MECHANISM of the HEAVENS By MARY SOMERVILLE With numerous Woodcuts 8vo 30s

The PRINCIPLES of GEOLOGY, with a GLOSSARY, containing an Explanation of Scientific Terms, and a copious INDEX By CHARLES LYELL, F R S, Foreign Secretary of the Geological Society A New and Cheap Edition, being the *Third*, 4 vols 12mo 24s Illustrated with 147 Woodcuts, 37 Plates and Maps

Since the publication of the former editions of this work, the Author has travelled over a large part of the Continent of Europe for the purpose of verifying facts, and collecting new materials In the present edition he has embodied all his own observations, together with a vast quantity of new facts brought to light since the first appearance of the work, which has been most materially improved by these corrections and additions, and yet the price has been reduced nearly one half Several new Illustrations have been added, and the Glossary at the end of the fourth volume will considerably assist those readers who are unacquainted with the Elements of Geology

ELEMENTS of GEOLOGY In the form of Dialogues, with numerous Illustrations of Fossil Remains Intended for the use of Students By CHARLES LYELL, F R S 1 vol 12mo

CONSOLATIONS in TRAVEL, or, the LAST DAYS of a PHILOSOPHER By Sir HUMPHRY DAVY, late President of the Royal Society In 1 vol Printed uniformly with "Salmonia" 6s

SALMONIA, or, DAYS of FLY FISHING Third Edition, with Plates and Woodcuts 12s

The JOURNAL of a NATURALIST Third Edition, post 8vo, with numerous additions and improvements, Plates, and Woodcuts, 15s

—— Plants, trees, and stones, we note,
Birds, insects, beasts, and many rural things

"It is a book that ought to find its way into every rural drawing room in the kingdom, and one that may safely be placed in every lady's boudoir, be her rank and station in life what they may" — *Quarterly Review*, No 78

CHEMICAL MANIPULATION, being Instructions to Students in Chemistry on the Methods of performing Experiments of Demonstration or of Research with accuracy and success By MICHAEL FARADAY, F R S F G S M R I 8vo 18s

A MANUAL of CHEMISTRY, Practical and Theoretical; containing an Account of all recent Investigations and Discoveries By W T BRANDE, F R S, Professor of Chemistry at the Royal Institution, &c Compressed into 2 vols 8vo., only 30s *Third Edition*, considerably enlarged and improved, with numerous Plates, Woodcuts, Diagrams, &c

TABLES in Illustration of the THEORY of DEFINITE PROPORTIONALS, showing the Prime Equivalent Numbers of the Elementary Substances, and the Volumes and Weights in which they combine, compiled for the Use of Chemical Students and Manufacturers By W T BRANDE, F R S 8vo 8s 6d

OUTLINES of GEOLOGY, being the Substance of a Course of Lectures delivered in the Theatre of the Royal Institution, by W T BRANDE, F R S Second Edition, post 8vo 7s 6d

In the Press,

GEOLOGY of the COUNTIES of SALOP, HEREFORD, RADNOR, MONTGOMERY, BRECKNOCK, CAERMARTHEN, MONMOUTH, WORCESTER, and GLOUCESTER, with large Geological Maps, numerous Coloured Sections, and many Plates of unpublished Organic Remains By RODERICK IMPEY MURCHISON, F R S, Vice President of the Geological and Royal Geographical Societies, F L S, &c &c